LUMINAIRE SCHEDULE

LUMINAIRE NUMBER	LIGHTING PLAN SHEET	SURVEY LINE	STATION NUMBER	OFFSET FROM CENTERLINE	POLE DATA**	LAMP WATTAGE AND TYPE	IES PATTERN	POLE DETAIL	DETAIL SHEET	LUMINAIRE NUMBER
S-01	25-006	SPRING ST	12+12	28.9 LT	30' STEEL POLE	400 HPS	TYPE IV	A	25-016	S-01
S-02	25-006	SPRING ST	12+73	28.9 LT	30' STEEL POLE	400 HPS	TYPE IV	A	25-016	S-02
S-03	25-006	SPRING ST	13+33	28.9 LT	30' STEEL POLE	400 HPS	TYPE IV	A	25-016	S-03
S-04	25-006	SPRING ST	13+93	28.9 LT	30' STEEL POLE	400 HPS	TYPE IV	A	25-016	S-04
S-05 (HEAD 1)	25-006	SPRING ST	14+61	34.6 LT	30' STEEL POLE	400 HPS	TYPE IV	B	25-016	S-05 (HEAD 1)
S-05 (HEAD 2)	25-006	SPRING ST	14+61	34.6 LT	30' STEEL POLE	400 HPS	TYPE IV	B	25-016	S-05 (HEAD 2)
S-06 (HEAD 1)	25-006	UPPER MLK JR DR	10+90	35.5 RT	30' STEEL POLE	400 HPS	TYPE IV	C	25-017	S-06 (HEAD 1)
S-06 (HEAD 2)	25-006	UPPER MLK JR DR	10+90	35.5 RT	30' STEEL POLE	100 HPS	TYPE II	C	25-017	S-06 (HEAD 2)
S-07 (HEAD 1)	25-010	UPPER MLK JR DR	11+55	35.5 RT	30' STEEL POLE	400 HPS	TYPE IV	C	25-017	S-07 (HEAD 1)
S-07 (HEAD 2)	25-010	UPPER MLK JR DR	11+55	35.5 RT	30' STEEL POLE	100 HPS	TYPE II	C	25-017	S-07 (HEAD 2)
S-08 (HEAD 1)	25-010	UPPER MLK JR DR	12+20	35.5 RT	30' STEEL POLE	400 HPS	TYPE IV	C	25-017	S-08 (HEAD 1)
S-08 (HEAD 2)	25-010	UPPER MLK JR DR	12+20	35.5 RT	30' STEEL POLE	100 HPS	TYPE II	C	25-017	S-08 (HEAD 2)
S-09 (HEAD 1)	25-010	UPPER MLK JR DR	12+84	35.5 RT	30' STEEL POLE	400 HPS	TYPE IV	C	25-017	S-09 (HEAD 1)
S-09 (HEAD 2)	25-010	UPPER MLK JR DR	12+84	35.5 RT	30' STEEL POLE	100 HPS	TYPE II	C	25-017	S-09 (HEAD 2)
S-10 (HEAD 1)	25-010	UPPER MLK JR DR	13+49	35.5 RT	38' STEEL POLE	400 HPS	TYPE IV	D	25-017	S-10 (HEAD 1)
S-10 (HEAD 2)	25-010	UPPER MLK JR DR	13+49	35.5 RT	38' STEEL POLE	100 HPS	TYPE II	D	25-017	S-10 (HEAD 2)
S-11 (HEAD 1)	25-010	UPPER MLK JR DR	14+14	35.5 RT	33' STEEL POLE	400 HPS	TYPE IV	D	25-017	S-11 (HEAD 1)
S-11 (HEAD 2)	25-010	UPPER MLK JR DR	14+14	35.5 RT	33' STEEL POLE	100 HPS	TYPE II	D	25-017	S-11 (HEAD 2)
S-12 (HEAD 1)	25-007	SPRING ST	15+62	40.4 LT	30' STEEL POLE	400 HPS	TYPE IV	E	25-018	S-12 (HEAD 1)
S-12 (HEAD 2)	25-007	SPRING ST	15+62	40.4 LT	30' STEEL POLE	400 HPS	TYPE IV	E	25-018	S-12 (HEAD 2)
S-13 (HEAD 1)	25-007	SPRING ST	16+31	40.4 LT	30' STEEL POLE	400 HPS	TYPE IV	E	25-018	S-13 (HEAD 1)
S-13 (HEAD 2)	25-007	SPRING ST	16+31	40.4 LT	30' STEEL POLE	400 HPS	TYPE IV	E	25-018	S-13 (HEAD 2)
S-14 (HEAD 1)	25-007	SPRING ST	17+31	40.4 LT	30' STEEL POLE	400 HPS	TYPE IV	E	25-018	S-14 (HEAD 1)
S-14 (HEAD 2)	25-007	SPRING ST	17+31	40.4 LT	30' STEEL POLE	400 HPS	TYPE IV	E	25-018	S-14 (HEAD 2)
S-15 (HEAD 1)	25-007	SPRING ST	18+31	40.4 LT	30' STEEL POLE	400 HPS	TYPE IV	E	25-018	S-15 (HEAD 1)
S-15 (HEAD 2)	25-007	SPRING ST	18+31	40.4 LT	30' STEEL POLE	400 HPS	TYPE IV	E	25-018	S-15 (HEAD 2)
S-16	25-007	SPRING ST	19+00	40.4 LT	30' STEEL POLE	400 HPS	TYPE IV	G	25-019	S-16
S-17	25-007	SPRING ST	19+63	32.4 RT	30' STEEL POLE	400 HPS	TYPE IV	G	25-019	S-17
S-18	25-007	SPRING ST	20+25	40.2 LT	30' STEEL POLE	400 HPS	TYPE IV	G	25-019	S-18
S-19	25-007	SPRING ST	20+88	32.5 RT	30' STEEL POLE	400 HPS	TYPE IV	G	25-019	S-19
S-20	25-008	SPRING ST	21+66	32.5 LT	30' STEEL POLE	400 HPS	TYPE IV	H	25-019	S-20
S-21	25-008	SPRING ST	22+57	32.5 RT	30' STEEL POLE	400 HPS	TYPE IV	G	25-019	S-21
S-22	25-008	SPRING ST	23+05	32.5 LT	30' STEEL POLE	400 HPS	TYPE IV	H	25-019	S-22
S-23	25-008	SPRING ST	24+22	32.5 RT	30' STEEL POLE	400 HPS	TYPE IV	G	25-019	S-23
S-24	25-008	SPRING ST	24+57	32.5 LT	30' STEEL POLE	400 HPS	TYPE IV	H	25-019	S-24
S-25	25-008	SPRING ST	25+47	29.0 LT	30' STEEL POLE	400 HPS	TYPE IV	F	25-018	S-25
S-26	25-009	SPRING ST	26+42	32.5 RT	30' STEEL POLE	400 HPS	TYPE IV	G	25-019	S-26
S-27	25-009	SPRING ST	27+02	32.9 LT	30' STEEL POLE	400 HPS	TYPE IV	G	25-019	S-27
S-28	25-009	SPRING ST	27+72	30.8 LT	30' STEEL POLE	400 HPS	TYPE IV	A	25-016	S-28
P-01 THROUGH P-12	25-011	MOUNTED TO BRIDGE STRUCTURE				175 MH	N/A	N/A	25-020	P-01 THROUGH P-12
W-01 THROUGH W-08	25-011	MOUNTED TO BRIDGE STRUCTURE				150 HPS	TYPE IV	N/A	25-021	W-01 THROUGH W-08
W-36 THROUGH W-40	25-011	MOUNTED TO BRIDGE STRUCTURE				150 HPS	TYPE IV	N/A	25-022	W-36 THROUGH W-40
W-41 THROUGH W-43	25-014	MOUNTED TO BRIDGE STRUCTURE				150 HPS	TYPE IV	N/A	25-022	W-41 THROUGH W-43
W-09 THROUGH W-28	25-012	MOUNTED TO BRIDGE STRUCTURE				150 HPS	TYPE IV	N/A	25-021	W-09 THROUGH W-28
W-29 THROUGH W-35	25-012	MOUNTED TO BRIDGE STRUCTURE				250 MH	TYPE IV	N/A	25-021	W-29 THROUGH W-35
P-13 THROUGH P-15	25-012	MOUNTED TO BRIDGE STRUCTURE				250 MH	N/A	N/A	25-020	P-13 THROUGH P-15
P-16 THROUGH P-27	25-013	MOUNTED TO BRIDGE STRUCTURE				250 MH	N/A	N/A	25-020	P-16 THROUGH P-27

**NOTE: POLE HEIGHTS SHOWN ARE APPROXIMATE. VERIFY ACTUAL POLE HEIGHT REQUIRED TO PROVIDE LUMINAIRE MOUNTING HEIGHTS ABOVE STREET LEVEL AS SHOWN ON POLE DETAIL SHEETS.