STATE PROJECT NUMBER SHEET N

GA BHNLB-9073-00(016), BRNLB-9073-00(018) 12 SHEET NO. TOTAL SHEETS j:\20||044\752086\dgn\752086qn0|.dgn USER:gcunningham _PENTBLL_

Heath & Lineback Engineers
INCORPORATED
2390 CANTON ROAD, BUILDING 200
MARIETTA, GEORGIA 30066-5393

SUMMARY OF QUANTITIES -SIGNAL

LIST OF MATERIALS	UNIT	QUANTITY
CONTROLLER CABINET ASSEMBLIES		
A. CONTROLLER UNIT, MODEL 2070L	EA	1
D. CABINET ASSEMBLY, MODEL 332A	EA	1
E. SWITCH PACK	EA	8
F. DC ISOLATOR	EA	3
G. LOOP DETECTOR, 2 CHANNEL	EA	4
J. 2010 CONFLICT MONITOR, EXTENDED FEATURES	EA	1
332A PREFABRICATED CONTROLLER CABINET BASE	EA	1
LOOP/PED LEAD-IN WIRE (SHIELDED, TWISTED/1000 FT); 3 PAIR, 18 AWG	REEL	1
SIGNAL CABLE (14 AWG); 7 CONDUCTOR, PER 1000 FT.	REEL	1
LOOP DETECTOR WIRE (14 AWG, STRANDED/1000 FT)	REEL	1
3-SECTION, 12" SIGNAL HEAD w/(5mm) LED - "INCANDESCENT LOOK" - , PLASTIC	EA	3
4-SECTION, 12" SIGNAL HEAD w/ (5mm) LED - "INCANDESCENT LOOK" - SIGNAL HEAD, PLASTIC	EA	1
5-SECTION, 12" SIGNAL HEAD w/(5mm) LED - "INCANDESCENT LOOK" - SIGNAL HEAD (CLUSTER), PLASTIC	EA	2
I-SECTION, 18" LED COUNTDOWN PEDESTRIAN SIGNAL HEAD, FULL HAND/MAN OVERLAP		
9" HIGH, Numbers & 12" Symbols	EA	8
PEDESTRIAN PUSHBUTTON STATION ADAPTERS (ONLY)		
9" x 15", Double Push Button Station Adapter for 4" Dia Pedestrian Pole, Adjustable	EA	4
PEDESTRIAN PUSHBUTTONS STATIONS, w/BUTTONS and SIGNS:		
9" x 15", R10-3e, 1L1eft or 1R1ight, Countdown	EA	8
BACK PLATE FOR ONE-WAY, 3-SECTION, 12" SIGNAL HEAD, ABS PLASTIC, BLACK	EA	3
BACK PLATE FOR ONE-WAY, 4-SECTION, 12" SIGNAL HEAD, ABS PLASTIC, BLACK	EA	1
BACK PLATE FOR ONE-WAY, 5-SECTION, CLUSTERED 12" SIGNAL HEAD, ABS PLASTIC, BLACK	EA	2
HARDWARE FOR MAST ARM MOUNTING	EA	6
HARDWARE FOR PEDESTAL POLE, TOP POST MOUNTING, TWO-WAY BRACKET ASSEMBLY	EA	1
HARDWARE FOR SIDE-OF-POLE MOUNTING, ONE-WAY BRACKET ASSEMBLY; CONCRETE, TIMBER, STEEL POLE	EA	6
PEDESTAL POLE & SQUARE BASE	EA	1
PULL BOX, PB-2	EA	4
PULL BOX, PB-3	EA	
LOOP SAW CUT	LF	850
CONDUIT, I"	LF	145
CONDUIT, 2"	LF	150
PED PUSH BUTTON POST/INCL FOOTING	EA	2
MISCELLANEOUS MATERIALS NEEDED TO COMPLETE INSTALLATION	LUMP	LUMP

PAY ITEMS	DESCRIPTION	UNITS	TOTAL
639-2001	STEEL WIRE STRAND CABLE, '4IN	LF	245
639-3004	STRAIN POLE, TPYE IV, WITH 35' MASTARM	EA	1
647-1000	TRAFFIC SIGNAL INSTALLATION - NO. 1	LS	1
682-6233	NONMETAL CONDUIT, 2", TYPE 3	EA	230

SIGNAL	N	0.	1		
LOCATION				S STRE 5+62.	

REVISION DATA						
	DEPARTMENT OF TRANSPORT	DEPARTMENT OF TRANSPORTATION				
	OFFICE: PROGRAM DELIVERY					
	SUMMARY QUANTITIE	SUMMARY QUANTITIES				
	SIGNAL					
	SPRING STREET	DRAWING No.				
	VIADUCT OVER CSXT	0-004				