SUMMARY OF QUANTITIES - STANDARD SIGNS

STATION	INSTL. NO.	HIGHWAY SIGNS													SQUARE TUBE POST									BREAKAWAY SIGN SUPPORT (EACH)
		SIGN CODE	TP 1 MATL, REFL SHEETING TP 3			TP 2 MATL, REFL SHEETING TP 3			TP 1 MATL, REFL SHEETING TP 9			TP 2 MATL, REFL SHEETING TP 9			TYPE 7			TYPE 8			TYPE 9			
			SIZE	QUANTITY	SQUARE FEET	SIZE	QUANTITY	SQUARE FEET	SIZE	QUANTITY	SQUARE FEET	SIZE	QUANTITY	SQUARE FEET	LENGTH (FEET)	QUANTITY	TOTAL LENGTH	LENGTH (FEET)	QUANTITY	TOTAL LENGTH	LENGTH (FEET)	QUANTITY	TOTAL LENGTH	
US 41/COBB PKWY																								
9+65	1	R4-7	24" X 30"	1	5.00										13.00	1	13.00							
10+70	2	D10-1	12" X 24"	1	3.00										13.00	1	13.00							
10+80	3	M3-2	24" X 12"	1	3.00																15.00	1	15.00	
		M1-5	24" X 24"	1	4.00																			
		M5-1R	21" X 15"	1	2.50																			
		M4-5	24" X 12"	1	3.00																15.00	1	15.00	
		M3-1	24" X 12"	1	3.00																			
		M1-5	24" X 24"	1	4.00																			
		M6-3	21" X 15"	1	2.50																			
11+10	4	R6-2R	24" X 30"	1	5.00										13.00	1	13.00							
12+50	5	D9-2	24" X 24"	1	4.00										14.00	1	14.00							
		M6-1	21" X 15"	1	2.50																			
13+90	6	R6-2R	24" X 30"	1	5.00										13.00	1	13.00							
15+50	7	M3-3	24" X 12"	1	3.00																15.00	1	15.00	
		M1-4	24" X 24"	1	4.00																			
		M1-5	24" X 24"	1	4.00																			
15+80	8	R5-1A							36" X 24"	1	6.00				13.00	1	13.00							
16+80	9	R5-1							30" X 30"	1	6.25				13.00	1	13.00							
17+00	10	R560-5	18" X 24"	1	3.00										13.00	1	13.00							
19+05	11	R5-1							30" X 30"	1	6.25				13.00	1	13.00							
19+25	12	R560-5	18" X 24"	1	3.00										13.00	1	13.00							
19+35	13	R6-2R	24" X 30"	1	5.00										13.00	1	13.00							
20+20	14	M3-1	24" X 12"	1	3.00																15.00	1	15.00	
		M1-4	24" X 24"	1	4.00																			
		M1-5	24" X 24"	1	4.00																			
21+15	15	R5-1A							36" X 24"	1	6.00				13.00	1	13.00							
21+35	16	R6-2R	24" X 30"	1	5.00										13.00	1	13.00							
23+00	17	D9-2	24" X 24"	1	4.00										14.00	1	14.00							
		M6-1	21" X 15"	1	2.50																			
23+55	18	MB4-5	24" X 12"	1	3.00										13.00	1	13.00							
		MB1-1 (75)	24" X 24"	1	4.00																			
		MB1-1 (575)	30" X 24"	1	5.00																			
		MB6-1R	21" X 15"	1	2.50																			
		M4-5	24" X 12"	1	3.00										13.00	1	13.00							
		M3-1	24" X 12"	1	3.00																			
		M1-5 (5)	24" X 24"	1	4.00																			
		M6-1R	21" X 15"	1	2.50																			
23+95	19	R2-1 (45)	24" X 30"	1	5.00										13.00	1	13.00							
25+20	20	R3-7	30" X 30"	1	6.25										13.00	1	13.00							
29+69	21	R560-5	18" X 24"	1	3.00																			
29+70	22	M3-3	24" X 12"	1	3.00																15.00	1	15.00	
		M1-4 (41)	24" X 24"	1	4.00																			
		M1-5 (3)	24" X 24"	1	4.00																			
30+30	23	R1-2							36" TRI	1	3.90				14.00	1	14.00							
31+15	24	R5-1							30" X 30"	1	6.25				13.00	1	13.00							
															a									
SUB SHEET 1					143.25						34.65						263						75	

ARCADIS
Infrastructure, environment, facilities

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION

SUMMARY QUANTITIES

CANTON ROAD AND RR
BRIDGE OVER SR 3/US 41

DRAWING No.
6-08