VOID

SUMMARY OF DRAINAGE QUANTITIES

STRUCTURE NUMBER	LOCATION	DROP INLET, GP 1	CATCH BASIN, GP 1	JUNCTION BOX	MANHOLE	RECONSTRUCT CATCH BASIN, GROUP 1	RECONSTRUCT CATCH BASIN, GROUP 2	ADDITIONAL DEPTH, CATCH BASIN, GP 1	ADDITIONAL DEPTH, DROP INLET, GP 1	CLASS A CONCRETE, INCL REINF STEEL TO CONSTRUCT 24"OUTLET HEADWALL GA. STD. 1125	CLASS A CONCRETE, INCL REINF STEEL TO CONSTRUCT 30"OUTLET HEADWALL GA. STD. 1125	CLASS A CONCRETE, INCL REINF STEEL TO CONSTRUCT 36"OUTLET HEADWALL GA. STD. 1125	STORM DRAIN PIPE (H 1-10) 18"	STORM DRAIN PIPE (H 1-10) 24"	STORM DRAIN PIPE (H 1-10) 30"	STORM DRAIN PIPE (H 1-10) 36"	STORM DRAIN PIPE (H 1-10) 48"	TYPE 3 12" STONE DUMPED RIP-RAP 12"	PLASTIC FILTER FABRIC
STRUCTURE	STATION	EA	EA	EA	EA	EA	EA	LF	LF	CY	CY	CY	LF	LF	LF	LF	LF	SY	SY
	SR 961																		
C-1	14+00 RT		1										258						
C-2	16+58 RT		1					4											
C-3	19+50 RT		1										450						
C-4	24+00 RT		1										122						
C-5	25+22 RT		Existing			1		3						22					
C-6	25+26 RT									2								8	8
B-1	28+00 RT		1					1					36						
B-2	28+36 RT		Existing			1		2								26			
B-3	28+36 RT											4						6	6
A-1	35+13 RT		Existing			1							300						
A-2	32+12 RT		Existing			1							212						
A-3	30+00 RT		1											98					
A-4	29+02 RT		1					1						31					
A-5	29+02 RT									2								4	4
D-1	12+50 LT		1										150						
D-2	14+00 LT		1										195						
D-3	4+20 LT (BUICE RD)		1										73						
D-4	15+95 LT		1										58						
D-5 TO C-2	16+53 LT		1					2					72						
D-6	18+00 LT		1										268						
D-7	20+68 LT		1										222						
D-8	22+90 LT		1											60					
D-9	23+50 LT		1											98					
D-10	24+48 LT		1											202					
D-11	26+50 LT		1												100				
D-12	27+50 LT		1												50				
D-13	28+00 LT		1												58				
D-14 TO B-2	28+58 LT		1					1								74			
D-15	29+30 LT		1											120					
D-16	30+50 LT		1										100						
D-17	31+50 LT		1										250						
D-18	34+00 LT		1																
D-15 TO A-4	29+30 LT													74					
SUB-TOTAL #1		0	25	0	0	4	0	14	0	4	0	4	2766	705	208	100	0	18	18

NOTE: STATIONING IS APPROXIMATE, EXACT STATIONS TO BE DETERMINED BY THE PROJECT ENGINEER DURING CONSTRUCTION

SUMMARY OF DRAINAGE QUANTITIES

STRUCTURE NUMBER	LOCATION	DROP INLET, GP 1	CATCH BASIN, GP 1	JUNCTION BOX	MANHOLE	RECONSTRUCT CATCH BASIN, GROUP 1	RECONSTRUCT CATCH BASIN, GROUP 2	ADDITIONAL DEPTH, CATCH BASIN, GP 1	ADDITIONAL DEPTH, DROP INLET, GP 1	CLASS A CONCRETE, INCL REINF STEEL TO CONSTRUCT 24"OUTLET HEADWALL GA. STD. 1125	CLASS A CONCRETE, INCL REINF STEEL TO CONSTRUCT 30"OUTLET HEADWALL GA. STD. 1125	CLASS A CONCRETE, INCL REINF STEEL TO CONSTRUCT 36"OUTLET HEADWALL GA. STD. 1125	STORM DRAIN PIPE (H 1-10) 18"	STORM DRAIN PIPE (H 1-10) 24"	STORM DRAIN PIPE (H 1-10) 30"	STORM DRAIN PIPE (H 1-10) 36"	STORM DRAIN PIPE (H 1-10) 48"	TYPE 3 12" STONE DUMPED RIP-RAP 12"	PLASTIC FILTER FABRIC
	STATION	EA	EA	EA	EA	EA	EA	LF	LF	CY	CY	CY	LF	LF	LF	LF	LF	SY	SY
	SR 961																		
F-1	29+03 LT	1							2										
F-2	28+98 RT	Existing					1											4	4
G-1	25+82.20 111.70 LT EXISTING MH	Existing																	
G-2	25+63.18 106.70 LT EXISTING SWCB		Existing																
G-7	25+91.66 63.63 LT			1				3									4		
G-8	26+04.78 63.89 LT				1												68		
G-9	26+73.73 66.29 LT			1				4											
	SR 141																		
E-1	116+66 IN MEDIAN		1										39						
E-2	116+27 IN MEDIAN		Existing	1															
SUB-TOTAL #1		0	25	0	0	4	0	14	0	4	0	4	2766	705	208	100	0	18	18
SUB-TOTAL #2		1	1	3	1	0	1	7	2	0	0	0	25	0	0	0	72	4	4
TOTALS		1	26	3	1	4	1	21	2	4	0	4	2805	705	208	100	72	22	22

EROSION CONTROL

TEMPORARY																	PERMANENT					
WATER QUALITY MONITORING AND SAMPLING	WATER QUALITY INSPECTIONS	CONSTR & REM RIP RAP CHECK DAMS, STONE PLAIN RIP RAP/SAND BAGS (AS DIRECTED BY ENGINEER)	MAINT OF CHECK DAMS-ALL TYPES (AS DIRECTED BY ENGINEER)	CONSTR & REMOVE ROCK FILTER DAMS(AS DIRECTED BY ENGINEER)	MAINT OF ROCK FILTER DAM (AS DIRECTED BY ENGINEER)	CONSTR/REM TEMP SEDIMENT BARRIER OR BALED STRAW CHECK DAM (AS DIRECTED BY ENGINEER)	MAINT OF SEDIMENT BARRIER - BALED STRAW CHECK DAM (AS DIRECTED BY ENGINEER)	CONSTR & REM TEMP PIPE SLOPE DRAIN (AS DIRECTED BY ENGINEER)	INLET SEDIMENT TRAP	MAINTENANCE OF INLET SEDIMENT TRAP	CONSTRUCTION EXIT	MAINTENANCE OF CONSTRUCTION EXIT	TEMPORARY SILT FENCE, TYPE C	MAINTENANCE OF TEMPORARY SILT FENCE, TYPE C	TEMPORARY GRASS	MULCH	EROSION CONTROL MATS, SLOPES	AGRICULTURAL LIME	FERTILIZER MIXED GRADE	FERTILIZER NITROGEN CONTENT	PERMANENT GRASSING	SOD
EA	MO	EA	LF	EA	EA	LF	LF	LF	EA	EA	EA	EA	LF	LF	AC	TN	SY	TN	TN	LBS	AC	SY
2	18	5	50	5	5	60	30	200	32	32	2	2	9200	4600	2	120	850	4	1	800	2	3698

GEORGIA
DEPARTMENT OF TRANSPORTATION

REVISION DATES
9/22/14

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: DISTRICT 7 PRECONSTRUCTION

SUMMARY QUANTITIES

OLD ALABAMA RD/961

DRAWING No. 6-02

GPLN