# SUMMARY OF QUANTITIES-STANDARD SIGNS

| STATION | INSTL. NO. | CODE | SIGNS (TYPE III REFLECTIVE SHEETING) TYPE 1 (0.08) SIZE | QTY | SQUARE FEET | TYPE 2 (0.10) SIZE | QTY | SQUARE FEET | (TYPE IX REFLECTIVE SHEETING) TYPE 1 (0.08) SIZE | QTY | SQUARE FEET | (TYPE II REFLECTIVE SHEETING) TYPE 1 (0.08) SIZE | QTY | SQUARE FEET | SQUARE TUBE POST TYPE 7 LENGTH (FEET) | QTY | TOTAL LENGTH | TYPE 8 LENGTH (FEET) | QTY | TOTAL LENGTH | TYPE 9 LENGTH (FEET) | QTY | TOTAL LENGTH | BREAKAWAY SIGN SUPPORT EACH |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| SR96/OLD ALABAMA | | | | | | | | | | | | | | | | | | | | | | | | |
| 10+25R | 1 | W3-3 | | | | | | | 36X36 | 1 | 9 | | | | 15 | 1 | 15 | | | | | | | |
| | | W16-8 | | | | | | | 36X8 | 1 | 2 | | | | | | | | | | | | | |
| 15+51L | 2 | R5-1(36) | | | | | | | | | | 36X36 | 1 | 9 | 15 | 1 | 15 | | | | | | | |
| 15+90 | 3 | R4-7 | 24X30 | 1 | 5 | | | | | | | | | | 15 | 1 | 15 | | | | | | | |
| | | R3-4 | 30X30 | 1 | 7 | | | | | | | | | | | | | | | | | | | |
| 18+16L | 4 | R3-7R(36) | 36X36 | 1 | 9 | | | | | | | | | | 15 | 1 | 15 | | | | | | | |
| 19+25L | 5 | W3-3 | | | | | | | 36X36 | 1 | 9 | | | | 15 | 1 | 15 | | | | | | | |
| | | W16-8 | | | | | | | 36X8 | 1 | 2 | | | | | | | | | | | | | |
| 20+75L | 6 | R1-2(36) | | | | | | | | | | 36X36X36 | 1 | 5 | 15 | 1 | 15 | | | | | | | |
| 21+13 | 7 | R4-7 | 24X30 | 1 | 5 | | | | | | | | | | 15 | 1 | 15 | | | | | | | |
| | | R3-4 | 30X30 | 1 | 7 | | | | | | | | | | | | | | | | | | | |
| 21+27L | 8 | R1-1 | | | | | | | | | | 36X36 | 1 | 9 | 15 | 1 | 15 | | | | | | | |
| 22+16 | 9 | R4-7 | 24X30 | 1 | 5 | | | | | | | | | | 15 | 1 | 15 | | | | | | | |
| | | R3-4 | 30X30 | 1 | 7 | | | | | | | | | | | | | | | | | | | |
| 22+16L | 10 | R1-2(36) | | | | | | | | | | 36X36X36 | 1 | 5 | 15 | 1 | 15 | | | | | | | |
| 29+29 | 11 | R3-4 | 30X30 | 1 | 7 | | | | | | | | | | 15 | 1 | 15 | | | | | | | |
| 30+10 | 12 | R3-4 | 30X30 | 1 | 7 | | | | | | | | | | 15 | 1 | 15 | | | | | | | |
| 33+29 | 13 | R3-5L | 30X36 | 2 | 16 | | | | | | | | | | | | | | | | | | | |
| OVERHEAD | | R3-5R | 30X36 | 1 | 8 | | | | | | | | | | | | | | | | | | | |
| | | GS24 | 30X36 | 1 | 8 | | | | | | | | | | | | | | | | | | | |
| | | GN24 | 30X36 | 1 | 8 | | | | | | | | | | | | | | | | | | | |
| 35+50R | 14 | M2-1 | 21X15 | 1 | 3 | | | | | | | | | | 15 | 1 | 15 | | | | | | | |
| | | M1-5 | 30X24 | 1 | 5 | | | | | | | | | | | | | | | | | | | |
| 36+00 | 15 | R2-1 | 36X48 | 1 | 12 | | | | | | | | | | 15 | 1 | 15 | | | | | | | |
| 37+03R | 16 | R5-1(36) | | | | | | | | | | 36X36 | 1 | 9 | 15 | 1 | 15 | | | | | | | |
| 37+08 | 17 | R4-7 | 24X30 | 1 | 5 | | | | | | | | | | 15 | 1 | 15 | | | | | | | |
| | | R3-4 | 30X30 | 1 | 7 | | | | | | | | | | | | | | | | | | | |
| 37+28R | 18 | R1-2(36) | | | | | | | | | | 36X36X36 | 1 | 5 | 15 | 1 | 15 | | | | | | | |
| | 19 | D3-1 *4 | | | | 96X24 | 1 | 16 | | | | | | | | | | | | | | | | |
| | 20 | D3-1 *5 | | | | 78X24 | 1 | 13 | | | | | | | | | | | | | | | | |
| | 21 | D3-1 *6 | | | | 78X24 | 1 | 13 | | | | | | | | | | | | | | | | |
| SR141/ MEDLOCK BRIDGE RD | | | | | | | | | | | | | | | | | | | | | | | | |
| 106+35R | 22 | W16-1 | | | | | | | 24X30 | 1 | 5 | | | | 15 | 1 | 15 | | | | | | | |
| | | W11-1 | | | | | | | 30X30 | 1 | 7 | | | | | | | | | | | | | |
| 110+35R | 23 | W16-1 | | | | | | | 24X30 | 1 | 5 | | | | 15 | 1 | 15 | | | | | | | |
| | | W11-1 | | | | | | | 30X30 | 1 | 7 | | | | | | | | | | | | | |
| 110+50 | 24 | R3-5L | 30X36 | 2 | 16 | | | | | | | | | | | | | | | | | | | |
| OVERHEAD | | R3-5A | 30X36 | 2 | 16 | | | | | | | | | | | | | | | | | | | |
| 114+50R | 25 | W16-1 | | | | | | | 24X30 | 1 | 5 | | | | 15 | 1 | 15 | | | | | | | |
| | | W11-1 | | | | | | | 30X30 | 1 | 7 | | | | | | | | | | | | | |
| | 26 | D3-1 *1 | | | | 108X24 | 1 | 18 | | | | | | | | | | | | | | | | |
| | 27 | D3-1 *2 | | | | 108X24 | 1 | 18 | | | | | | | | | | | | | | | | |
| | 28 | D3-1 *3 | | | | 108X24 | 1 | 18 | | | | | | | | | | | | | | | | |
| BUICE RD | | | | | | | | | | | | | | | | | | | | | | | | |
| 4+73L | 29 | R3-7R(36) | 36X36 | 1 | 9 | | | | | | | | | | 15 | 1 | 15 | | | | | | | |
| 6+75L | 30 | W3-3 | | | | | | | 36X36 | 1 | 9 | | | | 15 | 1 | 15 | | | | | | | |
| | | W16-8 | | | | | | | 36X8 | 1 | 2 | | | | | | | | | | | | | |
| TOTALS | | | | 24 | 172 | | 6 | 96 | | 12 | 69 | | 6 | 42 | | 22 | 330 | | | | | | | |

GEORGIA DEPARTMENT OF TRANSPORTATION

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: DISTRICT 7 PRECONSTRUCTION

SUMMARY QUANTITIES

OLD ALABAMA AT SR 141

DRAWING No. 6-04

9/10/2014 USER:dirobbins 4:35:26 PM

layer:Sign gdotborder-V8I-PD.101

S:\752660\Ref-fpn\fpn\062610NK4.fpn

STATE GA

PROJECT NUMBER STP00-2868-00(001)

SHEET NO. 13

TOTAL SHEETS 238

VOID