

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	HPP-9014(25)	4	140
REVISION DATES			
7/05/05			

GENERAL NOTES



TYPE OF PIPE MATERIAL	C O N D I T I O N S	CORRUGATED STEEL A152/A153		CORRUGATED ALUMINUM A136		PLASTIC				
		ALUMINUM COATED TYPE 30 CORN. STEEL	PLAIN ZINC COATED	PLAIN UNPAINTED ALUMINUM	CORR. POLY-ETHYLENE AHD/HT A136	CORR. POLY-ETHYLENE SANDWICH LINED AHD/HT A136	POLY VINYL CHLORIDE (PVC) PROFILE AHD/HT A136	POLY VINYL CHLORIDE (PVC) PROFILE AHD/HT A136	POLY VINYL CHLORIDE (PVC) PROFILE AHD/HT A136	
CONDUIT		X								
INTERSTATE AND TRAVEL BELT		X								
INTERSTATE AND NON-TRAVEL BELT		X	X		X		X	X		
SIDE DRAIN	ADP < 250	X	X		X		X	X		
	250 < ADP < 1000	X	X		X					
	ADP > 1000	X								
PERMANENT SLOPE DRAIN	ADP < 250		X		X		X	X		
	ADP > 250				X					
PERFORATED UNDERDRAIN		X	X	X	X	X	X			

NOTE:
 1. ALLOWABLE MATERIALS ARE INDICATED BY AN "X".
 2. STRUCTURAL REQUIREMENTS OF STORM DRAIN PIPE WILL BE IN ACCORDANCE WITH GEORGIA STANDARD 1000-D OR 1000-H, WHICHEVER IS APPLICABLE, AND THE STANDARD SPECIFICATION.
 3. THE CONTRACTOR SHALL PROVIDE ADDITIONAL STORM SEWER CAPACITY CALCULATIONS IF A PIPE MATERIAL OTHER THAN CONCRETE IS SELECTED.

DRIVEWAY RECONSTRUCTION MATERIALS

ALL DRIVES THAT ARE TO BE RECONSTRUCTED SHALL BE REPLACED IN KIND I.E. ASPHALT FOR ASPHALT, CONCRETE FOR CONCRETE, AND AGGREGATE SURFACE COURSE FOR EARTH. WHERE REQUIRED, DRIVES SHALL BE CONSTRUCTED AS FOLLOWS, UNLESS OTHERWISE NOTED ON THE DRIVEWAY SUMMARY:

ASPHALT DRIVES ----- RESIDENTIAL: 165 LBS./SQ. YD. ASPH. CONC., 12.5 mm SUPERPAVE
 6" GRADED AGGREGATE BASE

COMMERCIAL: 165 LBS./SQ. YD. ASPH. CONC., 12.5 mm SUPERPAVE
 220 LBS./SQ. YD. ASPH. CONC., 19 mm SUPERPAVE
 6" GRADED AGGREGATE BASE

CONCRETE DRIVES ----- RESIDENTIAL: 6" DRIVEWAY CONCRETE
 COMMERCIAL: 8" DRIVEWAY CONCRETE

PROJECT NOTES

1. This project will require a Notice of Intent (NOI).
2. All milled areas shall be re-paved the same day.
3. Dekalb Water and Sewer to coordinate with contractor during construction to relocate their facilities.
4. All water meters will be relocated by Dekalb Water and Sewer.
5. Poles and mast arms shall be hot dipped galvanized to ASTM A123 standards and finished with a painted exterior. All exteriors shall be primed and finished. Approved paint color is black. Finish coat shall be TGIC or urethane polyester powder. Cost to paint shall be included in installation cost.

NAME OF UTILITY	SERVICE	PHONE #'s
GEORGIA POWER COMPANY	ELECTRICAL	(404) 506-6526
ATLANTA GAS LIGHT COMPANY	GAS	(770) 907-4231
DEKALB COUNTY WATER AND SEWER	WATER	(770) 621-7200
BELL SOUTH TELECOMMUNICATION	TELEPHONE	(770) 493-3754
COMCAST	CABLE TV	(770) 559-2424
DEKALB COUNTY TRAFFIC ENGINEERING	SIGNALS	(770) 492-5200
UNITED WATER SERVICES ATLANTA	WATER	(770) 235-2010
MCI COMMUNICATIONS	TELEPHONE	CALL BELLSOUTH

07/06/2006 3:11 AM: \\TRAFFIC\45196-001_Candler_Road\Roadway\753170notes.dgn



400 NORTH PARK TOWN CENTER, SUITE 900
 1200 ASBURNATHY ROAD NE
 ATLANTA, GEORGIA 30328
 TEL: (678) 888-8800 FAX: (678) 888-8400

CANDLER ROAD
 ARTERIAL ENHANCEMENT

GENERAL NOTES

DRAWING No.

4-01