STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	HPP-9014(25)	12	140
REVISION DATES			
6/29/05			
7/05/05			

ITEM No.	DESCRIPTION	UNIT	QUANTITY
	ROADWAY ITEMS		
150-1000	TRAFFIC CONTROL HPP-9014(25)	LS	LUMP
210-0100	GRADING COMPLETE HPP-9014(25)	LS	LUMP
310-1101	GR AGGR BASE CRS. INCL MATL	TN	1060
318-3000	AGGREGATE SURFACE COURSE	TN	1140
402-1812	RECYCLED ASPH CONC LEVELING. INCL BITUM MATL & H LIME	TN	370
402-3112	RECYCLED ASPH CONC 19 mm SUPERPAVE, GP 1 OR 2. INCL BITUM MATL & H LIME	TN	285
402-4510	RECYCLED ASPH CONC 12.5 mm SUPERPAVE, GP 2 ONLY. INCL POLYMER MODIFIED, BITUM. MAT'L & H LIME	TN	2325
413-1000	BITUM TACK COAT	GL	990
432-0206	MILL ASPH CONC PVMT. 1½IN DEPTH	SY	26900
441-0018	DRIVEWAY CONCRETE, 8 IN THK	SY	210
441-0104	CONCRETE SIDEWALK, 4 IN	SY	4715
441-0746	CONCRETE MEDIAN, 5½IN	SY	220
441-4030	CONC VALLEY GUTTER, 8 IN	SY	1315
441-5002	CONCRETE HEADER CURB, 6 IN, TP2	LF	260
441-6216	CONC CURB & GUTTER, 8 IN X 24 IN, TP2	LF	10000
444-1000	SAWED JOINTS IN EXISTING PAVEMENTS - PCC	LF	120
446-1100	PVMT REINF FABRIC STRIPS, TP2, 18 INCH WIDTH	LF	2200
500-3200	CLASS B CONCRETE (RETAINING WALL)	CY	180
500-9999	CLASS B CONC. BASE OR PVMT WIDENING	CY	65
550-1180	STORM DRAIN PIPE, 18 IN, H 1-10	LF	85
550-1240	STORM DRAIN PIPE, 24 IN, H 1-10	LF	65
550-1360	STORM DRAIN PIPE, 36 IN, H 1-10	LF	20
611-4001	RECONSTRUCT MINOR DRAINAGE STRUCTURE	EA	16
611-8000	ADJUST CATCH BASIN TO GRADE	EA	3
611-8040	ADJUST DROP INLET TO GRADE	EA	1
634-1200	RIGHT OF WAY MARKER	EA	56
668-1100	CATCH BASIN, GP 1	EA	4
668-1110	CATCH BASIN, GP 1, ADDL DEPTH	LF	4
668-2100	DROP INLET, GP 1	EA	11
668-2110	DROP INLET, GP 1, ADDL DEPTH	LF	8
668-4300	STORM SEWER MANHOLE, TP1	EA	4
668-4311	STORM SEWER MANHOLE, TP1, ADDL DEPTH	LF	5
	LIGHTING ITEMS		
681-4120	LIGHTING STANDARD, 12FT MH, POST TOP	EA	82
681-6320	LUMINAIRE, TP 3, 150W HP SODIUM	EA	82
682-1406	CABLE, TP XHHW, AWG NO 6	LF	24465
682-6110	CONDUIT, RIGID, 1 IN	LF	955
682-6219	CONDUIT, NONMETL, TP 2, 1 IN	LF	7200
682-9000	MAIN SERVICE PICK UP POINT - A	LUMP	LUMP
682-9000	MAIN SERVICE PICK UP POINT - B	LUMP	LUMP
682-9000	MAIN SERVICE PICK UP POINT - C	LUMP	LUMP
682-9000	MAIN SERVICE PICK UP POINT - D	LUMP	LUMP
	EROSION CONTROL ITEMS		
163-0240	MULCH	TN	5.0
163-0550	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	EA	33
165-0020	MAINTENANCE OF TEMPORARY SILT FENCE, TP B	LF	2000
165-0105	MAINTENANCE OF INLET SEDIMENT TRAP	EA	33
171-0020	TEMPORARY SILT FENCE, TYPE B	LF	4000
700-6910	PERMANENT GRASSING	AC	1
700-7000	AGRICULTURAL LIME	TN	5
700-7010	LIQUID LIME	GL	5
700-8000	FERTILIZER MIXED GRADE	TN	1
700-8100	FERTILIZER NITROGEN CONTENT	LB	50

ITEM No.	DESCRIPTION	UNIT	QUANTITY
	SIGNING AND MARKING ITEMS		
636-1020	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 3	SF	210
636-1031	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 6	SF	75
636-2070	GALV STEEL POSTS, TP 7	LF	546
652-5451	SOLID TRAFFIC STRIPE, 5 IN, WHITE	LF	1115
653-0110	THERMOPLASTIC PVMT MARKING, ARROW, TP1	EA	2
653-0120	THERMOPLASTIC PVMT MARKING, ARROW, TP2	EA	25
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	LF	5800
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	7950
653-1704	THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE	LF	300
653-1804	THERMOPLASTIC SOLID TRAF STRIPE, 8 IN, WHITE	LF	3150
653-3501	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN, WHITE	GLF	7300
653-3502	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN, YELLOW	GLF	2900
653-6004	THERMOPLASTIC TRAF STRIPING, WHITE	SY	70
653-6006	THERMOPLASTIC TRAF STRIPING, YELLOW	SY	290
654-1001	RAISED PVMT MARKERS TP1	EA	80
654-1003	RAISED PVMT MARKERS TP3	EA	110
	TRAFFIC SIGNAL ITEMS		
615-1200	DIRECTIONAL BORE - 3" DIA.	LF	1250
639-3004	STEEL STRAIN POLE WITH 50' MAST ARM ASSEMBLY (DECORATIVE)	EA	2
639-3004	STEEL STRAIN POLE WITH 55' MAST ARM ASSEMBLY (DECORATIVE)	EA	1
639-3004	STEEL STRAIN POLE WITH 60' MAST ARM ASSEMBLY (DECORATIVE)	EA	1
647-1000	TRAFFIC SIGNAL INSTALLATION NO. 1	LUMP	LUMP
682-6233	CONDUIT, NONMETAL (HDPE), TP3, 2"	LF	2250
	HARDSCAPE		
754-4000	WASTE RECEPTACLE UNIT	EA	16
608-2000	BRICK MASONRY	M	10.2
	LANDSCAPE		
702-0905	QUERCUS PHELLOS (4")	EA	33
702-0474	ILEX X HGT.=8-10', SPREAD = 4-5', ROOT = B&B	EA	12
702-0472	ILEX X ATTENUATA HGT.=8-10', SPREAD = 4-5', ROOT = B&B	EA	3
702-0542	LAGERSTROEMIA INDICA HGT.=8-10', SPREAD = 4-5', ROOT = B&B	EA	23
702-0358	ILEX CORNUTA - CARISSA	EA	202
702-0395	ILEX CRENATA HGT.=18", SPREAD = 18", ROOT = 3 Gal.	EA	3003
702-0358	ILEX CORNUTA - NEEDLEPOINT	EA	78
702-0559	LIRIOPE MUSCARI HGT.=6", SPREAD = 6", ROOT = 4" Pot	EA	1851
702-0502	JUNIPERUS DAVURICA HGT.=6" min., SPREAD = 12-15", ROOT = 3 Gal.	EA	916
702-9020	MULCH	SY	450

URS
400 NORTHPARK TOWN CENTER, SUITE 900
1000 ABERNATHY ROAD NE
ATLANTA, GEORGIA 30328
TEL: (678) 808-8800 FAX: (678) 808-8400

CANDLER ROAD ARTERIAL ENHANCEMENT — DETAILED ESTIMATE

DRAWING No. 9-01

07/07/2005 11:51:29 AMP:\TRAFFIC\45196-001_Candler_Road\Roadway\753170DET.dgn
...\Roadway\753170DET.dgn