SUMMARY OF QUANTITIES

GRASSING, MULCH, LIME, & FERTILIZER	GRASSING AC	MULCH TN	AGRICULTURAL LIME TN	FERTILIZER MIXED GRADE TN	FERTILIZER NITROGEN CONTENT LB
PERMANENT	10.20	31	31	6.12	510
TEMPORARY	5.10	15	-	3.06	-
DISTURBED	-	86	-	1.02	-
TOTAL	15.30	132	31	10.20	510

STN DUMPED RIP RAP, TP 1, 24 IN	
TOTAL	24 SY

STN DUMPED RIP RAP, TP 3, 24 IN	
TOTAL	304 SY

STN DUMPED RIP RAP, TP 3, 18 IN	
TOTAL	3 SY

PLASTIC FILTER FABRIC	
TOTAL	331 SY

TEMPORARY SILT FENCE, TYPE C	
TOTAL	27277 LF
MAINTENANCE OF TEMPORARY SILT FENCE, TP C	
TOTAL	13639 LF

CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	
TOTAL	27 EA
MAINTENANCE OF INLET SEDIMENT TRAP	
TOTAL	27 EA

WATER QUALITY MONITORING AND SAMPLING	
TOTAL	1 EA
WATER QUALITY INSPECTIONS	
TOTAL	30 MO

LIQUID LIME	
TOTAL	25 GAL

CONSTRUCTION EXIT	
TOTAL	12 EA

MAINTENANCE OF CONSTRUCTION EXIT	
TOTAL	12 EA

EROSION CONTROL MATS	
TOTAL	7524 SY

CONSTRUCT AND REMOVE RIP RAP CHECK DAMS, STONE PLAIN RIP RAP/SAND BAGS	
TOTAL	48 EA
MAINTENANCE OF CHECK DAMS - ALL TYPES	
TOTAL	48 EA

CONSTRUCT AND REMOVE RETROFIT, STA NO - 121+35.00	
TOTAL	1 EA
MAINTENANCE OF RETROFIT, STA NO - 121+35.00	
TOTAL	1 EA

PERMANENT SOIL REINFORCING MAT	
TOTAL	525 SY

PLAIN CONC DITCH PAVING, 4 IN

SR 400 TO I-85 RAMP			
BEGIN	END		SY
STA 107+65 LT	STA 110+50 LT		621
STA 109+37 RT	STA 110+59 RT		765
STA 126+72 RT	STA 128+07 LT		999
		SUBTOTAL	2385
I-85 TO SR 400 RAMP			
BEGIN	END		SY
STA 220+80 RT	221+25 RT		364
		SUBTOTAL	364
		TOTAL	2749

PAVEMENT MARKINGS

8" SKIP WHITE PREFORMED PLASTIC CONTRAST (BLACK-WHITE)	GLF
SR 400 TO I-85	610
I-85 TO SR 400	970
TOTAL	1580

TYPE 3 C/R RPMS	EA
SR 400 TO I-85	244
I-85 TO SR 400	109
TOTAL	353

THERMO TRAFFIC STRIPE, 10" SOLID WHITE	LF
SR 400 TO I-85	675
I-85 TO SR 400	535
TOTAL	1210

THERMO TRAFFIC STRIPE, 8 IN, WHITE	SY
SR 400 TO I-85	0
I-85 TO SR 400	2475
TOTAL	2475

THERMO TRAFFIC STRIPE, 10 IN, WHITE	SY
SR 400 TO I-85	3453
I-85 TO SR 400	6885
TOTAL	10338

8" (2'-6" SKIP) WHITE CONTRAST	GLF
SR 400 TO I-85	320
I-85 TO SR 400	0
TOTAL	320

8" SOLID WHITE PREFORMED PLASTIC CONTRAST (BLACK-WHITE)	LF
SR 400 TO I-85	4600
I-85 TO SR 400	2700
TOTAL	7300

13" SOLID WHITE PREFORMED PLASTIC CONTRAST (BLACK-WHITE)	LF
SR 400 TO I-85	2520
I-85 TO SR 400	1390
TOTAL	3910

8" SOLID YELLOW PREFORMED PLASTIC CONTRAST (BLACK-YELLOW)	LF
SR 400 TO I-85	3155
I-85 TO SR 400	1500
TOTAL	4655

5" SOLID WHITE	LF
SR 400 TO I-85	173

RELEASED FOR CONSTRUCTION
FEBRUARY 28, 2012