STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	IM-M000-00(282)	2	26

INDEX

DESCRIPTION	SHEET NUMBERS
COVER SHEET	1
INDEX, GENERAL NOTES & REVISION SUMMARY	2
TYPICAL SECTIONS	3
SUMMARY OF QUANTITIES	4
DETAILED ESTIMATE	5
CONSTRUCTION PLANS	5A - 5C
MAINTENANCE OF TRAFFIC PLANS	6 - 7
SIGNING & MARKING PLANS	8 - 10
CONST. DETAILS	11
GEORGIA STANDARD DRAWINGS	12 - 20
BRIDGE PLANS	21 - 26

GENERAL NOTES

1. THE CONTRACTOR SHALL BE REQUIRED TO USE THE ONE-CALL CENTER TELEPHONE NUMBER, 1-800-282-7411, FOR THE PURPOSE OF COORDINATING THE MARKING OF UNDERGROUND UTILITIES. THE CONTRACTOR'S ATTENTION IS CALLED TO SUB-SECTION 105.06 "COOPERATION WITH UTILITIES".

2. ANY MILE POST MARKER OR SIGN THAT MAY BE DISTURBED OR REMOVED DURING CONSTRUCTION OR THAT BECOMES TOO CLOSE TO THE NEW EDGE OF PAVEMENT SHALL BE RESET OR REPLACED PER GA. STANDARD NO. 9033 (MILEPOSTS). NO SEPARATE PAYMENT WILL BE MADE FOR RESETTING OR REPLACING COST TO BE INCLUDED IN OVERALL BID.

3. THIS PROJECT LIES WITHIN THE LIMITS OF AN INSECT INFESTED AREA. THE CONTRACTOR'S ATTENTION IS CALLED TO THE FOLLOWING SUB-SECTIONS OR SPECIAL PROVISIONS TO THE STANDARD SPECIFICATIONS:
   A) SUB-SECTION 107.13D - INSECT CONTROL REGULATIONS
   B) SUB-SECTION 155 - INSECT CONTROL
   C) SUB-SECTION 893 - MISCELLANEOUS PLANTING.

4. NOTICE OF INTENT IS NOT REQUIRED.

5. ALL WORK SHALL BE COMPLETED WITHIN THE EXISTING RIGHT-OF-WAY.

6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL AND PROPERLY DISPOSING OF ALL UNSALVAGEABLE MATERIAL IN THIS PROJECT. THE CONTRACTOR SHALL NOT DEPOSIT ANY MATERIAL IN ANY WATERWAY. DISPOSAL SHALL BE INCLUDED IN THE PRICE BID FOR CONTRACT ITEMS.

7. THE CONTRACTOR SHALL BE LIMITED TO WORKING ON TWO BRIDGES AT A TIME. THE CONTRACTOR SHALL MOVE THE CHANGEABLE MESSAGE SIGNS FROM WORK SITE TO WORK SITE AS NECESSARY.

CONSTR. DETAILS

SHEET NO.	DESCRIPTION	DATE
11	IMPACT ATTENUATOR UNITS (G-11)	03-01

GEORGIA STANDARDS

SHEET NO.	DESCRIPTION	DATE
12	3901 BAR BENDING DETAILS	08-69
13	4010 "W" BEAM GUARDRAIL	07-97
14	4011-A POST & OFFSET BLOCKS FOR "W" & "T" BEAM GUARDRAIL	10-97
15	4040 GUARDRAIL ANCHORAGE TYPE 12	07-97
16	4360 REFLECTORIZED GUARDRAIL WASHERS	08-97
17	4960 CONCRETE BARRIER TEMPORARY	11-97
18	4961 PRECAST TEMP BARRIER	05-96
19	9106 TRAFFIC CONTROL DETAIL (FOR LANE CLOSURE ON MULTI-LANE HIGHWAY)	05-94
20	9100 TRAFFIC CONTROL GENERAL NOTES, STANDARD LEGEND, MISC. DETAILS	08-99

REVISION SUMMARY

DATE	REVISED SHEET NO.	REVISION
09-27-01	1	REVISED PROJECT LENGTH
09-27-01	2	ADDED CONSTRUCTION PLAN SHEETS
09-27-01	3	ADDED NOTE STATING PAVING DETAIL IS FOR BOTH SIDES OF ROADWAY
09-27-01	4	CHANGED TYPE OF PORTABLE IMPACT ATTENUATOR
09-27-01	4	REMOVED NOTE UNDER MILL ASPHALT CONCRETE PAVEMENT BLOCK
09-27-01	4	ADDED TEMPORARY MULCH QUANTITY
09-27-01	4	ADDED TEMPORARY SEEDING QUANTITY
09-27-01	4	CHANGED TYPE OF VARIABLE MESSAGE SIGN
09-27-01	4	CHANGED LENGTH OF TYPE W GUARDRAIL
09-27-01	5	CHANGED TYPE OF PORTABLE IMPACT ATTENUATOR
09-27-01	5	ADDED TEMPORARY MULCH QUANTITY
09-27-01	5	ADDED TEMPORARY SEEDING QUANTITY
09-27-01	5	REMOVED PAY ITEM 610-1065
09-27-01	5	REMOVED PAY ITEM 611-5301
09-27-01	5	REMOVED PAY ITEM 632-0010
09-27-01	5	ADDED PAY ITEM 632-0003
09-27-01	5	CHANGED LENGTH OF TYPE W GUARDRAIL
09-27-01	5A - 5C	ADDED CONSTRUCTION PLAN SHEETS
09-27-01	6	CHANGED NOTE REGARDING LENGTH OF GUARDRAIL TO BE REMOVED ON RIGHT SIDE
09-27-01	21	TRACK CLEARANCES ADDED
09-27-01	23 & 26	STRIPING NOTE REVISED
09-27-01	24	NOTE REMOVED
10-12-01	4	CHANGED TYPE OF PORTABLE IMPACT ATTENUATOR
10-12-01	5	CHANGED TYPE OF PORTABLE IMPACT ATTENUATOR
11-06-01	3	REVISED OGFC PAVEMENT TO POLYMER - MODIFIED
11-06-01	4	REVISED OGFC PAVEMENT TO POLYMER - MODIFIED
11-06-01	5	REVISED OGFC PAVEMENT TO POLYMER - MODIFIED
11-06-01	3	REVISED PAVING CONSTRUCTION SEQUENCE
11-06-01	4	REVISED MILL ASPH CONC PVMT VARIABLE DEPTH QUANTITY
11-06-01	5	REVISED MILL ASPH CONC PVMT VARIABLE DEPTH QUANTITY
11-06-01	4	REVISED BITUMINOUS TACK COAT QUANTITY
11-06-01	5	REVISED BITUMINOUS TACK COAT QUANTITY
11-06-01	4	REVISED 12.5 mm SUPERPAVE QUANTITY
11-06-01	5	REVISED 12.5 mm SUPERPAVE QUANTITY
11-06-01	4	REMOVED ASPHALTIC CONC LEVELING QUANTITY
11-06-01	5	REMOVED ASPHALTIC CONC LEVELING QUANTITY