STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	IM-M000-00(282)	4	26

SUMMARY OF QUANTITIES

GRADING COMPLETE IM-M000-00 (282)

TOTAL LUMP SUM

TRAFFIC CONTROL IM-M000-00 (282)

TOTAL LUMP SUM

VARIABLE MESSAGE SIGN PORTABLE, TYPE 3

TOTAL 2

PORTABLE IMPACT ATTENUATOR TYPE T-3-S-30

TOTAL 3

TO BE USED AS DIRECTED BY THE ENGINEER

SURFACING QUANTITES

ITEMS	UNIT	MAINLINE	SHOULDERS	TOTALS
RECYCL ASPH CONC 12.5 mm SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	3400	1400	4800
RECYCL ASPH CONC 19 mm SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	0	25	25
RECYCL ASPH CONC 25 mm SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	0	50	50
ASPH CONC 12.5 mm SMA, GP 2 ONLY, INCL POLYMER-MODIFIED	TN	1700	0	1700
BITUM MATL & H LIME				
ASPH CONC 12.5 mm OGFC, GP 2 ONLY, INCL POLYMER-MODIFIED	TN	920	80	1000
BITUM MATL & H LIME				
BITUMINOUS TACK COAT	GL	4900	1900	6800
GR AGGR BASE CRS, INCL MATL	TN	0	100	100

MILL ASPH CONC PVMT VARIABLE DEPTH

TOTAL 55,000 SQ. YD.

INDENTATION RUMBLE STRIPS GROUND IN PLACE

TOTAL 3 MILES

GUARDRAIL QUANTITIES

GUARDRAIL "W, DF" BEAM		ANCHORAGES	
LOCATION & SIDE	LIN FT	TP 12	TP 12†
1068+70 - 1071+70 RT	300	1	
1066+81 - 1069+81 LT	300	1	
1071+70 RT			1
TOTALS	600	2	1

SEE GA. STD. 4040 FOR TYPE 12 ANCHOR
SEE GA. STD. 4960 FOR PLACMENT OF TYPE 12 TEMPORARY ANCHOR

PAVEMENT MARKERS (EACH)

LOCATION	REFLECTIVE-RAISED			REFLECTIVE-RECESSED			OPAQUE		JIGGLE BAR		CHANNEL MKR	
	YELLOW	CLEAR	CLEAR/RED	YELLOW	CLEAR		WHITE	YELLOW				
	TYPE 1	TYPE 2	TYPE 3	TYPE 1	TYPE 2	TYPE 3	TYPE 5	TYPE 6	TYPE 7	TYPE 8	TYPE 9	TYPE 10
MAINLINE												
5" SKIP WHITE			150									
TOTALS			150									

NOTES: 1. TYPE 1,2, AND 3 PAVEMENT MARKERS SHALL BE SPACED 80 FEET APART.
2. INSERT IN COLUMN HEADING, AS SPECIFIED ON PLANS, ANY COMBINATION OF CLEAR, YELLOW, OR RED.
3. INSERT IN COLUMN HEADING, AS SPECIFIED ON PLANS, WHITE, YELLOW, OR RED.

TEMPORARY CONCRETE BARRIER METHOD 3

LOCATION	LIN. FT.
AS DIRECTED BY ENGINEER	2700
TOTAL	2700

TRAFFIC STRIPE

DESCRIPTION	UNIT	QUANTITY PREFORMED	QUANTITY THERMOPLASTIC
5" SOLID WHITE	LIN FEET	900	5,100
5" SOLID YELLOW	LIN FEET	900	5,100
5" SKIP WHITE	GR LIN FT	1,800	10,800

GRASSING

ITEM	UNIT	QUANTITY	AGRICULTURAL LIME	FERTILIZER MIXED GRADE	FERTILIZER NITROGEN CONTENT
			TON	TON	LB
PERMANENT GRASSING	LBS	50	3	1	50
ADDITIONAL GRASSING	LBS				
TOTAL			3	1	50

TEMPORARY MULCH

TOTAL 2 TONS

TEMPORARY GRASSING

TOTAL 50 LBS

INSTALLATION SILT FENCE - TYPE A

TOTAL 1000 LIN FT.

TO BE USED AT LOCATIONS SHOWN ON PLANS AND / OR AS DIRECTED BY ENGINEER.

MAINTENANCE SILT FENCE - TYPE A

TOTAL 500 LIN FT.