DETAILED ESTIMATE

ITEM NO.	ROADWAY ITEMS	UNIT	QUANTITY
150-1000	TRAFFIC CONTROL - IM-M000-00(282)	LS	LUMP
150-5010	TRAFFIC CONTROL, PORTABLE IMPACT ATTENUATOR - TYPE T-3-S-30	EA	3
163-0230	TEMPORARY GRASSING	LB	50
163-0235	TEMPORARY MULCH	TN	2
210-0100	GRADING COMPLETE - IM-M000-00(282)	LS	LUMP
310-1101	GR AGGR BASE CRS, INCL MATL	TN	100
400-3206	ASPH CONC 12.5 MM OGFC, GP 2 ONLY, INCL POLYMER-MODIFIED	TN	1000
	BITUM MATL & H LIME		
400-3604	ASPH CONC 12.5 MM SMA, GP 2 ONLY, INCL POLYMER-MODIFIED	TN	1700
	BITUM MATL & H LIME		
402-3112	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM & H LIME	TN	25
402-3113	RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 1 OR 2, INCL BITUM & H LIME	TN	4800
402-3121	RECYCLED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2, INCL BITUM & H LIME	TN	50
413-1000	BITUM TACK COAT	GL	6800
432-5010	MILL ASPH CONC PVMT, VARIABLE DEPTH	SY	55000
456-2010	INDENTATION RUMBLE STRIPS - GROUND IN PLACE	MI	3
622-1033	PRECAST CONCRETE MEDIAN BARRIER, METHOD 3	LF	2700
632-0003	VARIBLE MESSAGE SIGN, PORTABLE, TYPE 3	EA	2
641-4020	DBL FACED GUARDRAIL, TP W	LF	600
641-5012	GUARDRAIL ANCHORAGE, TP 12	EA	2
641-9912	TEMPORARY GUARDRAIL ANCHORAGE, TP 12	EA	1
	PERMANENT EROSION CONTROL		
700-6900	PERMANENT GRASSING	LB	50
700-7000	AGRICULTURAL LIME	TN	3
700-8000	FERTILIZER MIXED GRADE	TN	1
700-8100	FERTILIZER NITROGEN CONTENT	LB	50
	TEMPORARY EROSION CONTROL		
165-0010	MAINTAENANCE OF TEMPORARY SILT FENCE, TP A	LF	500
171-0010	TEMPORARY SILT FENCE, TYPE A	LF	1000
	SIGNING & MARKING		
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	LF	5100
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	5100
653-3501	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN, WHITE	GLF	5100
654-1003	RAISED PVMT MARKERS TP 3	EA	150
657-1054	PREFORMED PLASTIC SOLID PVMT MKG, 5 IN, WHITE, TP PB	LF	900
657-3054	PREFORMED PLASTIC SKIP PVMT MKG, 5 IN, WHITE, TP PB	GLF	1800
657-6054	PREFORMED PLASTIC SOLID PVMT MKG, 5 IN, YELLOW, TP PB	LF	900
	BRIDGE NO. 1		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	246
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 1, BENT NO - 1		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	246
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 1, BENT NO - 2		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	246
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 1, BENT NO - 3		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	246
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 1, BENT NO - 4		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	246
	POLYETHYLENE COPOLYMER NITROGEN-BLOWN SEAL, BR NO - 1, BENT NO - 5		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	246
	POLYETHYLENE COPOLYMER NITROGEN-BLOWN SEAL, BR NO - 1, BENT NO - 6		
500-0100	GROOVED CONCRETE	SY	1997
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONCRETE	CY	506
511-3000	SUPERSTR REINF STEEL, BR NO - 1 (104022)	LS	LUMP
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO - 1	LS	LUMP
	BRIDGE NO. 2		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	65
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 2, BENT NO - 3		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	65
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 2, BENT NO - 6		
500-0100	GROOVED CONCRETE	SY	2403
519-0401	CONCRETE OVERLAY, VARIABLE THK - FAST TRACK	SY	2403