

11-158

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	IM-M000-00 (283)	2	

SUMMARY OF QUANTITIES													
BRIDGE	UNIT	LS	LF	SY	CY	LS	SY	LS	EA	LF	LF	CLF	EA
BRIDGE NO. 1 BR. SERIAL NO. 067-0052-0		-	588	2035	120	(16590)	2035	LS	1	482	482	964	20
BRIDGE NO. 2 BR. SERIAL NO. 121-0119-0		-	145	1244			1244		1	214	248	461	8
BRIDGE NO. 3 BR. SERIAL NO. 121-0120-0		-	444	2148			2148		1	918	306	612	10
BRIDGE NO. 4 BR. SERIAL NO. 121-0153-0		-	367	4318			4318		1	479	470	2364	36
BRIDGE NO. 5 BR. SERIAL NO. 121-0242-0		-	906	5845	153	(22499)	5845	LS	1	844	844	2532	36
TOTAL	LUMP		2450	15590	273	(39089)	15590	LUMP	2 *	2937	2350	6933	110

* ONLY TWO OF THESE WILL BE REQUIRED TO COMPLETE THE WORK (ENOUGH FOR WORKING ON TWO BRIDGES AT ONE TIME)

GENERAL NOTES

TEMPORARY COVER PLATES - TEMPORARY STEEL COVER PLATES SHALL BE PLACED OVER OPENINGS IN THE DECK DURING HOURS WHEN WORK IS NOT BEING PERFORMED THEREIN. STEEL PLATES SHALL BE 1" THICK AND SHALL OVERLAP THE ADJACENT CONCRETE A MINIMUM OF 1 FOOT. PLATES SHALL BE ATTACHED TO DECK BY 3/4" CINCH ANCHORS EMBEDDED A MINIMUM OF 3 1/2" INTO THE CONCRETE. A MINIMUM OF TWO ANCHORS SHALL BE INSTALLED FOR EACH PLATE AND SHALL BE PLACED IN OPPOSITE CORNERS. ANCHORS SHALL BE PLACED A MINIMUM OF 6" AWAY FROM THE NEAREST CONCRETE EDGE AND 3' AWAY FROM THE NEAREST PLATE EDGE. HOLES IN PLATES FOR ANCHORS MAY BE FLAME CUT. PLATES SHALL BE ASTM A709 MATERIAL OR APPROVED EQUAL. CINCH ANCHORS SHALL BE ASTM A108 OR APPROVED EQUAL. PRIOR TO REOPENING THE STRUCTURE TO TRAFFIC THE CONTRACTOR SHALL REMOVE THE ANCHORS 1" (MINIMUM) BELOW THE TOP OF THE DECK. HOLES LEFT BY REMOVING THE ANCHORS SHALL THEN BE PATCHED WITH NON-SHRINK GROUT APPROVED BY THE ENGINEER. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING, HANDLING, INSTALLING, MOVING, STORAGE, REMOVAL OF THE TEMPORARY PLATES AND ANCHORS, AND PATCHING OF THE DECK. ALL COST OF SUCH SHALL BE INCLUDED IN THE OVERALL BID SUBMITTED.

ALL WORK SHALL BE COMPLETED WITHIN THE EXISTING RIGHT-OF-WAY.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL AND PROPERLY DISPOSING OF ALL UNSALVAGEABLE MATERIAL IN THIS PROJECT. THE CONTRACTOR SHALL NOT DEPOSIT ANY MATERIAL IN ANY WATERWAY. THE COST OF REMOVAL AND DISPOSAL SHALL BE INCLUDED IN THE PRICE BID FOR CONTRACT ITEMS.

THE CONTRACTOR SHALL BE LIMITED TO WORKING ON TWO BRIDGES AT A TIME. THE CONTRACTOR SHALL MOVE THE CHANGEABLE MESSAGE SIGNS FROM WORK SITE TO WORK SITE AS NECESSARY.

JBT **J.B. Trimble, Inc.**
 6445 Powers Ferry Road
 Atlanta GA 30339-2933
 (770) 952-1022

GEORGIA
DEPARTMENT OF TRANSPORTATION
 OPERATIONS DIVISION-OFFICE OF MAINTENANCE

DISTRICT 7 BRIDGE REPAIRS (DECK OVERLAY)
 SUMMARY OF QUANTITIES
 IM-M000-00 (283)

SCALE: AS SHOWN MAY 2001

DESIGNED MDT	CHECKED GLE	REVIEWED EHG
DRAWN ITD	DESIGN GROUP MAINTENANCE	APPROVED STH

	DATE								
BY	REVISIONS	DATE							

