M-158

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	IM-M000-00 (283)	3	

DETAILED ESTIMATE

ITEM NO.	ITEM	UNIT	QUANTITY
150-1000	TRAFFIC CONTROL - PROJECT NO IM-M000-00 (283)	LUMP	LUMP
632-0003	CHANGEABLE MESSAGE SIGN, PORTABLE, TYPE 3	EA	2
	BRIDGE NO. 1		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 1, BENT NO - 1	LF	168
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 1, BENT NO - 2	LF	84
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 1, BENT NO - 3	LF	84
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 1, BENT NO - 4	LF	84
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 1, BENT NO - 5	LF	168
500-0100	GROOVED CONCRETE	SY	2035
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONC, BR NO - 1	CY	120
511-3000	SUPERSTR REINF STEEL, BR NO - 1 (16590)	LS	LUMP
519-0401	CONCRETE OVERLAY, VARIABLE THK - FAST TRACK	SY	2035
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO - 1	LS	LUMP
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	LF	482
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	482
653-3501	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN, WHITE	GLF	964
654-1001	RAISED PVMT MARKERS TP 1	EA	20
	BRIDGE NO. 2		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 2, BENT NO - 1	LF	57
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 2, BENT NO - 4	LF	88
500-0100	GROOVED CONCRETE	SY	1244
519-0401	CONCRETE OVERLAY, VARIABLE THK - FAST TRACK	SY	1244
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	LF	214
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	248
653-3501	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN, WHITE	GLF	461
654-1001	RAISED PVMT MARKERS TP 1	EA	8
	BRIDGE NO. 3		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 3, BENT NO - 1	LF	164
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 3, BENT NO - 2	LF	79
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 3, BENT NO - 4	LF	69
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 3, BENT NO - 5	LF	132
500-0100	GROOVED CONCRETE	SY	2148
519-0401	CONCRETE OVERLAY, VARIABLE THK - FAST TRACK	SY	2148
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	LF	918
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	306
653-3501	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN, WHITE	GLF	612
654-1001	RAISED PVMT MARKERS TP 1	EA	10
	BRIDGE NO. 4		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 4, BENT NO - 1	LF	172
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 4, BENT NO - 4	LF	195
500-0100	GROOVED CONCRETE	SY	4318
519-0401	CONCRETE OVERLAY, VARIABLE THK - FAST TRACK	SY	4318
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	LF	479
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	470
653-3501	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN, WHITE	GLF	2364
654-1001	RAISED PVMT MARKERS TP 1	EA	36
	BRIDGE NO. 5		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 5, BENT NO - 1	LF	138
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 5, BENT NO - 2	LF	69
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 5, BENT NO - 3	LF	69
449-1300	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 5, -BENT NO - 6	LF	69
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 5, BENT NO - 7	LF	69
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 5, BENT NO - 8	LF	69
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 5, BENT NO - 9	LF	69
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 5, BENT NO - 10	LF	69
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 5, BENT NO - 11	LF	69
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 5, BENT NO - 12	LF	72
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 5, BENT NO - 13	LF	144
500-0100	GROOVED CONCRETE	SY	5845
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONCRETE, BR NO - 5	CY	153
511-3000	SUPERSTR REINF STEEL, BR NO - 5 (22499)	LS	LUMP
519-0401	CONCRETE OVERLAY, VARIABLE THK - FAST TRACK	SY	5845
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO - 5	LS	LUMP
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	LF	844
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	844
653-3501	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN, WHITE	GLF	2532
654-1001	RAISED PVMT MARKERS TP 1	EA	36

C:\DGN\ 2019\CT2\BOL2- DE.DGN 2-18-01 ITD

GEORGIA REGISTERED No. 16606 PROFESSIONAL ENGINEER SAMUEL L. POWELL, JR. 5-25-01

BY	REVISIONS	DATE

JBT J.B. Trimble, Inc.
6445 Powers Ferry Road
Atlanta GA 30339-2933
(770) 952-1022

GEORGIA
DEPARTMENT OF TRANSPORTATION
OPERATIONS DIVISION-OFFICE OF MAINTENANCE

DISTRICT 7 BRIDGE REPAIRS (DECK OVERLAY)

DETAILED ESTIMATE

IM-M000-00 (283)

SCALE: AS SHOWN MAY 2001

DESIGNED MDT CHECKED GLE REVIEWED EHG
DRAWN ITD DESIGN GROUP MAINTENANCE APPROVED STH

2/19/2008 12:47:27 PM \\GDOT-DSN1\GOPLOT\QCF\Road Design Tiff-18x12 to Tiff-36x24.qcf wnguyen C:\Documents and Settings\wnguyen\Desktop\M000283\Construction\Plan Sheet\M000283 0003.tif GO-RD-Plans-Review