TRAFFIC CONTROL

STP00-M000-00 (355)	LUMP SUM

GRADING COMPLETE

STP00-M000-00 (355)	LUMP SUM

PERMANENT GRASSING SUMMARY

PERMANENT GRASSING	AGRICULTURAL LIME	LIQUID LIME	FERTILIZER MIXED GRADE	FERTILIZER NITROGEN CONTENT
ACRE	TON	GALLON	TON	LB
1	2	2	1	35

PERMANENT EROSION CONTROL ITEMS

ITEM	UNIT	TOTAL
STN DUMPED RIP RAP, TP 3, 18 IN	SY	25
PLASTIC FILTER FABRIC	SY	25
EROSION CONTROL MATS, SLOPES	SY	330

CLASS "B" CONCRETE BASE OR PVMT WIDENING

15	CU. YDS.

4" CONCRETE SLOPE PAVING

275	SY

AGGREGATE SURFACE COURSE

250	TON

SAWED JOINTS IN EXIST PAVEMENTS - PCC

505	LF

TEMPORARY EROSION CONTROL

ITEM	UNIT	QUANTITY
BALED STRAW CHECK DAM - AS REQ'D	LIN FT	100
SILT FENCE-TYPE A - AS REQ'D	LIN FT	200
SILT FENCE-TYPE C	LIN FT	350
CONSTRUCTION EXIT	EACH	2
MAINTENANCE OF SILT FENCE, TYPE A	LIN FT	100
MAINTENANCE OF SILT FENCE, TYPE C	LIN FT	175
MAINTENANCE OF SEDIMENT BARRIER - BALED STRAW	LIN FT	50
MAINTENANCE OF CONSTRUCTION EXIT	EACH	2
CONSTR & REM TEMP PIPE SLOPE DRAIN - AS REQ'D	LIN FT	300
TEMPORARY GRASSING	ACRE	3
MULCH	TON	10
CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	EACH	10
MAINTENANCE OF INLET SEDIMENT TRAP	EACH	10

BARRIER FENCE (ORANGE) 4 FT

435	LIN FT

CONCRETE ITEMS

ITEMS	UNIT	QUANTITY
CONCRETE CURB & GUTTER 8" X 30" TYPE 2 STD. 9032-B	LIN. FT	1265
CONCRETE CURB & GUTTER W/RAISED EDGE 8" X 30"	LIN. FT	505
CONCRETE VALLEY GUTTER 8 IN.	SQ. YDS.	130
DRIVEWAY CONCRETE 8 IN.	SQ. YDS.	170
RIGHT OF WAY MARKERS	EACH	8
CONCRETE SIDEWALK 4 IN.	SQ. YDS.	415

SURFACING QUANTITIES

ITEMS	UNIT	SR 83	CHURCH ST.	TOTAL
RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 2 ONLY, INCL POLYMER-MODIFIED BITUM MATL & H LIME	TON	160	35	195
RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TON	215	45	260
RECYCLED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TON	790	160	950
GRADED AGGREGATE BASE CRS, INCL MATL	TON	1285	255	1540
RECYCLED ASPH CONC LEVELING, INCL BITUM MATL & H LIME, AS REQ'D	TON	50		50
BITUMINOUS TACK COAT	GAL	155	30	185
MILL ASPH CONC PVMT, VARIABLE DEPTH - AS REQ'D	SY	200		200

STRIPING QUANTITIES

	SOLID TRAFFIC STRIPE 5" WHITE	SOLID TRAFFIC STRIPE 5" YELLOW	SOLID TRAFFIC STRIPE 24" WHITE	SOLID TRAFFIC STRIPE 8" WHITE	RAISED PVMT MARKERS TP 2
	LF	LF	FT	LF	EA
TOTAL	1765	1765	10	250	20

GEORGIA
DEPARTMENT
OF
TRANSPORTATION

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: DISTRICT 2 DESIGN - TENNILLE

SUMMARY QUANTITIES

DRAWING No. 6-01

GPLN