STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	NHS-M000-00(416)	2	43

INDEX

DESCRIPTION	SHEET NUMBERS
COVER SHEET	1
INDEX & GENERAL NOTES	2
REVISION SUMMARY	3
TYPICAL SECTIONS	4
DETAIL OF TYPICAL SECTIONS	5
SUMMARY OF QUANTITIES	6-7
DETAILED ESTIMATE	8
CONSTRUCTION PLAN SHEETS	9-10
STAGING & DETOUR PLANS	11-13
SIGNING & MARKING PLANS	14-14A
EROSION CONTROL PLANS	15-16
CONSTRUCTION DETAILS	17-21
GEORGIA STANDARD DRAWINGS	22-37
BRIDGE PLANS	40-43

GEORGIA STANDARDS

OMITTED DWG. NO.	SHEET NO.		DESCRIPTION	DATE
			ROADWAY	
	22	3901	BAR BENDING DETAILS	08-69
	23	4010	"W" BEAM GUARDRAIL	07-97
	24	4011-A	POST & O/S BLOCKS "W" & "T" BEAM GUARDRAIL	10-97
	25	4012-C	G-RAIL CONN TP 1 G-RAIL CONN AT BRIDGE/BARRIER	08-97
	26	4022-A	LOCATION OF GUARDRAIL	11-97
	27	4040	GUARDRAIL ANCH TP 12	07-97
	28	4051	G-RAIL LOCATION DET'S	10-97
	29	4270	STD. "T" BEAM G-RAIL	12-89
	30	4360	REFLECTORIZED G-RAIL WASHERS	08-97
	31	4940	CONCRETE BARRIER PERMANENT	12-88
	32	4960	CONCRETE BARRIER TEMPORARY	11-97
	33	4961	PRECAST TEMP BARRIER	05-96
	34	4962	TEMP TRAFFIC IMPACT ATTENUATOR	08-93
	35-36	5001M	DROP INLETS TYPES M-1 & M-2	06-93
	37	9017M	REINFORCED CONCRETE APPROACH SLAB (WITH CONCRETE BARRIER)	06-93
	38	9037	TYPICAL FILL DETAIL AT END OF BRIDGE	10-97
	39	9106	TRAFFIC CONTROL DETAIL (FOR LANE CLOSURE ON MULTI-LANE HIGHWAY)	05-94

CONSTRUCTION DETAILS

OMITTED DWG. NO.	SHEET NO.	DESCRIPTION	DATE
		GEORGIA D.O.T.	
	17	TYPE "V" INLET "V" GUTTER DET	06-90
	18	TYPICAL LOCATION DETAILS FOR SILT FENCE/BALED STRAW	05-93
	19	LOCATION OF CONTINOUS DOUBLE FACED GUARDRAIL IN MEDIAN	09-99
	20	UNIFORM CODE SYSTEM FOR SOIL EROISON AND SEDIMENT CONTROL (TEMPORARY ITEMS)	03-98
	20A	SUBBASES FOR APPROACH SLABS	06-88
	21	TRAFFIC CONTROL GENERAL NOTES, STANDARD LEGEND, MISCELLANEOUS DETAILS	05-99

GENERAL NOTES

1. THE CONTRACTOR SHALL BE REQUIRED TO USE THE ONE-CALL CENTER TELEPHONE NUMBER, 1-800-282-7411, FOR THE PURPOSE OF COORDINATING THE MARKING OF UNDERGROUND UTILITIES. THE CONTRACTOR'S ATTENTION IS CALLED TO SUB-SECTION 105.06 "COOPERATION WITH UTILITIES".

2. ANY MILE POST MARKER THAT MAY BE DISTURBED OR REMOVED DURING CONSTRUCTION OR THAT BECOMES TOO CLOSE TO THE NEW EDGE OF PAVEMENT SHALL BE RESET OR REPLACED PER GA. STANDARD NO. 9033 (MILEPOSTS). NO SEPARATE PAYMENT WILL BE MADE FOR RESETTING OR REPLACING COST TO BE INCLUDED IN OVERALL BID.

3. THIS PROJECT LIES WITHIN THE LIMITS OF AN INSECT INFESTED AREA. THE CONTRACTOR'S ATTENTION IS CALLED TO THE FOLLOWING SUB-SECTIONS OR SPECIAL PROVISIONS TO THE STANDARD SPECIFICATIONS:
   A) SUB-SECTION 107.13D - INSECT CONTROL REGULATIONS
   B) SUB-SECTION 155 - INSECT CONTROL
   C) SUB-SECTION 893 - MISCELLANEOUS PLANTING.

4. NOTICE OF INTENT IS NOT REQUIRED.

5. THIS PROJECT IS LOCATED 100% WITHIN MONROE COUNTY.

6. THIS PROJECT IS LOCATED 100% WITHIN CONGRESSIONAL DISTRICT NUMBER 8 .

2/19/2008 1:23:15 PM \\GDOT-DSN1\GDPLOT\QCF\Road Design Tiff-18x12 to Tiff-36x24.qcf wnguyen C:\Documents and Settings\wnguyen\Desktop\M000416\Construction\Cover-Index\M000(416) 0002.tif GO-RD-Plans-Review