

SUMMARY OF QUANTITIES

GRASSING			AGRICULTURAL LIME	FERTILIZER MIXED GRADE	FERTILIZER NITROGEN CONTENT
ITEM	UNIT	QUANTITY	TON	TON	LB
PERMANENT GRASSING	LBS	50	3	1	50
ADDITIONAL GRASSING	LBS				
TOTAL			3	1	50

GRADING COMPLETE	
TOTAL	LUMP SUM

"V" GUTTER - SEE CONSTR. DETAILS		
LOCATION	SIDE	LIN. FT.
1329+05 - 1334+00	LT	495
TOTALS		495

TRAFFIC CONTROL	
TOTAL	LUMP SUM

INSTALLATION SILT FENCE - TYPE C	
TOTAL	150 LIN FT.

TEMPORARY CONCRETE BARRIER METHOD 1		
LOCATION	LIN. FT.	
AS DIRECTED BY ENGINEER	3100	
TOTAL		3100

PORTABLE VARIABLE MESSAGE SIGN-TP3	
TOTAL	2

MAINTENANCE SILT FENCE - TYPE C	
TOTAL	75 LIN FT.

TEMPORARY IMPACT ATTENUATOR SAND LOADED MODULES	
TOTAL	36

MILL ASPH CONC PVMT VARIABLE DEPTH	
TOTAL	46,800 SQ. YD.

THE CONTRACTOR IS RESPONSIBLE FOR ALL HANDLING, STORAGE, PROPER REPAIR & MAINTENANCE OF THE BARRIER WALL SECTIONS. IN ADDITION, THE DISTRICT MAINTENANCE ENGINEER, DISTRICT THREE, SHALL RECEIVE TWO WEEKS ADVANCE NOTICE OF THE REQUIRED PICKUP & STORAGE OF THE BARRIER WALL SECTIONS AT THE DOOLY COUNTY/1-75 STORAGE FACILITY.

TO BE USED AS DIRECTED BY THE ENGINEER

NOTE: ALL MILLED ASPHALT CONCRETE PAVEMENT WILL BE AVAILABLE FOR RECYCLING. TO BE USED AS DIRECTED BY THE ENGINEER.

INSTALLATION SILT FENCE - TYPE A	
TOTAL	3000 LIN FT.

TO BE USED AT LOCATIONS SHOWN ON PLANS AND / OR AS DIRECTED BY ENGINEER.

SURFACING QUANTITIES				
ITEMS	UNIT	MAINLINE	SHOULDERS	TOTALS
RECYCL ASPH CONC 12.5 mm SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TONS		1600	1600
RECYCL ASPH CONC 19 mm SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TONS	800	400	1200
ASPH CONC 12.5 mm OGFC, GP 2 ONLY, INCL BITUM MATL & H LIME	TONS	1550	150	1700
BITUMINOUS TACK COAT	GAL	2650	1400	4050

MAINTENANCE SILT FENCE - TYPE A	
TOTAL	1500 LIN FT.

TEMPORARY GRASSING	
TOTAL	10 LBS

INDENTATION RUMBLE STRIPS	
TOTAL	3 MILES