STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	NHS-M000-00(416)	8	43

DETAILED ESTIMATE

ITEM NO.	ROADWAY ITEMS	UNIT	QUANTITY
150-1000	TRAFFIC CONTROL - NHS-M000-00(416)	LS	LUMP
150-5000	TRAFFIC CONTROL, TEMPORARY SAND LOADED ATTENUATOR MODULE	EA	36
210-0100	GRADING COMPLETE - NHS-M000-00(416)	LS	LUMP
432-5010	MILL ASPH CONC PVM'T, VARIABLE DEPTH	SY	46800
433-1300	REINF CONC APPROACH SLAB, INCL BARRIER	SY	900
441-0004	CONC SLOPE PAV, 4 IN	SY	65
441-3999	CONCRETE 'V' GUTTER	LF	495
456-2003	INDENTATION RUMBLE STRIPS, 3 FT WIDE	MILE	3
500-3402	CLASS CS CONCRETE	CY	150
610-1065	REM GUARDRAIL DBL FACE	LF	1010
611-5301	RESET GUARDRAIL DBL FACE	LF	1010
611-8040	ADJUST DROP INLET TO GRADE	EA	4
622-1031	PRECAST CONCRETE MEDIAN BARRIER, METHOD 1	LF	3100
632-0003	VARIABLE MESSAGE SIGN, PORTABLE, TYPE 3	EA	2
641-1200	GUARDRAIL, TP W	LF	150
641-5012	GUARDRAIL ANCHORAGE, TP 12	EA	1
700-6900	PERMANENT GRASSING	LBS	50
700-7000	AGRICULTURAL LIME	TN	3
700-8000	FERTILIZER MIXED GRADE	TN	1
700-8100	FERTILIZER NITROGEN CONTENT	LBS	50
	PAVEMENT		
400-3205	ASPH CONC 12.5mm OGFC, GP 2 ONLY, INCL BITUM MATL & H LIME	TN	1700
402-3112	RECY ASHP CONC 19 mm SUPERPAVE, GP 1 OR 2, INCL BITMUM MATL & H LIME	TN	1200
402-3113	RECY ASPH CONC 12.5mm SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	1600
413-1000	BITUM TACK COAT	GL	4050
	TEMPORARY EROSION CONTROL		
163-0230	TEMPORARY GRASSING	LBS	10
165-0010	MAINTENANCE OF TEMPORARY SILT FENCE, TP A	LF	1500
165-0030	MAINTENANCE OF TEMPORARY SILT FENCE, TP C	LF	75
171-0010	TEMPORARY SILT FENCE, TYPE A	LF	3000
171-0030	TEMPORARY SILT FENCE, TYPE C	LF	150
	PAVEMENT MARKINGS		
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	LF	7200
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	7200
653-3501	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN, WHITE	GLF	14400
654-1003	RAISED PAVEMENT MARKERS, TP 3	EA	180
	BRIDGE 1 LT		
211-1000	BRIDGE EXCAVATION	CY	1040
449-1620	LOW DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYLACETATE,	LF	70
	POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO 1 LT, BENT NO 1		
449-1620	LOW DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYLACETATE,	LF	70
	POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO 1 LT, BENT NO 4		
500-0100	GROOVED CONCRETE	SY	2137
500-3800	CLASS A CONCRETE, INCL REINF STEEL	CY	87
519-0401	CONCRETE OVERLAY, VARIABLE THICKNESS - FAST TRACK	SY	1758
544-1000	DECK DRAIN SYSTEM - BR NO 1 LT (11)	LS	LUMP
	BRIDGE 1 RT		
211-1000	BRIDGE EXCAVATION	CY	1040
449-1620	LOW DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	70
	POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO 1 RT, BENT NO 1		
449-1620	LOW DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYLACETATE,	LF	70
	POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO 1 RT, BENT NO 4		
500-0100	GROOVED CONCRETE	SY	2137
500-3800	CLASS A CONCRETE, INCL REINF STEEL	CY	7
519-0401	CONCRETE OVERLAY, VARIABLE THICKNESS - FAST TRACK	SY	1758
544-1000	DECK DRAIN SYSTEM - BR NO 1 RT (11)	LS	LUMP