DETAILED ESTIMATE

ITEM NO.	ROADWAY ITEMS	UNIT	QUANTITY
150-1000	TRAFFIC CONTROL - IM-M000-00(436)	LS	LUMP
150-9011	TFAFFIC CONTROL - WORKZONE LAW ENFORCEMENT	HR	1500
432-5010	MILL ASPH CONC PVMT, VARIABLE DEPTH	SY	108,500
456-2012	INDENTATION RUMBLE STRIPS - GROUND IN PLACE (CONTINUOUS)	GLM	4
622-1033	PRECAST CONCRETE MEDIAN BARRIER, METHOD 3	LF	5,650
632-0003	VARIABLE MESSAGE SIGN, PORTABLE, TYPE 3	EA	3
650-1010	GUARDRAIL IMPACT ATTENUATOR, TYPE T-3-S-30	EA	3
	PAVEMENT		
400-3206	ASPH CONC 12.5mm OGFC, GP 2 ONLY, INCL POLYMER-MODIFED	TN	2,100
	BITUM MATL & H LIME		
400-3604	RECYCLED ASPH CONC 12.5 mm SMA, GP 2 ONLY, INCL POLYMER-MODIFIED		3,050
	BITUM MATL & H LIME	TN	
402-3113	RECY ASPH CONC 12.5mm SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	10,600
413-1000	BITUM TACK COAT	GL	13,100
	PAVEMENT MARKINGS		
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	LF	8,480
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	8,480
653-1810	THERMOPLASTIC SOLID TRAF STRIPE, 10 IN, WHITE	LF	500
653-3501	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN, WHITE	GLF	18,160
654-1003	RAISED PAVEMENT MARKERS, TP 3	EA	324
657-1054	PREFORMED PLASTIC SOLID PVMT MKG, 5 IN, WHITE, TP PB	LF	2,020
657-3054	PREFORMED PLASTIC SKIP PVMT MKG, 5 IN, WHITE, TP PB	GLF	4,040
657-6054	PREFORMED PLASTIC SOLID PVMT MKG, 5 IN, YELLOW, TP PB	LF	2,020
	BRIDGE NO. 1		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	152
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 1, BENT NO - 1		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	152
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 1, BENT NO - 2		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	152
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 1, BENT NO - 3		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	153
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 1, BENT NO - 4		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	153
	POLYETHYLENE COPOLYMER NITROGEN-BLOWN SEAL, BR NO - 1, BENT NO - 5		
500-0100	GROOVED CONCRETE	SY	3565
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONC, BR NO - 1	CY	523
511-3000	SUPERSTR REINF STEEL, BR NO - 1 (116063)	LS	LUMP
519-0401	CONCRETE OVERLAY, VARIABLE THK - FAST TRACK	SY	1605
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO - 1		LUMP
	BRIDGE NO. 2		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	155
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 2, BENT NO - 1		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	155
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 2, BENT NO - 2		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	155
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 2, BENT NO - 3		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	155
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 2, BENT NO - 4		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	155
	POLYETHYLENE COPOLYMER NITROGEN-BLOWN SEAL, BR NO - 2, BENT NO - 5		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	155
	POLYETHYLENE COPOLYMER NITROGEN-BLOWN SEAL, BR NO - 2, BENT NO - 6		
500-0100	GROOVED CONCRETE	SY	3907
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONC, BR NO - 2	CY	585
511-3000	SUPERSTR REINF STEEL, BR NO - 2 (133968)	LS	LUMP
519-0401	CONCRETE OVERLAY, VARIABLE THK - FAST TRACK	SY	1758
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO - 2		LUMP
	BRIDGE NO. 3		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	211
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 3, BENT NO - 1		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	214
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 3, BENT NO - 2		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	218
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 3, BENT NO - 3		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	221
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 3, BENT NO - 4		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	225
	POLYETHYLENE COPOLYMER NITROGEN-BLOWN SEAL, BR NO - 3, BENT NO - 5		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	230
	POLYETHYLENE COPOLYMER NITROGEN-BLOWN SEAL, BR NO - 3, BENT NO - 6		
500-0100	GROOVED CONCRETE	SY	4945
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONC, BR NO - 3	CY	628
511-3000	SUPERSTR REINF STEEL, BR NO - 3 (148498)	LS	LUMP
519-0401	CONCRETE OVERLAY, VARIABLE THK - FAST TRACK	SY	2616
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO - 3		LUMP
	BRIDGE NO. 4		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	288
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 4, BENT NO - 1		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	288
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 4, BENT NO - 2		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	288
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 4, BENT NO - 3		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	288
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 4, BENT NO - 4		
500-0100	GROOVED CONCRETE	SY	3353
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONC, BR NO - 4	CY	14
511-3000	SUPERSTR REINF STEEL, BR NO - 4 (1128)	LS	LUMP
519-0401	CONCRETE OVERLAY, VARIABLE THK - FAST TRACK	SY	3427
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO - 4		LUMP

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	NHS-M000-00(436)	5	50