STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	NHS-M000-00 (436)	48	50

LOCATION	NO. OF LOC.	MARK	LENGTH FT. IN.	NO. BARS REQ'D.	TYPE	A	G	B FT. IN.	C FT. IN.	D FT. IN.	E FT. IN.	N	θ
SPAN 1	1												
		400A	34- 6	164	1								
		400B	33- 9	164	1								
		402	3- 6	76	3			2- 6	1- 0				
		403	3- 2	76	3			2- 6	0- 8				
		404	3- 3	123	34	6	6	0- 6	1- 3	1- 0	1- 3		
		405	6- 8	123	31	4	4	0- 9	2- 7	2- 7			
		406A	37- 6	2	1								
		406B	15- 6	2	1								
		406C	26- 9	2	1								
		406D	15- 6	2	1								
		500A	26- 9	246	1								
		500B	10- 9	246	1								
		500C	27- 0	240	1								
		500D	10- 9	240	1								
		800A	11-11	4	1								
		800B	13- 4	24	1								
		800C	16- 3	8	1								
		800D	12- 3	4	1								
SPAN 2	1												
		400C	35- 2	164	1								
		400D	34- 4	164	1								
		405	6- 8	246	31	4	4	0- 9	2- 7	2- 7			
		406A	38- 0	4	1								
		406B	15- 9	4	1								
		406C	38- 6	4	1								
		406D	15- 9	4	1								
		500A	26- 9	252	1								
		500B	10- 9	252	1								
		500C	27- 0	244	1								
		500D	10- 9	244	1								
		800A	12- 1	8	1								
		800B	13- 6	8	1								
		800C	16- 6	16	1								
		800D	12- 5	8	1								

LOCATION	NO. OF LOC.	MARK	LENGTH FT. IN.	NO. BARS REQ'D.	TYPE	A	G	B FT. IN.	C FT. IN.	D FT. IN.	E FT. IN.	N	θ
SPAN 3	1												
		400E	39-11	82	1								
		400F	38-10	82	1								
		405	6- 8	246	31	4	4	0- 9	2- 7	2- 7			
		406A	38- 6	4	1								
		406B	16- 0	4	1								
		406C	39- 0	4	1								
		406D	16- 0	4	1								
		500A	26- 9	148	1								
		500B	10- 9	148	1								
		500C	27- 0	144	1								
		500D	10- 9	144	1								
		800A	12- 3	8	1								
		800B	13- 8	48	1								
		800C	16- 9	8	1								
		800D	12- 7	8	1								
SPAN 4	1												
		400H	34- 4	164	1								
		405	6- 8	246	31	4	4	0- 9	2- 7	2- 7			
		406A	39- 0	4	1								
		406B	16- 3	4	1								
		406C	39- 6	4	1								
		406D	16- 3	4	1								
		500A	26- 9	252	1								
		500B	10- 9	252	1								
		500C	27- 0	246	1								
		500D	10- 9	246	1								
		800A	12- 6	8	1								
		800B	13-10	48	1								
		800C	17- 0	16	1								
		800D	12- 9	8	1								

LOCATION	NO. OF LOC.	MARK	LENGTH FT. IN.	NO. BARS REQ'D.	TYPE	A	G	B FT. IN.	C FT. IN.	D FT. IN.	E FT. IN.	N	θ
SPAN 5	1												
		400J	36- 5	164	1								
		400K	35- 4	164	1								
		402	3- 6	76	3			2- 6	1- 0				
		403	3- 2	76	3			2- 6	0- 8				
		404	3- 3	123	34	6	6	0- 6	1- 3	1- 0	1- 3		
		405	6- 8	123	31	4	4	0- 9	2- 7	2- 7			
		406A	39- 6	2	1								
		406B	16- 6	2	1								
		406C	40- 0	2	1								
		406D	16- 6	2	1								
		500A	26- 9	260	1								
		500B	10- 9	260	1								
		500C	27- 0	252	1								
		500D	10- 9	252	1								
		800A	12- 9	4	1								
		800B	14- 0	24	1								
		800C	17- 4	8	1								
		800D	12-11	4	1								

BRIDGE NO. 3 LT & RT

JBT J.B. Trimble, Inc.
6445 Powers Ferry Road
Atlanta GA 30339-2933
(770) 952-1022

GEORGIA
DEPARTMENT OF TRANSPORTATION
OPERATIONS DIVISION-OFFICE OF MAINTENANCE

DISTRICT 6 BRIDGE REPAIRS (DECK REHABILITATION)
I-75 OVER CSXT
AND WILLOWDALE RD.

WHITFIELD COUNTY NHS-M000-00 (436)

SCALE: AS SHOWN AUGUST 2001

DESIGNED PJC CHECKED GLE REVIEWED EHG
DRAWN ITD DESIGN GROUP MAINTENANCE APPROVED STH

DATE | REVISIONS | BY

GEORGIA REGISTERED No. 16685 PROFESSIONAL ENGINEER
10-09-01

BRIDGE SHEET 7 OF 7

C:\DGN\2019\CT3\B0L3-3BS.DGN 5-22-01 ITD