STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	NHS-M000-00(437)	5	52

DETAILED ESTIMATE

ITEM NO.	ROADWAY ITEMS	UNIT	QUANTITY
150-1000	TRAFFIC CONTROL - NHS-M000-00(437)	LS	LUMP
150-9011	TRAFFIC CONTORL - WORKZONE LAW ENFORCEMENT	HR	1500
210-0100	GRADING COMPLETE - NHS-M000-00(437)	LS	LUMP
310-1101	GR AGGR BASE CRS, INCL MATL	TN	250
400-3604	ASPH CONC 12.5 MM SMA, GP 2 ONLY, INCL POLYMER-MODIFIED	TN	4200
	BITUM MATL & H LIME		
400-3624	APSH CONC 12.5 MM PEM, GP 2 ONLY, INCL POLYMER-MODIFIED	TN	3700
	BITUM MATL & H LIME		
402-3112	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM & H LIME	TN	60
402-3113	RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 1 OR 2, INCL BITUM & H LIME	TN	12200
402-3121	RECYCLED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2, INCL BITUM & H LIME	TN	125
413-1000	BITUM TACK COAT	GL	16500
432-5010	MILL ASPH CONC PVMT, VARIABLE DEPTH	SY	132000
456-2012	INDENTATION RUMBLE STRIPS - GROUND IN PLACE (CONTINUOUS)	MI	5
622-1033	PRECAST CONCRETE MEDIAN BARRIER, METHOD 3	LF	8900
632-0003	VARIBLE MESSAGE SIGN, PORTABLE, TYPE 3	EA	4
641-4020	DBL FACED GUARDRAIL, TP W	LF	1600
641-5001	GUARDRAIL ANCHORAGE, TP 1	EA	1
641-5012	GUARDRAIL ANCHORAGE, TP 12	EA	1
641-9912	TEMPORARY GUARDRAIL ANCHORAGE, TP 12	EA	1
650-1010	GUARDRAIL IMPACT ATTENUATOR, TYPE T-3-S-30	EA	6
	PERMANENT EROSION CONTROL		
700-6910	PERMANENT GRASSING	AC	1
700-7000	AGRICULTURAL LIME	TN	3
700-8000	FERTILIZER MIXED GRADE	TN	1
700-8100	FERTILIZER NITROGEN CONTENT	LB	50
	TEMPORARY EROSION CONTROL		
163-0232	TEMPORARY GRASSING	AC	1
163-0240	MULCH	TN	2
165-0010	MAINTAENANCE OF TEMPORARY SILT FENCE, TP A	LF	500
171-0010	TEMPORARY SILT FENCE, TYPE A	LF	1000
	SIGNING & MARKING		
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	LF	13450
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	13450
653-1810	THERMOPLASTIC SOLID TRAF STRIPE, 10 IN, WHITE	LF	200
653-3501	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN, WHITE	GLF	27900
654-1003	RAISED PVMT MARKERS TP 3	EA	375
657-1054	PREFORMED PLASTIC SOLID PVMT MKG, 5 IN, WHITE, TP PB	LF	1532
657-3054	PREFORMED PLASTIC SKIP PVMT MKG, 5 IN, WHITE, TP PB	GLF	3228
657-6054	PREFORMED PLASTIC SOLID PVMT MKG, 5 IN, YELLOW, TP PB	LF	1532
	BRIDGE NO. 1		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	160
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 1, BENT NO - 1		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	160
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 1, BENT NO - 2		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	160
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 1, BENT NO - 3		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	160
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 1, BENT NO - 4		
500-0100	GROOVED CONCRETE	SY	1878
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONC, BR NO - 1	CY	10
511-3000	SUPERSTR REINF STEEL, BR NO - 1 (547)	LS	LUMP
519-0401	CONCRETE OVERLAY, VARIABLE THK - FAST TRACK	SY	1907
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO - 1	LS	LUMP
	BRIDGE NO. 2		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	165
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 2, BENT NO - 1		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	165
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 2, BENT NO - 2		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	165
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 2, BENT NO - 3		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	165
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 2, BENT NO - 4		
500-0100	GROOVED CONCRETE	SY	2627
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONC, BR NO - 2	CY	325
511-3000	SUPERSTR REINF STEEL, BR NO - 2 (76820)	LS	LUMP
519-0401	CONCRETE OVERLAY, VARIABLE THK - FAST TRACK	SY	1462
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO - 2	LS	LUMP
	BRIDGE NO. 3		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	159
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 3, BENT NO - 1		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	159
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 3, BENT NO - 2		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	159
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 3, BENT NO - 3		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	159
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 3, BENT NO - 4		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	159
	POLYETHYLENE COPOLYMER NITROGEN-BLOWN SEAL, BR NO - 3, BENT NO - 5		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	159
	POLYETHYLENE COPOLYMER NITROGEN-BLOWN SEAL, BR NO - 3, BENT NO - 6		
500-0100	GROOVED CONCRETE	SY	4360
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONC, BR NO - 3	CY	77
511-3000	SUPERSTR REINF STEEL, BR NO - 3 (14429)	LS	LUMP
519-0401	CONCRETE OVERLAY, VARIABLE THK - FAST TRACK	SY	4373
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO - 3	LS	LUMP
	BRIDGE NO. 4		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	159
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 4, BENT NO - 1		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	159
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 4, BENT NO - 2		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	159
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 4, BENT NO - 3		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	159
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 4, BENT NO - 4		
500-0100	GROOVED CONCRETE	SY	2547
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONC, BR NO - 4	CY	328
511-3000	SUPERSTR REINF STEEL, BR NO - 4 (72764)	LS	LUMP
519-0401	CONCRETE OVERLAY, VARIABLE THK - FAST TRACK	SY	1311
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO - 4	LS	LUMP