STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	NHS-M000-00(438)	6	

TEMPORARY EROSION CONTROL QUANTITIES

LOCATION STATION	SILT FENCE TYPE "A"	MAINT.	SILT FENCE TYPE "B"	MAINT.	SILT CONTROL GATE, TP. 1	MAINT.	SILT CONTROL GATE, TP. 2	MAINT.	SILT CONTROL GATE, TP. 3	MAINT.
	LF	LF	LF	LF	EACH	EACH	EACH	EACH	EACH	EACH
DECEL. LANE	78	39	568	284	2	2	1	1	1	1
ACCEL. LANE	452	226	1874	937						
NHS-M000-00(438) TOTAL	530	265	2442	1221	2	2	1	1	1	1

BALED STRAW EROSION CHECKS

	CONST & REMOVE (LF)	MAINTENANCE (LF)
NHS-M000-00(438)	400	200

UNDERDRAIN PIPE

INCL. DRAINAGE AGGREGATE, 6 INCH

NHS-M000-00(438)	400	LF

TEMPORARY PIPE SLOPE DRAIN

NHS-M000-00(438)	400	LF

NOTE: CONSTRUCT AND REMOVE TEMPORARY PIPE SLOPE DRAINS

GRASSING

LOCATION	PERMANENT GRASSING	AGRICULTURAL LIME	LIQUID LIME	FERTILIZER MIXED GRADE	FERTILIZER NITROGEN CONTENT
	AC.	TON	GALLONS	TON	LB
DECEL. LANE	1.2	4	3	1	37
ACCEL. LANE	0.7	2	2	1	22
NHS-M000-00(438) TOTAL	1.9	6	5	2	59

LIGHTING STANDARD

LOCATION	REMOVE	RESET
	EACH	EACH
DECEL. LANE	1	1
NHS-M000-00(438) TOTAL	1	1

ASPHALTIC CONCRETE CURB

6 INCH *

LOCATION	LF
NHS-M000-00(438)	600

* TO BE USED AS DIRECTED BY ENGINEER

METAL DRAIN INLET

COMPLETE ASSEMBLY *

LOCATION	EA
NHS-M000-00(438)	2

* TO BE USED AS DIRECTED BY ENGINEER

TEMPORARY GRASSING

LOCATION	AC.
DECEL. LANE	0.6
ACCEL. LANE	0.4
NHS-M000-00(438) TOTAL	1.0

AVI SYSTEM-TRUCK WEIGHING STATION

NHS-M000-00(438)	LUMP SUM

VARIABLE MESSAGE SIGN, PORTABLE, TYPE 3

LOCATION	EACH
NHS-M000-00(438)	2

SLOPE PROTECTION

LOCATION	EROSION CONTROL MATS, SLOPES
	SQ YD
DECEL. LANE	2372
ACCEL. LANE	2025
NHS-M000-00(438) TOTAL	4397

MULCH

LOCATION	TON
DECEL. LANE	37
ACCEL. LANE	22
NHS-M000-00(438) TOTAL	59

PERMANENT CHANGEABLE MESSAGE SIGN, PERM., ONE LINE MATRIX, TP1, 18"

LOCATION	EACH
DECEL. LANE	
STA 30+45	1
NHS-M000-00(438) TOTAL	1

PBSJ

DATE	REVISIONS	DATE	REVISIONS

GEORGIA
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

H:\t060327\M000438\Dgn\000438q02.dgn

10-JUN-2002