ITEM NO.	ITEM	UNIT	QUANTITY
	ROADWAY ITEMS		
150-1000	TRAFFIC CONTROL - PROJECT NO. NHS-M000-00(438)	LUMP	LUMP
153-1300	FIELD ENGINEERS OFFICE TP 3	EA	1
210-0100	GRADING COMPLETE - PROJECT NO. NHS-M000-00(438)	LUMP	LUMP
310-1101	GR AGGR BASE CRS, INCL MATL	TN	8800
400-3624	ASPH CONC 12.5 mm PEM, GP2 ONLY, INCL. POLYMER-MOD BITUM MATL & H LIME	TN	480
402-1802	RECYCLED ASPH CONC PATCHING, INCL BITUM MATL & H LIME	TN	150
402-3121	RECYCLED ASPH CONC 25 mm SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	4700
402-3130	RECYCLED ASPH CONC 12.5 mm SUPERPAVE, GP 2 ONLY, INCL BITUM MATL & H LIME	TN	1600
402-3190	RECYCLED ASPH CONC 19 mm SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	2100
407-0010	ASPHALT - RUBBER JOINT AND CRACK SEAL, TP M	LF	5300
413-1000	BITUM TACK COAT	GL	2100
432-5010	MILL ASPH CONC PVMT, VARIABLE DEPTH	SY	590
436-1000	ASPHALT CONCRETE CURB, 6 IN	LF	600
441-0204	PLAIN CONC DITCH PAVING, 4 IN	SY	1600
441-0303	CONC SPILLWAY, TP 3	EA	2
446-1002	PVMT REINF FABRIC STRIPS, TP 2, INCL BITUM BINDER	LF	5300
456-2012	INDENTATION RUMBLE STRIPS - GROUND-IN-PLACE	GLM	1[illegible]
550-1150	STORM DRAIN PIPE, 15 IN, H 1-10	LF	8
550-1240	STORM DRAIN PIPE, 24 IN, H 1-10	LF	8
550-4215	FLARED END SECTION 15 IN, STORM DRAIN	EA	1
550-4224	FLARED END SECTION 24 IN, STORM DRAIN	EA	2
573-2006	UNDDR PIPE INCL DRAINAGE AGGR, 6 IN	LF	400
577-1100	METAL DRAIN INLET - COMPLETE ASSEMBLY	EA	2
610-6605	REM LIGHTING STANDARD	EA	1
611-5480	RESET LIGHTING STANDARD	EA	1
621-4021	CONCRETE SIDE BARRIER, TYPE 2A	LF	1800
621-4022	CONCRETE SIDE BARRIER, TYPE 2B	LF	1100
621-4082	CONCRETE SIDE BARRIER, TYPE 7T	LF	60
632-0003	VARIABLE MESSAGE SIGN, PORTABLE, TYPE 3	EA	2
641-1100	GUARDRAIL, TP T	LF	94
641-1200	GUARDRAIL, TP W	LF	2100
641-5001	GUARDRAIL ANCHORAGE, TP 1	EA	2
641-5006	GUARDRAIL ANCHORAGE, TP 6	EA	1
641-5012	GUARDRAIL ANCHORAGE, TP 12	EA	3
	EROSION CONTROL		
163-0232	TEMPORARY GRASSING	AC	1
163-0240	MULCH	TN	59
163-0501	CONSTRUCT AND REMOVE SILT CONTROL GATE, TP 1	EA	2
163-0502	CONSTRUCT AND REMOVE SILT CONTROL GATE, TP 2	EA	1
163-0503	CONSTRUCT AND REMOVE SILT CONTROL GATE, TP 3	EA	1
163-0520	CONSTRUCT AND REMOVE TEMPORARY PIPE SLOPE DRAIN	LF	400
163-0530	CONSTRUCT AND REMOVE BALED STRAW EROSION CHECK	LF	400
165-0010	MAINTENANCE OF TEMPORARY SILT FENCE, TYPE A	LF	270
165-0020	MAINTENANCE OF TEMPORARY SILT FENCE, TYPE B	LF	1300
165-0070	MAINTENANCE OF BALED STRAW EROSION CHECK	LF	200
165-0085	MAINTENANCE OF SILT CONTROL GATE, TP I	EA	2
165-0086	MAINTENANCE OF SILT CONTROL GATE, TP II	EA	1
165-0087	MAINTENANCE OF SILT CONTROL GATE, TP III	EA	1
167-0100	WATER QUALITY MONITORING	MO	12
167-0200	WATER QUALITY SAMPLING	EA	24
171-0010	TEMPORARY SILT FENCE, TYPE A	LF	530
171-0020	TEMPORARY SILT FENCE, TYPE B	LF	2500
603-2181	STN DUMPED RIP RAP, TP 3, 18 IN	SY	110
603-7000	PLASTIC FILTER FABRIC	SY	110
700-6910	PERMANENT GRASSING	AC	2
700-7000	AGRICULTURAL LIME	TN	6
700-7010	LIQUID LIME	GL	5
700-8000	FERTILIZER MIXED GRADE	TN	2
700-8100	FERTILIZER NITROGEN CONTENT	LB	59
715-2200	BITUMINOUS TREATED ROVING, WATERWAYS	SY	590
716-2000	EROSION CONTROL MATS, SLOPES	SY	4400
	SIGNING & MARKING		
610-6515	REM HIGHWAY SIGN, STD	EA	1
610-6520	REMOVE HIGHWAY SIGN, SPCL ROADSIDE	EA	3
611-5551	RESET SIGN	EA	4
631-0005	PERMANENT CHANGEABLE MESSAGE SIGN, PERM. ONE LINE MATRIX, TP1, 18"	EA	1
636-1020	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP3	SF	8
636-1029	HIGHWAY SIGNS, TP 2 MATL, REFL SHEETING, TP3	SF	130
636-2030	GALV STEEL POSTS, TP 3	LF	60
636-2040	GALV STEEL POSTS, TP 4	LF	30
636-5010	DELINEATORS, TP 1	EA	12
636-5020	DELINEATORS, TP 2	EA	56
653-0291	THERMOPLASTIC PVMT MARKING, WORD, TP 10	EA	1
653-1501	THERMOPLASTIC SOLID TRAFFIC STRIPE, 5 IN, WHITE	LF	8200
653-1810	THERMOPLASTIC SOLID TRAFFIC STRIPE, 10 IN, WHITE	LF	280
653-3501	THERMOPLASTIC SKIP TRAFFIC STRIPE, 5 IN, WHITE	GLF	1900
654-1003	RAISED PVMT MARKERS TP 3	EA	69
656-0050	REMOVE EXIST. SOLID TRAF. STRIPE, 5 IN, THERMOPLASTIC	LF	5100
	AVI SYSTEMS		
692-1000	AUTOMATIC VEHICLE IDENTIFICATION SYSTEM	LUMP	LUMP

GENERAL NOTES

1. THE PROJECT LIES WITHIN THE AREA INFESTED BY THE IMPORTED FIRE ANT. THE CONTRACTOR SHALL CONDUCT OPERATIONS IN ACCORDANCE WITH SECTION 155.
2. THE WEIGH STATION MAY BE CLOSED FOR A PEROID OF ONE (1) WEEK MAXIMUM.
3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY SIGNING DURING WEIGH STATION CLOSURE.
4. CLEARING LIMITS ARE TO BE 10' BEYOND FILL SLOPES, 5' BEYOND CUT SLOPES, AND AS DIRECTED BY ENGINEER FOR CONDUIT ROUTING.

PROJECT SPECIFIC NOTES

1. THE CONTRACTOR IS RESPONSIBLE FOR CONTACTING THE UPC ONE-CALL CENTER AT 1-800-282-7411 PRIOR TO THE START OF WORK FOR THE VERIFICATION OF EXISTING UTILITIES.
2. THERE IS NO SUITABLE PLACE FOR DISPOSAL OF THE REMOVED SLABS WITHIN THE PROJECT LIMITS.
3. LOADING AND UNLOADING OF MATERIALS/EQUIPMENT MUST BE MAINTAINED WITHIN THE PROJECT LIMITS. NO EQUIPMENT OR MATERIALS WILL BE ALLOWED IN THE WEIGH STATION AREAS.
4. A N.O.I. IS REQUIRED FOR THIS PROJECT.

UTILITY OWNERS	
NAME	SERVICE
DALTON UTILITIES	WATER
Contact - Emory DeBord	
Phone - 706-281-1081	
	SEWER
NORTH GA EMC	ELECTRIC
Contact - Keith Queen	
Phone - 706-259-9441	
	GAS
	CABLE TV
RINGGOLD TELEPHONE	TELEPHONE
Contact - Kevin Hill	
Phone - 706-965-2345	

PBS&J

DATE	REVISIONS	DATE	REVISIONS	LAND LOT NO.
				LAND DISTRICT
				GMD

GEORGIA DEPARTMENT OF TRANSPORTATION

DETAILED ESTIMATE

I-75 CATOOSA COUNTY WEIGH STATION, SOUTHBOUND DECEL/ACCEL

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA	NHS-M000-001(438)	10	

REVISED 8-30-02