STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	NHS-M000-00(458)	5	

SUMMARY OF PAVING QUANTITIES

LOCATION	GRADED AGGREGATE BASE COURSE, INCL. MAT'L	ASPHALTIC CONC. 12.5 mm PEM, GP 2 ONLY INCL. POLYMER-MODIFIED BITUM. MAT'L & H. LIME	RECYCLED ASPH. CONC. 12.5 mm SUPERPAVE, GP 2 ONLY INCL. BITUM. MAT'L & H. LIME	RECYCLED ASPH. CONC. 19 mm SUPERPAVE, GP 1 OR 2 INCL. BITUM. MAT'L & H. LIME	RECYCLED ASPH. CONC. 25 mm SUPERPAVE, GP 1 OR 2 INCL. BITUM. MAT'L & H. LIME	BITUM. TACK COAT	MILL ASPHALTIC CONC. PVMT., 2 IN. DEPTH	PVMT. REINF. FABRIC STRIPS, TP. 2, INCL. BITUM. BINDER	ASPHALT - RUBBER JOINT AND CRACK SEAL, TP M	INDENTATION RUMBLE STRIPS GROUND-IN-PLACE (CONTINUOUS)	UNDER GUARDRAIL PVMT			
											GRADED AGGREGATE BASE COURSE, INCL. MAT'L	RECYCLED ASPH. CONC. 12.5 mm SUPERPAVE, GP 2 ONLY INCL. BITUM. MAT'L & H. LIME	RECYCLED ASPH. CONC. 19 mm SUPERPAVE, GP 1 OR 2 INCL. BITUM. MAT'L & H. LIME	BITUM. TACK COAT
	TONS	TONS	TONS	TONS	TONS	GAL	SY	LF	LF	GLM	TONS	TONS	TONS	GAL
NB DECEL. LANE	3000	228	470	610	1210	730	255	2250	2250	0.43	60	18	24	13
SB DECEL. LANE	2980	228	465	605	1205	725	255	2250	2250	0.43	140	42	56	32
NHS-M000-00(458) TOTAL	5980	456	935	1215	2415	1455	510	4500	4500	0.86	200	60	80	45

GRADING COMPLETE

NHS-M000-00(458)	LUMP

TRAFFIC CONTROL

NHS-M000-00(458)	LUMP SUM

FIELD ENGINEER'S OFFICE - TYPE 3

NHS-M000-00(458)	1	EACH

GUARDRAIL

GA. STDS. 4010, 4011-A, 4012-C, 4012-D, 4013-B, 4040, 4051, 4052, 4056, & 4270

LOCATION (STATION)	"W" BEAM	"T" BEAM	TYPE 1 ANCHOR GA. STD. 4012-D	TYPE 6 ANCHOR GA. STD. 4013-B	TYPE 12 ANCHOR GA. STD. 4040
	LF	LF	EACH	EACH	EACH
NB DECEL. LANE	175		1		1
SB DECEL. LANE	650		2		2
NHS-M000-00(458) TOTAL	825		3		3

PULL BOXES

LOCATION	PULL BOX TP 2
NB DECEL. LANE	5
NHS-M000-00(458) TOTAL	5

RECYCLED ASPH. CONC. PATCHING, INCL. BITUM. MAT'L. & H LIME*

NHS-M000-00(458)	150 TONS

* TO BE USED AS DIRECTED BY ENGINEER

LIGHTING STANDARD

LOCATION	REMOVE EACH	RESET EACH
NB DECEL. LANE	1	1
SB DECEL. LANE	1	1
NHS-M000-00(458) TOTAL	2	2

CONDUIT

LOCATION	NONMETAL	RIGID
NB DECEL. LANE	5200	100
NHS-M000-00(458) TOTAL	5200	100

ASPHALTIC CONCRETE CURB

6 INCH *

LOCATION	LF
NHS-M000-00(458)	400

* TO BE USED AS DIRECTED BY ENGINEER

CHANGEABLE MESSAGE SIGN, PORTABLE, TYPE 3

LOCATION	EACH
NHS-M000-00(458)	2

PBS&J

DATE	REVISIONS

STATE OF GEORGIA
DEPARTMENT
OF
TRANSPORTATION
OFFICE OF MAINTENANCE

GEORGIA
DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

I-75 MONROE COUNTY WEIGH STATION, DECELERATION LANES

28-JAN-2003 h:\t060328\M000458\Dgn\000458q01.dgn