ITEM NO.	ITEM	UNIT	QUANTITY
	ROADWAY ITEMS		
150-1000	TRAFFIC CONTROL - PROJECT NO. NHS-M000-00(458)	LUMP	LUMP
153-1300	FIELD ENGINEERS OFFICE TP 3	EA	1
207-0203	FOUND BACKFILL MATL, TP II	CY	3
210-0100	GRADING COMPLETE - PROJECT NO. NHS-M000-00(458)	LUMP	LUMP
310-1101	GR AGGR BASE CRS, INCL MATL	TN	6200
400-3624	ASPH CONC 12.5 mm PEM, GP2 ONLY, INCL. POLYMER-MOD BITUM MATL & H LIME	TN	460
402-1802	RECYCLED ASPH CONC PATCHING, INCL BITUM MATL & H LIME	TN	150
402-3121	RECYCLED ASPH CONC 25 MM SUPERPAVE BASE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	2500
402-3130	RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 2 ONLY, INCL BITUM MATL & H LIME	TN	1000
402-3190	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR GP 2, INCL BITUM MATL & H LIME	TN	1300
407-0010	ASPHALT - RUBBER JOINT AND CRACK SEAL, TP M	LF	4500
413-1000	BITUM TACK COAT	GL	1500
432-0208	MILL ASPH CONC PVMT, 2 IN DEPTH	SY	510
436-1000	ASPHALT CONCRETE CURB, 6 IN	LF	400
441-0204	PLAIN CONC DITCH PAVING, 4 IN	SY	20
446-1002	PVMT REINF FABRIC STRIPS, TP 2, INCL BITUM BINDER	LF	4500
456-2012	INDENTATION RUMBLE STRIPS, GROUND-IN-PLACE (CONTINUOUS)	GLM	1
500-3800	CLASS A CONCRETE, INCL REINF STEEL	CY	5
550-1150	STORM DRAIN PIPE, 15 IN, H 1-10	LF	9
550-1180	STORM DRAIN PIPE, 18 IN, H 1-10	LF	10
550-1480	STORM DRAIN PIPE, 48 IN, H 1-10	LF	12
550-3318	SAFETY END SECTION 18 IN, STORM DRAIN, 4:1 SLOPE	EA	1
550-4215	FLARED END SECTION 15 IN, STORM DRAIN	EA	1
573-2006	UNDDR PIPE INCL DRAINAGE AGGR, 6 IN	LF	400
610-6605	REM LIGHTING STANDARD	EA	2
611-5480	RESET LIGHTING STANDARD	EA	2
632-0003	CHANGEABLE MESSAGE SIGN, PORTABLE, TYPE 3	EA	2
641-1200	GUARDRAIL, TP W	LF	825
641-5001	GUARDRAIL ANCHORAGE, TP 1	EA	3
641-5012	GUARDRAIL ANCHORAGE, TP 12	EA	3
647-2120	PULL BOX, PB-2	EA	5
682-6120	CONDUIT, RIGID, 2 IN	LF	100
682-6222	CONDUIT, NONMETL, TP 2, 2 IN	LF	5200
	EROSION CONTROL		
163-0232	TEMPORARY GRASSING	AC	2
163-0240	MULCH	TN	64
163-0503	CONSTRUCT AND REMOVE SILT CONTROL GATE, TP 3	EA	1
163-0520	CONSTRUCT AND REMOVE TEMPORARY PIPE SLOPE DRAIN	LF	400
163-0530	CONSTRUCT AND REMOVE BALED STRAW EROSION CHECK	LF	1100
165-0020	MAINTENANCE OF TEMPORARY SILT FENCE, TYPE B	LF	1450
165-0070	MAINTENANCE OF BALED STRAW EROSION CHECK	LF	550
165-0087	MAINTENANCE OF SILT CONTROL GATE, TP 3	EA	1
167-0100	WATER QUALITY MONITORING	MO	12
167-0200	WATER QUALITY SAMPLING	EA	24
171-0020	TEMPORARY SILT FENCE, TYPE B	LF	2900
603-2181	STN DUMPED RIP RAP, TP 3, 18 IN	SY	24
603-7000	PLASTIC FILTER FABRIC	SY	24
700-6910	PERMANENT GRASSING	AC	3
700-7000	AGRICULTURAL LIME	TN	16
700-7010	LIQUID LIME	GL	8
700-8000	FERTILIZER MIXED GRADE	TN	3
700-8100	FERTILIZER NITROGEN CONTENT	LB	260
716-2000	EROSION CONTROL MATS, SLOPES	SY	2000
	SIGNING & MARKING		
610-6520	REMOVE HIGHWAY SIGN, SPCL ROADSIDE	EA	5
611-5551	RESET SIGN	EA	5
631-0005	PERMENANT CHANGEBLE MESSAGE SIGN, PERM. ONE LINE MATRIX, TP 1, 18"	EA	2
636-1020	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP3	SF	32
636-1029	HIGHWAY SIGNS, TP 2 MATL, REFL SHEETING, TP3	SF	40
636-2070	GALV STEEL POSTS, TP 7	LF	96
636-2080	GALV STEEL POSTS, TP 8	LF	48
636-3010	GROUND-MOUNTED BREAKAWAY SIGN SUPPORT	EA	4
636-5020	DELINEATORS, TP 2	EA	46
653-1501	THERMOPLASTIC SOLID TRAFFIC STRIPE, 5 IN, WHITE	LF	8500
653-1810	THERMOPLASTIC SOLID TRAFFIC STRIPE, 10 IN, WHITE	LF	95
653-3501	THERMOPLASTIC SKIP TRAFFIC STRIPE, 5 IN, WHITE	GLF	500
654-1003	RAISED PVMT MARKERS TP 3	EA	62
	AVI SYSTEMS		
692-1000	AUTOMATIC VEHICLE IDENTIFICATION SYSTEM, NORTHBOUND	LUMP	LUMP
692-1000	AUTOMATIC VEHICLE IDENTIFICATION SYSTEM, SOUTHBOUND	LUMP	LUMP

GENERAL NOTES

1. THE PROJECT LIES WITHIN THE AREA INFESTED BY THE IMPORTED FIRE ANT. THE CONTRACTOR SHALL CONDUCT OPERATIONS IN ACCORDANCE WITH SECTION 155.

PROJECT SPECIFIC NOTES

1. THE CONTRACTOR IS RESPONSIBLE FOR CONTACTING THE UPC ONE-CALL CENTER AT 1-800-282-7411 PRIOR TO THE START OF WORK FOR THE VERIFICATION OF EXISTING UTILITIES.
2. THE PROJECT IS LOCATED 100 PERCENT WITHIN CONGRESSIONAL DISTRICT NO. 3.
3. THE PROJECT IS LOCATED 100 PERCENT WITHIN MONROE COUNTY.
4. THERE IS NO SUITABLE PLACE FOR DISPOSAL OF THE REMOVED SLABS WITHIN THE PROJECT LIMITS.
5. A N.O.I. IS REQUIRED FOR THIS PROJECT.

UTILITY OWNERS	
NAME	SERVICE
CITY OF FORSYTH	WATER
	SEWER
	ELECTRIC
	GAS
	CABLE TV
	TELEPHONE

PBS&J

DATE	REVISIONS	DATE	REVISIONS

STATE OF GEORGIA
DEPARTMENT
OF
TRANSPORTATION
OFFICE OF MAINTENANCE

GEORGIA
DEPARTMENT OF TRANSPORTATION
DETAILED ESTIMATE
I-75 MONROE COUNTY WEIGH
STATION, DECELERATION LANES

REVISED 3-4-03

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	NHS-M000-00(458)	9	