DETAILED ESTIMATE

ITEM NO.	ITEM	UNIT	QUANTITY
150-1000	TRAFFIC CONTROL - PROJECT NO NHS-M000-00 (863)	LUMP	LUMP
632-0003	CHANGEABLE MESSAGE SIGN, PORTABLE, TYPE 3	EA	1
	BRIDGE NO. 1		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 1, BENT NO - 1	LF	45
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 1, BENT NO - 2	LF	45
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 1, BENT NO - 4	LF	45
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 1, BENT NO - 5	LF	45
500-0100	GROOVED CONCRETE	SY	1311
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONCRETE, BR NO - 1	CY	22
511-3000	SUPERSTR REINF STEEL, BR NO - 1 (3500)	LS	LUMP
519-0401	CONCRETE OVERLAY, VARIABLE THK - FAST TRACK	SY	1311
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO - 1	LS	LUMP
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	LF	578
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	578
	BRIDGE NO. 2		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 2, BENT NO - 1	LF	45
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLUMER, NITROGEN-BLOWN SEAL, BR NO - 2, BENT NO - 2	LF	45
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 2, BENT NO - 4	LF	45
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 2, BENT NO - 5	LF	45
500-0100	GROOVED CONCRETE	SY	1279
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONCRETE, BR NO - 2	CY	22
511-3000	SUPERSTR REINF STEEL, BR NO - 2 (3500)	LS	LUMP
519-0401	CONCRETE OVERLAY, VARIABLE THK - FAST TRACK	SY	1279
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO - 2	LS	LUMP
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	LF	564
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	564

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	NHS-M000-00(863)	3	9

JBT J.B. Trimble, Inc.
6445 Powers Ferry Road
Atlanta GA 30339-2933
(770) 952-1022

GEORGIA
DEPARTMENT OF TRANSPORTATION
OPERATIONS DIVISION-OFFICE OF MAINTENANCE

DISTRICT 2 BRIDGE REPAIRS (DECK OVERLAY)

DETAILED ESTIMATE

NHS-M000-00 (863)

SCALE: AS SHOWN APRIL 2002

BY	REVISIONS	DATE

GEORGIA REGISTERED No. 19545 PROFESSIONAL ENGINEER SAMUEL L. POWELL, JR.
05-24-02

DESIGNED MDT	CHECKED GLE	REVIEWED EHG
DRAWN ITD	DESIGN GROUP MAINTENANCE	APPROVED STH

C:\DGN\2019\CT9\BOL9- DE.DGN 10-3-01 ITD