STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	STP-M000-00 (864)	3	26

DETAILED ESTIMATE

ITEM NO.	ITEM	UNIT	QUANTITY
150-1000	TRAFFIC CONTROL - PROJECT NO. STP-M000-00 (864)	LS	LUMP
632-0003	CHANGEABLE MESSAGE SIGN, PORTABLE, TYPE 3	EA	4
	BRIDGE NO. 1		
449-1620	LOW-DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO-1, BENT NO-1	LF	60
449-1620	LOW-DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO-1, BENT NO-2	LF	60
449-1620	LOW-DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO-1, BENT NO-3	LF	60
449-1620	LOW-DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO-1, BENT NO-4	LF	60
500-0100	GROOVED CONCRETE	SY	877
504-0600	TWENTY FOUR HOUR ACCELERATED STRENGHT CONCRETE, BR NO-1	CY	10
511-3000	SUPERSTR REINF STEEL, BR NO-1 (600)	LS	LUMP
519-0401	CONCRETE OVERLAY, VARIABLE THK-FAST TRACK	SY	877
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO-1	LS	LUMP
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN WHITE	LF	306
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN YELLOW	LF	306
653-3501	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN WHITE	GLF	306
654-1001	RAISED PVMT MARKERS TP 1	EA	6
	BRIDGE NO. 2		
449-1620	LOW-DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO-2, BENT NO-1	LF	72
449-1620	LOW-DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO-2, BENT NO-2	LF	72
449-1620	LOW-DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO-2, BENT NO-4	LF	72
449-1620	LOW-DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO-2, BENT NO-5	LF	72
500-0100	GROOVED CONCRETE	SY	1590
504-0600	TWENTY FOUR HOUR ACCELERATED STRENGHT CONCRETE, BR NO-2	CY	13
511-3000	SUPERSTR REINF STEEL, BR NO-2 (700)	LS	LUMP
519-0401	CONCRETE OVERLAY, VARIABLE THK-FAST TRACK	SY	1590
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO-2	LS	LUMP
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN WHITE	LF	450
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN YELLOW	LF	450
653-3501	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN WHITE	GLF	675
654-1001	RAISED PVMT MARKERS TP 1	EA	12
	BRIDGE NO. 3		
449-1620	LOW-DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO-3, BENT NO-1	LF	72
449-1620	LOW-DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO-3, BENT NO-2	LF	72
449-1620	LOW-DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO-3, BENT NO-3	LF	72
449-1620	LOW-DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO-3, BENT NO-4	LF	72
500-0100	GROOVED CONCRETE	SY	798
504-0600	TWENTY FOUR HOUR ACCELERATED STRENGHT CONCRETE, BR NO-3	CY	13
511-3000	SUPERSTR REINF STEEL, BR NO-3 (700)	LS	LUMP
519-0401	CONCRETE OVERLAY, VARIABLE THK-FAST TRACK	SY	798
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO-3	LS	LUMP
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN WHITE	LF	226
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN YELLOW	LF	226
653-3501	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN WHITE	GLF	339
654-1001	RAISED PVMT MARKERS TP 1	EA	9
	BRIDGE NO. 4		
449-1620	LOW-DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO-4, BENT NO-1	LF	78
449-1620	LOW-DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO-4, BENT NO-2	LF	74
449-1620	LOW-DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO-4, BENT NO-4	LF	72
449-1620	LOW-DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO-4, BENT NO-5	LF	72
500-0100	GROOVED CONCRETE	SY	1600
504-0600	TWENTY FOUR HOUR ACCELERATED STRENGHT CONCRETE, BR NO-4	CY	14
511-3000	SUPERSTR REINF STEEL, BR NO-4 (800)	LS	LUMP
519-0401	CONCRETE OVERLAY, VARIABLE THK-FAST TRACK	SY	1600
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO-4	LS	LUMP
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN WHITE	LF	444
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN YELLOW	LF	444
653-3501	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN WHITE	GLF	666
654-1001	RAISED PVMT MARKERS TP 1	EA	12

ITEM NO.	ITEM	UNIT	QUANTITY
	BRIDGE NO. 5		
449-1620	LOW-DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO-5, BENT NO-1	LF	60
449-1620	LOW-DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO-5, BENT NO-2	LF	60
449-1620	LOW-DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO-5, BENT NO-3	LF	60
443-1000	ELASTOMERIC PROFILE BRIDGE JOINT SEALS BR NO-5, BENT NO-4	EA	2
443-1000	ELASTOMERIC PROFILE BRIDGE JOINT SEALS BR NO-5, BENT NO-7	EA	2
443-1000	ELASTOMERIC PROFILE BRIDGE JOINT SEALS BR NO-5, BENT NO-10	EA	2
449-1620	LOW-DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO-5, BENT NO-11	LF	60
449-1620	LOW-DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO-5, BENT NO-12	LF	61
449-1620	LOW-DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO-5, BENT NO-13	LF	71
449-1620	LOW-DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO-5, BENT NO-14	LF	81
500-0100	GROOVED CONCRETE	SY	7040
504-0600	TWENTY FOUR HOUR ACCELERATED STRENGHT CONCRETE, BR NO-5	CY	56
511-3000	SUPERSTR REINF STEEL, BR NO-5 (2600)	LS	LUMP
519-0401	CONCRETE OVERLAY, VARIABLE THK-FAST TRACK	SY	7040
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO-5	LS	LUMP
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN WHITE	LF	2416
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN YELLOW	LF	2416
653-3501	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN WHITE	GLF	2416
654-1001	RAISED PVMT MARKERS TP1	EA	34
	BRIDGE NO. 6		
449-1620	LOW-DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO-6, BENT NO-1	LF	22
449-1620	LOW-DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO-6, BENT NO-2	LF	22
449-1620	LOW-DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO-6, BENT NO-3	LF	22
449-1620	LOW-DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO-6, BENT NO-4	LF	22
500-0100	GROOVED CONCRETE	SY	203
504-0600	TWENTY FOUR HOUR ACCELERATED STRENGHT CONCRETE, BR NO-6	CY	4
511-3000	SUPERSTR REINF STEEL, BR NO-6 (200)	LS	LUMP
519-0401	CONCRETE OVERLAY, VARIABLE THK-FAST TRACK	SY	203
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO-6	LS	LUMP
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN WHITE	LF	103
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN YELLOW	LF	103
	BRIDGE NO. 7		
449-1620	LOW-DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO-7, BENT NO-1	LF	22
449-1620	LOW-DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO-7, BENT NO-2	LF	22
449-1620	LOW-DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO-7, BENT NO-3	LF	22
449-1620	LOW-DENSITY, CLOSED CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BR NO-7, BENT NO-4	LF	22
500-0100	GROOVED CONCRETE	SY	214
504-0600	TWENTY FOUR HOUR ACCELERATED STRENGHT CONCRETE, BR NO-7	CY	4
511-3000	SUPERSTR REINF STEEL, BR NO-7 (200)	LS	LUMP
519-0401	CONCRETE OVERLAY, VARIABLE THK-FAST TRACK	SY	214
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO-7	LS	LUMP
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN WHITE	LF	108
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN YELLOW	LF	108

GEORGIA REGISTERED No. 14808 PROFESSIONAL ENGINEER SAMUEL L. POWELL, JR.
05-24-02

BY	REVISIONS	DATE

JBT J.B. Trimble, Inc.
6445 Powers Ferry Road
Atlanta GA 30339-2933
(770) 952-1022

GEORGIA
DEPARTMENT OF TRANSPORTATION
OPERATIONS DIVISION-OFFICE OF MAINTENANCE

DISTRICT 2 BRIDGE REPAIRS (DECK OVERLAY)
DETAILED ESTIMATE

STP-M000-00 (864)

SCALE: AS SHOWN — APRIL 2002

DESIGNED PJC — CHECKED GLE — REVIEWED EHG
DRAWN ITD — DESIGN GROUP MAINTENANCE — APPROVED STH