DETAILED ESTIMATE

ITEM NO.	ITEM	UNIT	QUANT.
	ROADWAY		
150-1000	TRAFFIC CONTROL - STP-M001-00(147)	LS	LUMP
207-0203	FOUND BKFILL MATL, TP II	CY	380
210-0100	GRADING COMPLETE - STP-M001-00(147)	LS	LUMP
310-5060	GR AGGR BASE CRS, 6 INCH, INCL MATL	SY	240
318-3000	AGGR SURF CRS	TN	50
402-1812	RECYCLED ASPH CONC LEVELING, INCL BITUM MATL & H LIME	TN	56
402-3131	RECYCLED ASPH CONC 9.5 MM SUPERPAVE, GP 2 ONLY, INCL BITUM MATL & H LIME	TN	20
402-3190	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	27
413-1000	BITUM TACK COAT	GL	10
441-0016	DRIVEWAY CONCRETE, 6 IN TK	SY	400
441-0104	CONCRETE SIDEWALK, 4 IN	SY	106
441-4030	CONC VALLEY GUTTER, 8 IN	SY	700
441-6222	CONC CURB & GUTTER, 8 IN X 30 IN, TP 2	LF	1715
	EROSION CONTROL		
700-7000	AGRICULTURAL LIME	TN	1
700-7010	LIQUID LIME	GL	3
700-8000	FERTILIZER MIXED GRADE	TN	2
700-8100	FERTILIZER NITROGEN CONTENT	LB	50
700-9300	SOD	SY	3333
	TEMPORARY EROSION CONTROL		
163-0232	TEMPORARY GRASSING	ACRE	1
163-0240	MULCH	TN	20
163-0300	CONSTRUCTION EXIT	EA	4
163-0550	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	EA	27
165-0030	MAINTENANCE OF TEMPORARY SILT FENCE, TP C	LF	500
165-0101	MAINTENANCE OF CONSTRUCTION EXIT	EA	4
165-0105	MAINTENANCE OF INLET SEDIMENT TRAP	EA	27
167-1000	WATER QUALITY MONITORING AND SAMPLING	EA	2
167-1500	WATER QUALITY INSPECTIONS	MO	9
171-0030	TEMPORARY SILT FENCE, TYPE C	LF	1000
	DRAINAGE		
550-1180	STORM DRAIN PIPE, 18 IN, H-1-10	LF	1696
550-1240	STORM DRAIN PIPE, 24 IN, H-1-10	LF	409
550-1300	STORM DRAIN PIPE, 30 IN, H-1-10	LF	194
550-1360	STORM DRAIN PIPE, 36 IN, H-1-10	LF	359
668-1100	CATCH BASIN, GP 1	EA	22
668-1110	CATCH BASIN, GP 1, ADDL DEPTH	LF	39
668-2100	DROP INLET	EA	2
668-4300	STORM SEWER MANHOLE, TP 1	EA	3
668-4311	STORM SEWER MANHOLE, TP 1, ADDL DEPTH, CL 1	LF	11
668-5000	JUNCTION BOX	EA	1
	SIGNING AND MARKING		
647-6090	LOOP DETECTOR, 6'x 6' PULSE LOOPS	EA	2
647-6090	LOOP DETECTOR, 6'x 40' QUADRUPLE PULSE LOOPS	EA	2
653-1704	THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE	LF	79

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	STP-M001-00(147)	10	61

D:\TMP\000\9625\10dets1.prf
D:\15B6Nolivertonw016\cadd\C1v1\68251dets1.dgn