

DETAILED ESTIMATE

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	NHS-M001-00(269)	7	42
REVISION DATES			
OCTOBER 31, 2001			

ITEM NO.	DESCRIPTION	UNITS	QUANTITY
150-J000	TRAFFIC CONTROL - NHS-M001-00(269)	LS	LUMP
207-D203	FOUND BK FILL MATL, TP 11	CY	4
210-D100	GRADING COMPLETE - NHS-M001-00(269)	LS	LUMP
402-3112	RECYCLED ASPH CONC 19 mm SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	1424
402-3113	RECYCLED ASPH CONC 12.5 mm SUPERPAVE, GP 2 ONLY, INCL BITUM MATL & H LIME	TN	712
402-3121	RECYCLED ASPH CONC 25 mm SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	4746
413-1000	BITUM TACK COAT	GL	690
446-1002	PVMT REINF FABRIC STRIPS, TP 2, INCL BITUM BINDER	LF	2740
550-1180	STORM DRAIN PIPE, 18 IN, H 1-10	LF	32
573-2006	UNDDR PIPE INCL DRAINAGE AGGR, 6 IN	LF	500
635-2000	DROP GATE BARRICADE	EA	4
668-2100	DROP INLET, GP 1	EA	6
668-2105	DROP INLET, SPCL DES	EA	3
668-2110	DROP INLET, GP 1, ADDL DEPTH	LF	5.00
	TEMPORARY EROSION CONTROL ITEMS		
163-0230	TEMPORARY GRASSING	LB	120
163-0235	TEMPORARY MULCH	TN	10
163-0520	CONSTRUCT AND REMOVE TEMP PIPE SLOPE DRAIN	LF	400
163-0530	CONSTRUCT AND REMOVE BALED STRAW EROSION CHECK	LF	300
171-0010	TEMPORARY SILT FENCE, TYPE A	LF	16000
171-0030	TEMPORARY SILT FENCE, TYPE C	LF	200
	MAINTENANCE OF EROSION CONTROL ITEMS		
165-0010	MAINTENANCE OF TEMPORARY SILT FENCE, TP A	LF	8000
165-0030	MAINTENANCE OF TEMPORARY SILT FENCE, TP C	LF	100
165-0070	MAINTENANCE OF BALED STRAW EROSION CHECK	LF	200
	EROSION CONTROL ITEMS		
700-6900	PERMANENT GRASSING	LB	150
700-7000	AGRICULTURAL LIME	TN	10
700-8000	FERTILIZER MIXED GRADE	TN	3
700-8100	FERTILIZER NITROGEN CONTENT	LB	236
	TRAFFIC SIGNS AND POSTS		
636-1029	HIGHWAY SIGNS, TP 2 MATL, REFL SHEETING, TP 3	SF	20
636-2030	GALV STEEL POSTS, TP 3	LF	56
636-4103	PLASTIC FLEXIBLE DELINEATOR, TP 2A	EA	788
	PAVEMENT MARKINGS		
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	LF	4800
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	4800

STATE OF GEORGIA  
DEPARTMENT OF TRANSPORTATION  
JESUP, DISTRICT 5

DRAWING No.