CHATHAM COUNTY

| STATE | PROJECT NUMBER | SHEET NO. | TOTAL SHEETS |
|---|---|---|---|
| GA. | NHS-M001-00(269) | 8 | 42 |

| REVISION DATES |
|---|
| |

55+00 60+00 65+00 70+00

BEG. PROJECT
NHS-M001-00(269)
SITE 1
STA 53+67.00
MILE POST 158.53

STA. 58+52.57
REQD 1 MEDIAN DROP INLET
SPECIAL DESIGN AND REMOVE
3 LIN FT OF 18" S.D.P.

REQD. ROAD CLOSURE DROP GATE
WITH 25' GATE AT STA 63+50

STA. 68+32.14
REQD 2 MEDIAN DROP INLET
WITH 24 LIN FT OF 18" S.D.P.
REMOVW 16 LIN FT OF 18" S.D.P.

INTERSTATE 16 WEST TO MACON

SURVEY $C_L$

S 79^57'29.3" E

S 81^21'04.0" E

20'

INTERSTATE 16 EAST TO SAVANNAH

BEG. 5" SOLID
WHITE THERMOPLASTIC
STA. 55+35.56

BEG. 5" SOLID
YELLOW THERMOPLASTIC
STA. 60+21.80

BEG EDGE OF
PAVEMENT TAPER
STA. 61+86.26

BEG EDGE OF
PAVEMENT TAPER
STA. 53+67.00

REQD. 207 FLEXIBLE DELINEATORS
PERM. FROM STA. 54+47.42 TO 64+77.12

NEW E.O.P
4'
5" SOLID YELLOW (TYP)
12'
5" SOLID WHITE (TYP)
4'
NEW E.O.P
20'

## WEST OF DEAN FOREST ROAD

PVI STA 54+42.74 PVI EL 102.41
PVI STA 55+64.66 PVI EL 102.74
PVI STA 56+90.57 PVI EL 102.96
PVI STA 58+19.68 PVI EL 102.89
PVI STA 59+37.84 PVI EL 102.82
PVI STA 60+62.65 PVI EL 102.66
PVI STA 61+89.11 PVI EL 102.47
PVI STA 63+14.23 PVI EL 102.30
PVI STA 64+38.72 PVI EL 102.21
PVI STA 65+59.62 PVI EL 102.00
PVI STA 66+85.47 PVI EL 101.79
PVI STA 68+02.27 PVI EL 101.75
PVI STA 68+81.53 PVI EL 101.68

+0.2666 % -0.0534 % -0.1330 % -0.1359 % -0.0707 % -0.1737 % -0.1669 % -0.0342 % -0.0883 %
+0.1763 % -0.0592 % -0.1487 %

102.22 102.43 102.57 102.70 102.95 102.80 102.99 102.89 103.03 102.96 102.95 102.93 102.86 102.90 102.75 102.87 102.63 102.84 102.48 102.81 102.32 102.74 102.29 102.67 102.25 102.60 102.00 102.53 101.74 102.45 101.54 102.39 101.33 102.32 101.18 102.27 101.02 102.24 100.88 102.19 100.75 102.10 100.46 102.02 100.18 101.93 99.82 101.85 99.46 101.79 98.99 101.77 98.53 101.75 98.54 101.71 98.55 101.65

150.0 140.0 130.0 120.0 110.0 100.0 90.0 80.0 70.0 60.0

54+00 55+00 56+00 57+00 58+00 59+00 60+00 61+00 62+00 63+00 64+00 65+00 66+00 67+00 68+00 69+00

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE OF DESIGN

DRAWING No.

7-SEP-2001 07:59:06
E:\WIN32APP\DGN\CSLIP1WEST\WESTPP1.DGN ON= 1-63
E:\WIN32APP\DGN\CSLIP1WEST\WESTPP1.PRF

9/7/01 7:58:59 AM \\GDOT-DSN1\GOPLOT\OCF\d5_8830_myler.ocf brewerm E:\WIN32APP\DGN\CSL