ITEM CODE NO.	ITEM	UNIT	AMOUNT
150-1000	TRAFFIC CONTROL NHS-M001-00(732)	LS	LUMP
150-5000	TRAFFIC CONTROL, TEMPORARY SAND LOADED ATTENUATOR MODULE	EA	420
210-0100	GRADING COMPLETE - NHS-M001-00(732)	LS	LUMP
310-1101	GR AGGR BASE CRS, INCL MATL	TN	59910
402-3112	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	9333
402-3121	RECYCLED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	18667
402-3130	RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 2 ONLY, INCL BITUM MATL & H LIME	TN	7000
413-1000	BITUM TACK COAT	GL	33914
456-2003	INDENTATION RUMBLE STRIPS	MI	10
550-1180	STORM DRAIN PIPE, 18 IN, H 1 - 10	LF	1171
621-0025	CONCRETE BARRIER, SPCL DESIGN, TYPE 22	LF	8693
621-3020	CONCRETE BARRIER, TYPE 20	LF	10363
621-3021	CONCRETE BARRIER, TYPE 21	LF	3334
621-3022	CONCRETE BARRIER, TYPE 22	LF	1683
641-1100	GUARDRAIL , TP T	LF	168
641-1200	GUARDRAIL , TP W	LF	1590
641-5001	GUARDRAIL , ANCHORAGE, TP 1	EA	4
641-5012	GUARDRAIL , ANCHORAGE, TP 12	EA	4
647-0200	TRAFFIC DETECTION LOOP SYSTEM No. 1	LS	LUMP
648-1200	TRAFFIC IMPACT ATTENUATOR, TYPE 2	EA	1
650-1008	GUARDRAIL IMPACT ATTENUATOR, TYPE P - B	EA	1
668-2100	DROP INLET, GP 1	EA	87
	EROSION CONTROL		
163-0230	TEMPORARY GRASS	LB	20
163-0240	MULCH	TN	30
163-0530	CONSTR AND REMOVE BALED STRAW EROSION CHECK	LF	500
165-0070	MAINTENANCE OF BALED STRAW EROSION CHECK	LF	250
163-0300	CONSTRUCTION EXIT	EA	8
163-0550	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	EA	86
165-0101	MAINTENANCE OF CONSTRUCTION EXIT	EA	8
165-0105	MAINTENANCE OF INLET SEDIMENT TRAP	EA	86
167-0100	WATER QUALITY MONITORING	MO	18
167-0200	WATER QUALITY SAMPLING	EA	37

STATE ROUTE 166 - LANGFORD PKWY
MEDIAN IMPROVEMENT

DETAILED ESTIMATE

SHEET NO. 1 OF 1

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	NHS-M001-00(732)	7	159

9/5/02 3:05:53 PM \\GDOT-DSN1\GOPLOT\OCF\d7_8830_mylar.gcf colemanm X:\squad1\M001732\detailest.prf