4/9/02 11:29:03 AM \\GDOT-DSN1\GOPLOT\OCF\GO_8830_PAPER.OCF ROBERTSONG C:\ATEST\BENRABUN\GENERALNOTES.PRF

REVISION SUMMARY SHEET

DATE	REVISED SH. NO.	REVISION
6-3-2002	1	ADDED REVISION DATE
	4-8	REVISED PER AMENDMENT

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	STP-M001-00(951)	2	12

PROJECT NOTES

1. THE CONTRACTOR SHALL REPLACE THE EXISTING LANE CLOSURE WITH TRAFFIC CONTROL DEVICES SUPPLIED BY THE CONTRACTOR. ALL DEVICES SHALL BE SAFELY STORED ON-SITE. THE CONTRACTOR SHALL NOTIFY THE MACON AREA ENGINEER AT (478) 757-2601 TO ARRANGE FOR THE PICK-UP OF THESE DEVICES. THIS WORK SHALL BE ACCOMPLISHED PRIOR TO THE COMMENCEMENT OF ANY OTHER WORK. THE COST OF THIS WORK SHALL BE INCLUDED IN THE LUMP SUM PRICE BID FOR ITEM *150-1000, TRAFFIC CONTROL, STP-M001-00(951).*

2. THE CONTRACTOR SHALL USE THE FOLLOWING ASPHALTIC CONCRETE OVERLAY TO BRING TO LINE AND GRADE THE RIDING SURFACE WHERE THE BRIDGE DECK IS REMOVED TO REPLACE THE BEAM:
RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 2 ONLY,
INCL POLYMER-MODIFIED BITUM MATL & H LIME DESIGN LEVEL C
PAYMENT FOR THE ASPHALTIC CONCRETE OVERLAY SHALL BE INCLUDED IN OTHER ITEMS BID ON THIS PROJECT.

3. THE CONTRACTOR SHALL RE-STRIPE ALL EXISTING ROADWAY MARKINGS REMOVED OR OBLITERATED DURING CONSTRUCTION. THE COST OF RE-STRIPING SHALL BE INCLUDED IN THE LUMP SUM PRICE BID FOR ITEM *150-1000, TRAFFIC CONTROL, STP-M001-00(951).*

4/9/02 11:29:03 AM \\GDOT-DSN1\GOPLOT\OCF\GO_8830_PAPER.OCF ROBERTSONG C:\ATEST\BENRABUN\GENERALNOTES.PRF GO-GSG