STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	NHS-M001-00(992)	2	28

INDEX

DESCRIPTION	SHEET NUMBERS
COVER SHEET	1
INDEX, GENERAL NOTES & REVISION SUMMARY	2
PAVING DETAILS	3
SUMMARY OF QUANTITIES	4
DETAILED ESTIMATE	5
CONSTRUCTION PLANS	6 - 8
MAINTENANCE OF TRAFFIC PLANS	9 - 14
SIGNING & MARKING PLANS	15 - 17
CONST. DETAILS	18
GEORGIA STANDARD DRAWINGS	19 - 23
BRIDGE PLANS	24 - 28

CONSTR. DETAILS

SHEET NO.	DESCRIPTION	DATE
18	IMPACT ATTENUATOR UNITS (G-11)	03-01

GEORGIA STANDARDS

SHEET NO.	DESCRIPTION	DATE
19	3901 BAR BENDING DETAILS	08-69
20	4960 CONCRETE BARRIER TEMPORARY	02-01
21	4961 PRECAST TEMP BARRIER	05-01
22	9100 TRAFFIC CONTROL GENERAL NOTES, STANDARD LEGEND, MISC. DETAILS	04-01
23	9106 TRAFFIC CONTROL DETAIL (FOR LANE CLOSURE ON MULTI-LANE HIGHWAY)	07-99

REVISION SUMMARY

DATE	REVISED SHEET NO.	REVISION
9/23/03	9,10,11,12,13&14	REMOVED BARRELS FROM MAINTENANCE OF TRAFFIC DIAGRAMS
9/23/03	2	REMOVED GENERAL NOTE # 8
9/23/03	2	REVISED DESCRIPTION OF INDENTATION RUMBLE STRIP TO INCLUDE THE TERM CONTINOUS
9/30/03	3	REVISED 12.5mm SUPERPAVE TO DESIGN LEVEL A FOR SHOULDER PAVEMENT
9/30/03	5	BRIDGE PAY ITEMS AND QUANTITIES REVISED
9/30/03	24	NOTES ADDED
9/30/03	25	QUANTITIES REVISED / PAY ITEM ADDED
9/30/03	26	BACKWALL SECTION REVISED
9/30/03	27	PAY ITEM ADDED / QUANTITIES REVISED / NOTES ADDED
9/30/03	28	BACKWALL SECTION REVISED
10/07/03	5	REVISED PAY ITEM 150-0910 TO 150-9011
10/07/03	5	REVISED PAY ITEM 456-2010 TO 456-2012
10/07/03	5, 25 & 27	REVISED PAY ITEM 519-0401 TO 519-0400
10/07/03	5	REVISED PAY ITEM 150-5010 TO 650-1200

GENERAL NOTES

1. THE CONTRACTOR SHALL BE REQUIRED TO USE THE ONE-CALL CENTER TELEPHONE NUMBER, 1-800-282-7411, FOR THE PURPOSE OF COORDINATING THE MARKING OF UNDERGROUND UTILITIES. THE CONTRACTOR'S ATTENTION IS CALLED TO SUB-SECTION 105.06 "COOPERATION WITH UTILITIES".

2. ANY SIGN THAT MAY BE DISTURBED OR REMOVED DURING CONSTRUCTION OR THAT BECOMES TOO CLOSE TO THE NEW EDGE OF PAVEMENT SHALL BE RESET OR REPLACED PER GA. STANDARDS. NO SEPARATE PAYMENT WILL BE MADE FOR RESETTING OR REPLACING COST TO BE INCLUDED IN OVERALL BID.

3. NOTICE OF INTENT IS NOT REQUIRED.

4. ALL WORK SHALL BE COMPLETED WITHIN THE EXISTING RIGHT-OF-WAY.

5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL AND PROPERLY DISPOSING OF ALL UNSALVAGEABLE MATERIAL IN THIS PROJECT. THE CONTRACTOR SHALL NOT DEPOSIT ANY MATERIAL IN ANY WATERWAY. DISPOSAL SHALL BE INCLUDED IN THE PRICE BID FOR CONTRACT ITEMS.

6. THE CONTRACTOR SHALL BE LIMITED TO WORKING ON TWO BRIDGES AT A TIME. THE CONTRACTOR SHALL MOVE THE CHANGEABLE MESSAGE SIGNS FROM WORK SITE TO WORK SITE AS NECESSARY.

7. TEMPORARY COVER PLATES - TEMPORARY STEEL COVER PLATES SHALL BE PLACED OVER OPENINGS IN THE DECK DURING HOURS WHEN WORK IS NOT BEING PERFORMED THEREIN. STEEL PLATES SHALL BE 1" THICK AND SHALL OVERLAP THE ADJACENT CONCRETE A MINIMUM OF 1 FOOT. PLATES SHALL BE ATTACHED TO DECK BY ¾" CINCH ANCHORS EMBEDDED A MINIMUM OF 3½" INTO THE CONCRETE. A MINIMUM OF TWO ANCHORS SHALL BE INSTALLED FOR EACH PLATE AND SHALL BE PLACED IN OPPOSITE CORNERS. ANCHORS SHALL BE PLACED A MINIMUM OF 6" AWAY FROM THE NEAREST CONCRETE EDGE AND 3" AWAY FROM THE NEAREST PLATE EDGE. HOLES IN PLATES FOR ANCHORS MAY BE FLAME CUT. PLATES SHALL BE ASTM A709 MATERIAL OR APPROVED EQUAL. CINCH ANCHORS SHALL BE ASTM A108 OR APPROVED EQUAL. PRIOR TO REOPENING THE STRUCTURE TO TRAFFIC THE CONTRACTOR SHALL REMOVE THE ANCHORS 1" (MINIMUM) BELOW THE TOP OF THE DECK. HOLES LEFT BY REMOVING THE ANCHORS SHALL THEN BE PATCHED WITH NON-SHRINK GROUT APPROVED BY THE ENGINEER. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING, HANDLING, INSTALLING, MOVING, STORAGE, REMOVAL OF THE TEMPORARY PLATES AND ANCHORS, AND PATCHING OF THE DECK. ALL COST OF SUCH SHALL BE INCLUDED IN THE OVERALL BID SUBMITTED.

2/20/2008 9:38:39 AM \\GDOT-DSN1\GOPLOT\GCF\Road Design Tiff-18x12 to Tiff-36x24.gcf wnguyen C:\Documents and Settings\wnguyen\Desktop\M001992\Construction\Cover-Index\M0001992 0002.TIF GO-RD-Plans-Review