DETAILED ESTIMATE

ITEM NO.	ITEMS	UNIT	QUANTITY
	ROADWAY		
150-1000	TRAFFIC CONTROL - PROJECT NO NHS-M001-00 (992)	LS	LUMP
150-5000	TRAFFIC CONTROL, PORTABLE IMPACT ATTENUATOR - TYPE T-3-S-30	EA	4
150-9011	TRAFFIC CONTROL - WORKZONE LAW ENFORCEMENT	HR	500
400-3604	ASPH CONC 12.5 MM SMA, GP 2 ONLY, INCL POLYMER-MODIFIED BITUM MATL & H LIME	TN	2100
400-3624	ASPH CONC 12.5 MM PEM, GP 2 ONLY, INCL POLYMER-MODIFIED	TN	1900
402-1812	RECYCLED ASPH CONC LEVELING, INCL BITUM & H LIME	TN	1700
402-3113	RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	1300
413-1000	BITUM TACK COAT	GL	8900
432-5010	MILL ASPH CONC PVMT, VARIABLE DEPTH	SY	40500
456-2012	INDENTATION RUMBLE STRIPS - GROUND IN PLACE	MI	3
622-1033	PRECAST CONCRETE MEDIAN BARRIER, METHOD 3	LF	2600
632-0003	VARIABLE MESSAGE SIGN, PORTABLE, TYPE 3	EA	4
	SIGNING & MARKING		
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	LF	6520
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	6520
653-3501	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN, WHITE	GLF	13040
654-1003	RAISED PVMT MARKERS TP 3	EA	184
657-1054	PREFORMED PLASTIC SOLID PVMT MKG, 5 IN, WHITE, TP PB	LF	880
657-3054	PREFORMED PLASTIC SKIP PVMT MKG, 5 IN, WHITE, TP PB	GLF	1760
657-6054	PREFORMED PLASTIC SOLID PVMT MKG, 5 IN, YELLOW, TP PB	LF	880
	BRIDGE NO. 1 (SCRUGGS)		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 1, BENT NO - 1	LF	372
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 1, BENT NO - 4	LF	342
500-0100	GROOVED CONCRETE	SY	2764
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONCRETE, BR NO- 1	CY	33
511-3000	SUPERSTR REINF STEEL, BR NO - 1 (2600)	LS	LUMP
519-0400	CONCRETE OVERLAY, VARIABLE THK - FAST TRACK	SY	2764
528-0501	EPOXY PRESSURE INJECTION OF CONCRETE CRACKS	LF	3210
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO - 1	LS	LUMP
	BRIDGE NO. 2 (CHICKAMAUGA)		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 2, BENT NO - 1	LF	275
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 2, -BENT NO - 4	LF	275
500-0100	GROOVED CONCRETE	SY	3602
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONCRETE, BR NO - 2	CY	9
511-3000	SUPERSTR REINF STEEL, BR NO - 2 (500)	LS	LUMP
519-0400	CONCRETE OVERLAY, VARIABLE THK - FAST TRACK	SY	3602
528-0501	EPOXY PRESSURE INJECTION OF CONCRETE CRACKS	LF	4180
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO - 2	LS	LUMP

VOID

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	NHS-M001-001(992)	5	28

2/20/2008 9:39:55 AM \\GDOT-DGN\GDPLOT\DEV\Road_Design_Tiff-18x26-to-Tiff-36x24.pcf wnguyen C:\Documents and Settings\wnguyen\Desktop\M001992\Construction\Plan Sheet\M001992_0005.tif GD-RD-Plans-Review