STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	NHS-M001-00(993)	7	110

DETAILED ESTIMATE

ITEM NO.	ITEMS	UNIT	QUANTITY
	ROADWAY		
150-1000	TRAFFIC CONTROL - PROJECT NO NHS-M001-00 (993)	LS	LUMP
150-9011	TRAFFIC CONTROL - WORKZONE LAW ENFORCEMENT (CONTRACTOR BIDS)	HR	500
210-0100	GRADING COMPLETE - NHS-M001-00 (993)	LS	LUMP
310-5120	GR AGGR BASE CRS, 12 INCH, INCL MATL	SY	1200
400-3604	ASPH CONC 12.5 MM SMA, GP 2 ONLY, INCL POLYMER-MODIFIED BITUM MATL & H LIME	TN	6200
400-3624	ASPH CONC 12.5 MM PEM, GP 2 ONLY, INCL POLYMER-MODIFIED	TN	5200
402-1812	RECYCLED ASPH CONC LEVELING, INCL BITUM & H LIME	TN	4200
402-3113	RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	2900
402-3121	RECYCLED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	300
413-1000	BITUM TACK COAT	GL	21500
432-5010	MILL ASPH CONC PVMT, VARIABLE DEPTH	SY	101500
433-1300	REINF CONC APPROACH SLAB, INCL BARRIER	SY	5415
441-0301	CONC SPILLWAY, TP 1	EA	2
456-2012	INDENTATION RUMBLE STRIPS - GROUND IN PLACE (CONTINUOUS)	GLM	6
576-1018	SLOPE DRAIN PIPE, 18 IN	LF	100
622-1033	PRECAST CONCRETE MEDIAN BARRIER, METHOD 3	LF	5800
622-1050	PRECAST CONCRETE MEDIAN BARRIER, METHOD 4	LF	1000
632-0003	VARIABLE MESSAGE SIGN, PORTABLE, TYPE 3	EA	6
641-1100	GUARDRAIL TP T	LF	289
641-1200	GUARDRAIL TP W	LF	2925
641-5001	GUARDRAIL ANCHORAGE, TP 1	EA	4
641-5012	GUARDRAIL ANCHORAGE, TP 12	EA	4
650-1200	IMPACT ATTENUATOR UNIT, (COMPRESSION CRASH CUSHION) TYPE T-3-S-30	EA	6
	SIGNING & MARKING		
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	LF	15900
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	16100
653-1810	THERMOPLASTIC SOLID TRAF STRIPE, 10 IN, WHITE	LF	8200
653-0293	THERMOPLASTIC PVMT MARKING, WORD, TP 12	EA	1
653-3501	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN, WHITE	GLF	34700
654-1003	RAISED PVMT MARKERS TP 3	EA	1100
657-1054	PREFORMED PLASTIC SOLID PVMT MKG, 5 IN, WHITE, TP PB	LF	2288
657-1104	PREFORMED PLASTIC SOLID PVMT MKG, 10 IN, WHITE, TP PB	LF	660
657-3054	PREFORMED PLASTIC SKIP PVMT MKG, 5 IN, WHITE, TP PB	GLF	5190
657-6054	PREFORMED PLASTIC SOLID PVMT MKG, 5 IN, YELLOW, TP PB	LF	2288
	PERMANENT EROSION CONTROL		
700-6910	PERMANENT GRASSING	AC	1
700-7000	AGRICULTURAL LIME	TN	2
700-7010	LIQUID LIME	GL	3
700-8000	FERTILIZER MIXED GRADE	TN	1
700-8100	FERTILIZER NITROGEN CONTENT	LB	100
	TEMPORARY EROSION CONTROL	AC	1
163-0232	TEMPORARY GRASS	TN	10
163-0240	MULCH	LF	500
165-0030	MAINTAINANCE OF TEMPORARY SILT FENCE, TP C	LF	1000
171-0030	TEMPORARY SILT FENCE, TP C	SY	1000
716-2000	EROSION CONTROL MAT, SLOPES		
	BRIDGE NO. 1		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 1, BENT NO - 1	LF	177
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 1, BENT NO - 4	LF	177
500-0100	GROOVED CONCRETE	SY	1996
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONCRETE, BR NO- 1	CY	200
511-3000	SUPERSTR REINF STEEL, BR NO - 1 (60240)	LS	LUMP
519-0400	CONCRETE OVERLAY, PORTLAND CEMENT, VARB THK	SY	1048
528-0750	EPOXY SEALING OF CONCRETE CRACKS	LF	1216
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO - 1	LS	LUMP
	BRIDGE NO. 2		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 2, BENT NO - 1	LF	143
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 2, BENT NO - 6	LF	142
500-0100	GROOVED CONCRETE	SY	2895
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONCRETE, BR NO- 2	CY	229
511-3000	SUPERSTR REINF STEEL, BR NO - 2 (65910)	LS	LUMP
519-0400	CONCRETE OVERLAY, PORTLAND CEMENT, VARB THK	SY	1768
528-0750	EPOXY SEALING OF CONCRETE CRACKS	LF	2050
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO - 2	LS	LUMP
	BRIDGE NO. 3		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 3, BENT NO - 1	LF	176
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 3, BENT NO - 2	LF	173
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 3, BENT NO - 3	LF	170
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 3, BENT NO - 4	LF	166
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 3, BENT NO - 5	LF	162
500-0100	GROOVED CONCRETE	SY	2676
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONCRETE, BR NO- 3	CY	190
511-3000	SUPERSTR REINF STEEL, BR NO - 3 (53640)	LS	LUMP
519-0400	CONCRETE OVERLAY, PORTLAND CEMENT, VARB THK	SY	1763
528-0750	EPOXY SEALING OF CONCRETE CRACKS	LF	2045
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO - 3	LS	LUMP
	BRIDGE NO. 4		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 4, BENT NO - 1	LF	142
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 4, BENT NO - 4	LF	142
500-0100	GROOVED CONCRETE	SY	2225
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONCRETE, BR NO- 4	CY	234
511-3000	SUPERSTR REINF STEEL, BR NO - 4 (64250)	LS	LUMP
519-0400	CONCRETE OVERLAY, PORTLAND CEMENT, VARB THK	SY	1167
528-0750	EPOXY SEALING OF CONCRETE CRACKS	LF	1353
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO - 4	LS	LUMP
	BRIDGE NO. 5		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 5, BENT NO - 1	LF	140
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 5, BENT NO - 7	LF	145
500-0100	GROOVED CONCRETE	SY	3253
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONCRETE, BR NO- 5	CY	287
511-3000	SUPERSTR REINF STEEL, BR NO - 5 (88860)	LS	LUMP
519-0400	CONCRETE OVERLAY, PORTLAND CEMENT, VARB THK	SY	1832
528-0750	EPOXY SEALING OF CONCRETE CRACKS	LF	2125
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO - 5	LS	LUMP
	BRIDGE NO. 6		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 6, BENT NO - 1	LF	183
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO - 6, BENT NO - 5	LF	183
500-0100	GROOVED CONCRETE	SY	2808
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONCRETE, BR NO- 6	CY	298
511-3000	SUPERSTR REINF STEEL, BR NO - 6 (93670)	LS	LUMP
519-0400	CONCRETE OVERLAY, PORTLAND CEMENT, VARB THK	SY	1500
528-0750	EPOXY SEALING OF CONCRETE CRACKS	LF	1740
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO - 6	LS	LUMP