STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	NHS-M001-00(994)	9	55

GUARDRAIL QUANTITIES

	LOCATION	GUARDRAIL (LF)		ANCHORAGES (EACH)		
		"W" BEAM	"T" BEAM	TYPE 1	TYPE 12	WITHOUT FLARE
SITE 1	STA. 22+52 TO BEG. BRIDGE	118.75	20.6	0	1	0
	STA. 22+59 TO BEG. BRIDGE	112.50	20.6	0	1	0
	END BRIDGE TO STA. 27+84	118.75	20.6	0	1	0
	END BRIDGE TO STA. 27+93	125.00	20.6	0	1	0
	TOTAL SITE 1	475.00	82.4	0	4	0
SITE 2	STA. 21+90 TO BEG. BRIDGE	137.50	20.6	0	0	1
	STA. 21+40 TO BEG. BRIDGE	168.75	20.6	0	0	1
	END BRIDGE TO STA. 28+07	125.00	20.6	0	0	1
	END BRIDGE TO STA. 28+71	112.50	20.6	0	0	1
	TOTAL SITE 2	543.75	82.4	0	0	4
SITE 3	STA. 21+99 TO BEG. BRIDGE	75.00	20.6	0	1	0
	STA. 21+70 TO BEG. BRIDGE	112.50	20.6	0	0	1
	END BRIDGE TO STA. 26+48	75.00	20.6	0	1	0
	END BRIDGE TO STA. 26+59	81.25	20.6	0	1	0
	TOTAL SITE 3	343.75	82.4	0	3	1
SITE 4	STA. 22+02 TO BEG. BRIDGE	81.25	20.6	0	1	0
	STA. 22+30 TO BEG. BRIDGE	50.00	20.6	0	1	0
	END BRIDGE TO STA. 26+56	81.25	20.6	0	0	1
	END BRIDGE TO STA. 26+17	37.50	20.6	0	1	0
	TOTAL SITE 4	250.00	82.4	0	3	1

NOTE: THE ACTUAL BEGINNING AND ENDING OF GUARDRAIL MAY BE ADJUSTED TO MEET FIELD CONDITION, AS DIRECTED BY THE ENGINEER.

PAVEMENT MARKERS

LOCATION	PAVEMENT MARKERS (EACH)											
	SITE 1			SITE 2			SITE 3			SITE 4		
	REFLECTIVE RAISED			REFLECTIVE RAISED			REFLECTIVE RAISED			REFLECTIVE RAISED		
	YELLOW	CLEAR	CLEAR/ RED	YELLOW	CLEAR	CLEAR/ RED	YELLOW	CLEAR	CLEAR/ RED	YELLOW	CLEAR	CLEAR/ RED
	TYPE 1	TYPE 2	TYPE 3	TYPE 1	TYPE 2	TYPE 3	TYPE 1	TYPE 2	TYPE 3	TYPE 1	TYPE 2	TYPE 3
JENKINSBURG ROAD	18											
LOCUST GROVE ROAD				20								
INDIAN CREEK ROAD							18					
BETHLEHEM ROAD										16		
TOTALS	18			20			18			16		

NOTE: TYPE 1, 2, & 3 PAVEMENT MARKERS SHALL BE SPACED AS SPECIFIED ON THE RAISED PAVEMENT MARKERS LOCATION DETAILS.

TRAFFIC STRIPE

DESCRIPTION	UNIT	QUANTITY SITE 1		QUANTITY SITE 2		QUANTITY SITE 3		QUANTITY SITE 4	
		PREFORMED	PAINT	PREFORMED	PAINT	PREFORMED	PAINT	PREFORMED	PAINT
5" SOLID WHITE	LF	750	750	860	820	632	828	626	578
5" SOLID YELLOW	LF	751	750	860	740	632	828	626	578
5" SKIP WHITE (10' SEG. 30' GAP)	LF								
24" SOLID WHITE	LF								

FOUR HOUR ACCELERATED STRENGTH CONCRETE, BRIDGE NO. 1
TOTAL 13 CY

FOUR HOUR ACCELERATED STRENGTH CONCRETE, BRIDGE NO. 2
TOTAL 18 CY

FOUR HOUR ACCELERATED STRENGTH CONCRETE, BRIDGE NO. 3
TOTAL 13 CY

FOUR HOUR ACCELERATED STRENGTH CONCRETE, BRIDGE NO. 4
TOTAL 13 CY

TWENTY-FOUR HOUR ACCELERATED STRENGTH CONCRETE, BRIDGE NO. 1
TOTAL 3 CY

TWENTY-FOUR HOUR ACCELERATED STRENGTH CONCRETE, BRIDGE NO. 2
TOTAL 4 CY

TWENTY-FOUR HOUR ACCELERATED STRENGTH CONCRETE, BRIDGE NO. 3
TOTAL 5 CY

TWENTY-FOUR HOUR ACCELERATED STRENGTH CONCRETE, BRIDGE NO. 4
TOTAL 5 CY

TRAFFIC CONTROL, TEMPORARY SAND LOADED ATTENUATOR MODULE
TOTAL 8 EA

CHANGEABLE MESSAGE SIGN, PORTABLE, TYPE 3
TOTAL 4 EACH

PVMT. REINF FABRIC STRIP TP 2, INCL BITUM BINDER SITE 1
TOTAL 370 LIN FT

PVMT. REINF FABRIC STRIP TP 2, INCL BITUM BINDER SITE 2
TOTAL 416 LIN FT

PVMT. REINF FABRIC STRIP TP 2, INCL BITUM BINDER SITE 3
TOTAL 635 LIN FT

PVMT. REINF FABRIC STRIP TP 2, INCL BITUM BINDER SITE 4
TOTAL 460 LIN FT

ADJUST SPILLWAY TO GRADE SITE 1
TOTAL 4 EACH

ADJUST SPILLWAY TO GRADE SITE 2
TOTAL 2 EACH

ADJUST SPILLWAY TO GRADE SITE 3
TOTAL 2 EACH

ADJUST SPILLWAY TO GRADE SITE 4
TOTAL 2 EACH

GRESHAM SMITH AND PARTNERS

DATE	REVISIONS	DATE	REVISIONS

GEORGIA DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
PROJECT - NHS-M001-00(994)
COUNTY - SPALDING-HENRY
DATE SHEET 6-02

o:\2280925\t\001994QUAN2.dgn
11/10/2004