STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	NHS-M001-00(995)	8	51

EROSION CONTROL

TEMPORARY EROSION CONTROL ITEM	UNIT	SITE 1 QUANTITY	SITE 1 AS DIRECTED BY ENGINEER	SITE 1 TOTAL	SITE 2 QUANTITY	SITE 2 AS DIRECTED BY ENGINEER	SITE 2 TOTAL	SITE 3 QUANTITY	SITE 3 AS DIRECTED BY ENGINEER	SITE 3 TOTAL
CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	EA							1		1
TEMPORARY SILT FENCE, TYPE A	LF	1124		1124	1055		1055	719		719
MAINTENANCE OF INLET SEDIMENT TRAP	EA							1		1
MAINTENANCE OF TEMPORARY SILT FENCE, TP A	LF	1124		1124	1055		1055	719		719
CONSTRUCTION EXIT	EA	4		4	4		4	4		4
MAINTENANCE OF CONSTRUCTION EXIT	EA	4		4	4		4	4		4
EROSION CONTROL MATS	SY	450		450	0		0	0		0

ADJUST SPILLWAY TO GRADE SITE 1
TOTAL SITE 1 — 2 EACH

ADJUST SPILLWAY TO GRADE SITE 2
TOTAL SITE 2 — 4 EACH

ADJUST SPILLWAY TO GRADE SITE 3
TOTAL SITE 3 — 2 EACH

ADJUST CATCH BASIN TO GRADE SITE 3
TOTAL SITE 3 — 1 EACH

CLASS B CONCRETE, INCL REINF STEEL
TOTAL — 46 CY

TWENTY-FOUR HOUR ACCELERATED STRENGTH CONCRETE
TOTAL — 61 CY

LOW-DENSITY, CLOSED CELL, CROSS-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BRIDGE NO. 1
TOTAL — 184 LF

LOW-DENSITY, CLOSED CELL, CROSS-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BRIDGE NO. 2
TOTAL — 106 LF

LOW-DENSITY, CLOSED CELL, CROSS-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN BLOWN SEAL, BRIDGE NO. 3
TOTAL — 406 LF

ELASTOMERIC PROFILE BRIDGE JOINT SEALS, BRIDGE NO. 2
TOTAL — 106 LF

FIELD FENCE WOVEN WIRE SITE 1
TOTAL SITE 1 — 100 LF

FIELD FENCE WOVEN WIRE SITE 2
TOTAL SITE 2 — 100 LF

RAISE EXISTING BRIDGE BRIDGE NO. 1
TOTAL — LUMP

RAISE EXISTING BRIDGE BRIDGE NO. 2
TOTAL — LUMP

RAISE EXISTING BRIDGE BRIDGE NO. 3
TOTAL — LUMP

FIELD FENCE WOVEN WIRE SITE 3
TOTAL SITE 3 — 100 LF

GRASSING

	ITEM	UNIT	QUANTITY	AGRICULTURAL LIME TON	FERTILIZER MIXED GRADE TON	FERTILIZER NITROGEN CONTENT LB	MULCH TON	LIQUID LIME GL
SITE 1	PERMANENT GRASSING	ACRES	1	1	1	N/A	-	2
	TEMPORARY GRASSING	ACRES	1	1	1	N/A	2	1
	DISTURBED AREA	ACRES	1	N/A	N/A	N/A	8	N/A
	TOTAL			2	2	N/A	10	3
SITE 2	PERMANENT GRASSING	ACRES	1	1	1	N/A	-	2
	TEMPORARY GRASSING	ACRES	1	1	1	N/A	1	1
	DISTURBED AREA	ACRES	1	N/A	N/A	N/A	6	N/A
	TOTAL			2	2	N/A	7	3
SITE 3	PERMANENT GRASSING	ACRES	1	1	1	N/A	-	1
	TEMPORARY GRASSING	ACRES	1	1	1	N/A	1	1
	DISTURBED AREA	ACRES	1	N/A	N/A	N/A	2	N/A
	TOTAL			2	2	N/A	3	2

GRESHAM SMITH AND PARTNERS

DATE	REVISIONS	DATE	REVISIONS
03-03-04	ADDED SUMMARY BLOCKS FOR FIELD FENCE WOVEN WIRE		

GEORGIA DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
PROJECT - NHS-M001-00(995)
COUNTY - COBB & CHEROKEE
DATE 2/5/04 SHEET 6-02

o:\2280926\t\0019950UAN2.dgn
03/03/2004