STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	STP-M002-00 (072)	2	7

SUMMARY OF QUANTITIES

	TRAFFIC CONTROL PROJECT NO STP-M002-00 (072) PAY ITEM 150-1000	CLASS AA CONCRETE, HES PAY ITEM 500-3001	SUPERSTR REINF STEEL PAY ITEM 511-3000	EPOXY PRESSURE INJECTION OF CONCRETE CRACKS PAY ITEM 528-0501	REMOVAL OF PARTS OF EXISTING BR PAY ITEM 540-1202	FIBER REINF POLYMER (CARBON), BR NO - 1 PAY ITEM 590-1000	CHANGEABLE MESSAGE SIGN, PORTABLE, TYPE 3 PAY ITEM 632-0003	RAISED PVMT MARKERS TP 3 PAY ITEM 654-1003	PREFORMED PLASTIC SOLID PVMT MKG, 5 IN, WHITE, TP PB PAY ITEM 657-1054	PREFORMED PLASTIC SKIP PVMT MKG, 5 IN, WHITE, TP PB PAY ITEM 657-3054	PREFORMED PLASTIC PVMT MKG, WORDS AND/OR SYM, ARROW, TP 2, WHITE, TP PB PAY ITEM 657-5017	PREFORMED PLASTIC SOLID PVMT MKG, 5 IN, YELLOW, TP PB PAY ITEM 657-6054
BRIDGE UNIT	LS	CY	LS	LF	LS	SY	EA	EA	LF	LF	GLF	LF
BRIDGE NO. 1 BR. SERIAL NO. 057-0018-0	LUMP	20	(1000)	50	LUMP	104	2	4	70	180	1	320
TOTAL	LUMP	20	(1000)	50	LUMP	104	2	4	70	180	1	320

DETAILED ESTIMATE

ITEM NO.	ITEM	UNIT	QUANTITY
150-1000	TRAFFIC CONTROL - PROJECT NO STP-M002-00 (072)	LUMP	LUMP
632-0003	CHANGEABLE MESSAGE SIGN, PORTABLE, TYPE 3	EA	2
	BRIDGE NO 1		
500-3001	CLASS AA CONCRETE, HES	CY	20
511-3000	SUPERSTR REINF STEEL, BR NO - 1 (1000)	LS	LUMP
528-0501	EPOXY PRESSURE INJECTION OF CONCRETE CRACKS	LF	50
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO - 1	LS	LUMP
590-1000	FIBER REINF POLYMER (CARBON), BR NO - 1	SY	104
654-1003	RAISED PVMT MARKERS TP 3	EA	4
657-1054	PREFORMED PLASTIC SOLID PVMT MKG, 5 IN, WHITE, TP PB	LF	70
657-3054	PREFORMED PLASTIC SKIP PVMT MKG, 5 IN, WHITE, TP PB	GLF	180
657-5017	PREFORMED PLASTIC PVMT MKG, WORDS AND/OR SYM, ARROW, TP 2, WHITE, TP PB	EA	1
657-6054	PREFORMED PLASTIC SOLID PVMT MKG, 5 IN, YELLOW, TP PB	LF	320

GENERAL NOTES

ALL WORK SHALL BE COMPLETED WITHIN THE EXISTING RIGHT-OF-WAY.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL AND PROPER DISPOSAL OF ALL UNSALVAGEABLE MATERIAL IN THIS PROJECT. THE CONTRACTOR SHALL NOT DEPOSIT ANY MATERIAL IN ANY WATERWAY. THE COST OF REMOVAL AND DISPOSAL SHALL BE INCLUDED IN THE PRICE BID FOR CONTRACT ITEMS. THERE IS NOT A SUITABLE SITE WITHIN THE PROJECT LIMITS TO BURY BRIDGE OR BRIDGE PARTS.

NOTICE OF INTENT IS NOT REQUIRED ON THIS PROJECT.

BRIDGE NO. 1

JBT J.B. Trimble, Inc.
6445 Powers Ferry Road
Atlanta GA 30339-2933
(770) 952-1022

GEORGIA
DEPARTMENT OF TRANSPORTATION
OPERATIONS DIVISION-OFFICE OF MAINTENANCE

CAPACITY UPGRADE
SR 92 OVER NOONDAY CREEK
SUMMARY OF QUANTITIES AND DETAILED ESTIMATE
CHEROKEE COUNTY STP-M002-00 (072)

SCALE: NO SCALE U.N.O. JUNE 2003

BY	REVISIONS	DATE

DESIGNED MDT CHECKED GLE REVIEWED BKS
DRAWN ITD DESIGN GROUP MAINTENANCE APPROVED EHG