

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	STP-M002-00(112)	2	40

INDEX	
SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX & GENERAL NOTES
3	REVISION SUMMARY
4	SUMMARY OF QUANTITIES
5	DETAILED ESTIMATE
6-7	DETOUR PLANS
8-13	BRIDGE NO. 1
14-20	BRIDGE NO. 2
21	CONSTR DETAILS - ADJUSTING GUARDRAIL TO GRADE (G-4) (01/88)
22	CONSTR DETAILS - DETAILS OF RAISED PAVEMENT MARKER LOCATION NON-LIMITED ACCESS ROADWAY (T15A) (01/04)
23	CONSTR DETAILS - DETAILS OF RAISED PVM'T MARKERS (T-15C) (01-00)
24	GA STD 3054 - END POST AND END POST GUARDRAIL ATTACHMENT DETAIL (09/02)
25	GA STD 3901 - BAR BENDING DETAILS (8/69)
26	GA STD 4000-W - GUARDRAIL WARRANT GUIDES (12/99)
27	GA STD 4010 - "W" BEAM GUARDRAIL (07-97)
28	GA STD 4011-A - POST AND OFFSET BLOCKS FOR "W" AND "T" BEAM GUARDRAIL (REPLACES STANDARDS 4011 & 4271) - ADDED COMPOSITE BLOCK (12/01)
29	GA STD 4012-C - GUARDRAIL CONNECTION AT BRIDGE END OR AT CONCRETE BARRIER END (03/03)
30	GA STD 4012-D - GUARDRAIL ANCHORAGE TYPE 1 (07/02)
31	GA STD 4013 - GUARDRAIL ANCHORAGE TYPE 5 AND 6 - GUARDRAIL ATTACHMENTS TO COLUMNS, PIERS, WALLS (06/98)
32	GA STD 4040 - GUARDRAIL ANCHORAGE TYPE 12 (07/97)
33	GA STD 4052 - GUARDRAIL LOCATION DETAILS FOR UNDIVIDED HIGHWAYS AND ROADS (10/97)
34	GA STD 4270 - "T" BEAM GUARDRAIL (11/99)
35	GA STD 4360 - REFLECTORIZED GUARDRAIL WASHERS (02/01)
36	GA STD 9017P - REINFORCED CONCRETE APPROACH SLAB 30 FT. LENGTH (TYPICAL USE; WHERE SHOULDER IS ADJACENT TO ROADWAY AND/OR ACROSS BRIDGE) (09/02)
37	GA STD 9031-T - ISOMETRIC VIEWS OF SIDE ROAD OR DRIVE FLARE DETAIL AT BRIDGE ENDS (08/95)
38	GA STD 9037 - TYPICAL FILL DETAIL AT END OF BRIDGE (10-97)
39	GA STD 9100 - TRAFFIC CONTROL GEN. NOTES, STD. LEGEND, MISC. DETAILS (04-01)
40	GA STD 9106 - TRAFFIC CONTROL DETAIL FOR LANE CLOSURE (07-99)
40	TOTAL SHEETS

GENERAL NOTES

1. THE CONTRACTOR SHALL BE REQUIRED TO USE THE UPC ONE-CALL CENTER TELEPHONE NUMBER, 1-800-282-7411, FOR UTILITY LOCATIONS PRIOR TO BEGINNING CONSTRUCTION. THE CONTRACTOR'S ATTENTION IS CALLED TO SUB-SECTION 105.06 "COOPERATION WITH UTILITIES".
2. ANY SIGN THAT MAY BE DISTURBED OR REMOVED DURING CONSTRUCTION OR THAT BECOMES TOO CLOSE TO THE NEW EDGE OF PAVEMENT SHALL BE RESET OR REPLACED PER GA. STANDARDS. NO SEPARATE PAYMENT WILL BE MADE FOR RESETTING OR REPLACING COST TO BE INCLUDED IN OVERALL BID.
3. NOTICE OF INTENT IS NOT REQUIRED.
4. ALL WORK SHALL BE COMPLETED WITHIN THE EXISTING RIGHT-OF-WAY.
5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL AND PROPERLY DISPOSING OF ALL UNSALVAGEABLE MATERIAL IN THIS PROJECT. THE CONTRACTOR SHALL NOT DEPOSIT ANY MATERIAL IN ANY WATERWAY. DISPOSAL SHALL BE INCLUDED IN THE PRICE BID FOR CONTRACT ITEMS.
6. ANY AREAS OF THE BRIDGE DAMAGED OR LEFT OPEN BY THE RELOCATION OF EXISTING UTILITIES SHALL BE REPAIRED AS DIRECTED BY THE ENGINEER. COST FOR THIS WORK SHALL BE INCLUDED IN THE OVERALL BID SUBMITTED.

UTILITY OWNERS		
ELECTRICAL	NONE	
GAS	ATLANTA GAS LIGHT	(678) 409-8054
SEWER	NONE	
WATER	CITY OF GAINESVILLE	(770) 538-2400
TELEPHONE	BELLSOUTH	(706) 353-4300
RAILROAD	NONE	
CABLE TV	NONE	