DETAILED ESTIMATE

ITEM NO.	ITEMS		
	ROADWAY	UNIT	QUANTITY
150-1000	TRAFFIC CONTROL - STP-M002-00(112)	LS	LUMP
402-3129	RECYCLED ASPH CONC 12.5 MM MIX, GP 2 ONLY, INCL BITUM MATL & H LIME	TN	470
413-1000	BITUM TACK COAT	GL	260
432-5010	MILL ASPH CONC PVMT, VARIABLE DEPTH	SY	400
610-1055	REM GUARDRAIL	LF	1000
632-0003	CHANGEABLE MESSAGE SIGN, PORTABLE, TYPE 3	EA	4
641-1100	GUARDRAIL, TP T	LF	83
641-1200	GUARDRAIL, TP W	LF	1300
641-5001	GUARDRAIL ANCHORAGE, TP 1	EA	4
641-5005	GUARDRAIL ANCHORAGE, TP 5	EA	4
641-5012	GUARDRAIL ANCHORAGE, TP 12	EA	4
	SIGNING & MARKING		
654-1001	RAISED PVMT MARKERS TP 1	EA	40
657-1054	PREFORMED PLASTIC SOLID PVMT MKG, 5 IN, WHITE, TP PB	LF	2920
657-6054	PREFORMED PLASTIC SOLID PVMT MKG, 5 IN, YELLOW, TP PB	LF	2920
	BRIDGE NO. 1		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, BR NO-1, BENT NO-1	LF	30
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, BR NO-1, BENT NO-7	LF	30
501-3000	STR STEEL, BR NO -1 (58000)	LS	LUMP
503-1600	FOUR HOUR ACCELERATED STRENGTH CONCRETE	CY	90
505-1000	COMPOSITE STEEL GRID DECK WITH PRECAST SLAB	SF	21960
511-1000	BAR REINF STEEL	LB	500
519-0515	SURFACE PREPARATION	SY	2371
519-0520	COPOLYMER OVERLAY	SY	2371
535-1105	PAINT EXIST STEEL STRUCTURE, BR ID - 139-00011D-013.58N	LS	LUMP
540-1202	REMOVAL OF PARTS OF EXISTING BRIDGE, BR NO -1	LS	LUMP
	BRIDGE NO. 2		
443-1000	REINF CONC APPROACH SLAB	SY	98
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, BR NO-2, BENT NO-1	LF	28
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, BR NO-2, BENT NO-7	LF	28
500-2110	CONCRETE PARAPET, SPCL DESIGN	LF	757
501-3000	STR STEEL, BR NO -2 (12500)	LS	LUMP
503-1600	FOUR HOUR ACCELERATED STRENGTH CONCRETE	CY	88
505-1000	COMPOSITE STEEL GRID DECK WITH PRECAST CONCRETE SLAB	SF	11130
511-1000	BAR REINF STEEL	LB	720
519-0515	SURFACE PREPARATION	SY	1108
519-0520	COPOLYMER OVERLAY	SY	1108
540-1202	REMOVAL OF PARTS OF EXISTING BRIDGE, BR NO -2	LS	LUMP

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	STP-M002-00(112)	5	40

k:\tro\3-3029 bridge deck repairs\stp-m002-00(112) hall county (lake lanier)\m00200112est.dgn
6/10/2004
...\M00200112est.dgn 6/10/2004 4:48:16 PM