

GENERAL NOTES

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	STP-M002-00 (113)	4	80

1. THE CONTRACTOR SHALL BE REQUIRED TO USE THE ONE-CALL CENTER TELEPHONE NUMBER, 1-800-282-7411, FOR THE PURPOSE OF COORDINATING THE MARKING OF UNDERGROUND UTILITIES. THE CONTRACTOR'S ATTENTION IS CALLED TO SUB-SECTION 105.06 "COOPERATION WITH UTILITIES".
2. ANY SIGN THAT MAY BE DISTURBED OR REMOVED DURING CONSTRUCTION OR THAT BECOMES TOO CLOSE TO THE NEW EDGE OF PAVEMENT SHALL BE RESET OR REPLACED PER GA. STANDARDS. NO SEPARATE PAYMENT WILL BE MADE FOR RESETTING OR REPLACING COST TO BE INCLUDED IN OVERALL BID.
3. NOTICE OF INTENT IS NOT REQUIRED.
4. ALL WORK SHALL BE COMPLETED WITHIN THE EXISTING RIGHT-OF-WAY.
5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL AND PROPERLY DISPOSING OF ALL UNSALVAGEABLE MATERIAL IN THIS PROJECT. THE CONTRACTOR SHALL NOT DEPOSIT ANY MATERIAL IN ANY WATERWAY. DISPOSAL SHALL BE INCLUDED IN THE PRICE BID FOR CONTRACT ITEMS.
6. THE CONTRACTOR SHALL BE LIMITED TO WORKING ON TWO BRIDGES AT A TIME. THE CONTRACTOR SHALL MOVE THE CHANGEABLE MESSAGE SIGNS FROM WORK SITE TO WORK SITE AS NECESSARY.
7. THERE IS NOT A SUITABLE SITE TO DISPOSE OF BRIDGE PARTS IN THE RIGHT-OF-WAY.
9. THE CONTRACTOR SHALL BACKFILL ANY VOIDS UNDER APPROACH SLABS IN ORDER TO MEET SUBGRADE REQUIREMENTS AND ELEVATIONS PRIOR TO PLACING APPROACH SLAB SUBBASE

TRAFFIC CONTROL GENERAL NOTES

1. ALL ITEMS NECESSARY FOR COMPLIANCE WITH THESE REQUIREMENTS SHALL BE INCLUDED IN THE PRICE BID FOR TRAFFIC CONTROL, LUMP SUM.
2. ALL SIGNS AND PAVEMENT MARKINGS SHALL CONFORM TO THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, (LATEST EDITION).
3. ALL SIGNS SHALL HAVE HIGH INTENSITY GRADE SHEETING.
4. EXISTING TRAFFIC SIGNS SHALL BE MAINTAINED BY THE CONTRACTOR THROUGHOUT CONSTRUCTION. MAINTENANCE INCLUDES REPLACING DAMAGED AND STOLEN SIGNS, AND PERIODIC CLEANING OF EXISTING SIGNS AND CONSTRUCTION RELATED TRAFFIC CONTROL DEVICES.
5. ONLY REFLECTORIZED PLASTIC DRUMS AND TEMPORARY CONCRETE BARRIERS SHALL BE USED ADJACENT TO TRAVEL LANES. TYPE I AND TYPE II BARRICADES AND CONES SHALL NOT BE USED.
6. ALL REFLECTORIZED PLASTIC DRUMS AND TEMPORARY CONCRETE BARRIERS SHALL BE PLACED A MINIMUM OF 2 FEET FROM THE EDGE OF THE TRAVEL LANES UNLESS PRIOR APPROVAL IS GRANTED BY THE DEPARTMENT OF TRANSPORTATION.
7. THE CONTRACTOR SHALL MAINTAIN INGRESS AND EGRESS TO DRIVEWAYS AT ALL TIMES.
8. ALL TRAFFIC CONTROL DEVICES SHALL BE MAINTAINED BY THE CONTRACTOR SO AS TO NOT INTERFERE WITH SIGHT DISTANCE ALONG ANY ADJACENT SIDE ROAD OR DRIVEWAY.
9. PRICE BID FOR TRAFFIC CONTROL - LUMP SUM SHALL INCLUDE, BUT IS NOT LIMITED TO, CONSTRUCTION, MAINTENANCE, AND REMOVAL OF TEMPORARY SIGNING AND PAVEMENT MARKINGS, BARRICADES, CHANNELIZING DEVICES, DETOUR PAVING, AND AGGREGATE SURFACE COURSE REQUIRED FOR MAINTENANCE OF TRAFFIC DURING CONSTRUCTION. ALL TEMPORARY SIGNING AND PAVEMENT MARKING SHALL BE IN ACCORDANCE WITH THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES", CURRENT EDITION AND/OR AS DIRECTED BY THE ENGINEER.
10. CONTRACTOR IS RESPONSIBLE FOR ANY REQUIRED ADJUSTMENT OF EXISTING TRAFFIC SIGNAL HEADS NEEDED TO ACCOMMODATE TRAFFIC SHIFTS. PRICE TO BE INCLUDED IN PRICE BID FOR TRAFFIC CONTROL, LUMP SUM.
11. TEMPORARY STRIPING ERADICATION SHALL BE ACCOMPLISHED WITHOUT SCARRING FINAL SURFACE.

JBT J.B. TRIMBLE, INC.
6445 Powers Ferry Road,
Suite 100
Atlanta, GA 30339

DATE	REVISIONS	DATE	REVISIONS
01-28-04	ADDED TRAFFIC CONTROL NOTE		

GEORGIA
DEPARTMENT OF TRANSPORTATION
GENERAL NOTES

PROJECT: STP-M002-00 (113)
COUNTY: HALL AND HABERSHAM

DRAWING No.	4-01
-------------	------

DGN#SPECIFICATION*****
SHOWDATE TIME*****

K:\TRA\31-3029\113\HALL CO\DGN\RDY\113BINOT.DGN

10-10-03 GKS