STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	STP-M002-00 (113)	11	80

DETAILED ESTIMATE

ITEM NO.	DESCRIPTION	UNITS	QUANTITY
	ROADWAY		
150-1000	TRAFFIC CONTROL - STP-M002-00(113)	LS	LUMP
210-0100	GRADING COMPLETE - STP-M002-00(113)	LS	LUMP
310-5120	GR AGGR BASE CRS, 12 INCH, INCL MATL	TN	375
318-3000	AGGR SURF CRS	TN	50
402-1812	RECYCLED ASPH CONC LEVELING, INCL BITUM MATL & H LIME	TN	850
402-3121	RECYCLED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	150
402-3110	RECYCLED ASPH CONC 9.5 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	250
402-4510	RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 2 ONLY, INCL POLYMER-MODIFIED BITUM MATL & H LIME	TN	375
413-1000	BITUM TACK COAT	GL	1200
432-5010	MILL ASPH CONC PVMT, VARIABLE DEPTH	SY	6500
433-1100	REINF CONC APPROACH SLAB, INCL CURB	SY	694
441-0104	CONC SIDEWALK, 4 IN	SY	100
441-0748	CONCRETE MEDIAN, 6 IN	SY	575
441-6012	CONC CURB & GUTTER, 6 IN, TP 2	LF	100
500-9999	CLASS B CONC, BASE OR PVMT WIDENING	CY	33
622-1033	PRECAST CONCRETE MEDIAN BARRIER, METHOD 3	LF	350
622-1050	PRECAST CONCRETE MEDIAN BARRIER, METHOD 4	LF	690
632-0003	CHANGEABLE MESSAGE SIGN, PORTABLE, TYPE 3	EA	2
641-1100	GUARDRAIL, TP T	LF	566
641-1200	GUARDRAIL, TP W	LF	800
641-5001	GUARDRAIL ANCHORAGE, TP 1	EA	3
641-5012	GUARDRAIL ANCHORAGE, TP 12	EA	4
647-0220	TRAFFIC SIGNAL INSTALLATION, TEMPORARY	LS	LUMP
647-6090	LOOP DETECTOR - (6' X 6')	EA	2
647-6090	LOOP DETECTOR - (6' X 40')	EA	2
650-1200	IMPACT ATTENUATOR UNIT, (COMPRESSION CRASH CUSHION) TYPE T	EA	4
	SIGNING & MARKING		
652-0120	THERMOPLASTIC PVMT MARKING, ARROW, TP 2	EA	2
652-5451	SOLID TRAFFIC STRIPE, 5 IN, WHITE	LF	1860
652-5452	SOLID TRAFFIC STRIPE, 5 IN, YELLOW	LF	1860
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	LF	1070
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	970
653-1704	THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE	LF	84
653-3501	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN, WHITE	GLF	1070
654-1001	RAISED PVMT MARKERS TP 1	EA	22
654-1003	RAISED PVMT MARKERS TP 3	EA	36
657-1054	PREFORMED PLASTIC SOLID PVMT MKG, 5 IN, WHITE, TP PB	LF	1920
657-3054	PREFORMED PLASTIC SKIP PVMT MKG, 5 IN, WHITE, TP PB	GLF	1380
657-6054	PREFORMED PLASTIC SOLID PVMT MKG, 5 IN, YELLOW, TP PB	LF	1920
	PERMANENT EROSION CONTROL		
700-6910	PERMANENT GRASSING	AC	1
700-7000	AGRICULTURAL LIME	TN	2
700-7010	LIQUID LIME	GL	3
700-8000	FERTILIZER MIXED GRADE	TN	1
700-8100	FERTILIZER NITROGEN CONTENT	LB	100
	TEMPORARY EROSION CONTROL		
163-0232	TEMPORARY GRASSING	AC	1
163-0240	MULCH	TN	10
163-0300	CONSTRUCTION EXIT	EA	1
163-0530	CONSTRUCT AND REMOVE BALED STRAW EROSION CHECK	LF	500
165-0030	MAINTENANCE OF TEMPORARY SILT FENCE, TP C	LF	500
165-0070	MAINTENANCE OF BALED STRAW EROSION CHECK	LF	250
165-0101	MAINTENANCE OF CONSTRUCTION EXIT	EA	1
171-0030	TEMPORARY SILT FENCE, TYPE C	LF	1000
716-2000	EROSION CONTROL MATS, SLOPES	SY	1000
	BRIDGE NO. 1		
500-0100	GROOVED CONCRETE	SY	3991
500-1006	SUPERSTR CONCRETE, CL AA, BR NO-1 (1888)	LS	LUMP
511-3000	SUPERSTR REINF STEEL, BR NO-1 (432980)	LS	LUMP
516-1100	ALUM HANDRAIL, STD 3626	LF	1366
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO-1	LS	LUMP
	BRIDGE NO. 2		
500-0100	GROOVED CONCRETE	SY	1260
500-1006	SUPERSTR CONCRETE, CL AA, BR NO-2 (462)	LS	LUMP
501-3000	STR STEEL, BR NO-2 (13300)	LS	LUMP
511-3000	SUPERSTR REINF STEEL, BR NO-2 (107020)	LS	LUMP
516-1100	ALUM HANDRAIL, STD 3626	LF	531
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO-2	LS	LUMP

PROPERTY AND EXISTING R/W LINE
REQUIRED R/W LINE
CONSTRUCTION LIMITS
EASEMENT FOR CONSTR & MAINTENANCE OF SLOPES
EASEMENT FOR CONSTR OF SLOPES
EASEMENT FOR CONSTR OF DRIVES

BEGIN LIMIT OF ACCESS.....BLA
END LIMIT OF ACCESS.....ELA
LIMIT OF ACCESS
R/W AND LIMIT OF ACCESS

J.B. TRIMBLE, INC.
6445 Powers Ferry Road,
Suite 100
Atlanta, GA 30339

DATE	REVISIONS	DATE	REVISIONS
1-12-04	REVISED IMPACT ATTENUATOR	2-12-04	ADDED LOOP DETECTORS
	REVISED 9.5 mm SUPERPAVE		
	REVISED TRAFFIC SIGNAL		
1-28-04	ADDED CLASS B CONC		
	ADDED SIGNAL LOOPS		
	REVISED STRIPING		
2-12-04	REVISED LOOP DETECTORS		

GEORGIA
DEPARTMENT OF TRANSPORTATION
DETAILED ESTIMATE
PROJECT: STP-M002-00 (113)
COUNTY: HALL AND HABERSHAM
DRAWING NO. 9-01

DGN$SPECIFICATION$$$$$$$$$$$$$$$$$$$$
SHOWDATETIME$$$$$$
K:\TRA\31-3029\(113)\HALL CO\DGN\RDY\113Blest.dgn 01-12-04 MGS