SUMMARY OF QUANTITIES

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	NHS-M002-00(136) CT 1	5	51

TRAFFIC CONTROL NHS-M002-00(136) CT 1

TOTAL LUMP SUM

CHANGEABLE MESSAGE SIGN, PORTABLE, TYPE 3

TOTAL 6

SURFACING QUANTITES

ITEMS	UNIT	BRIDGE 1	BRIDGE 4	AS DIRECTED BY ENGINEER	TOTALS
RECYCL ASPH CONC 12.5 mm SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	320	470	10	800
BITUM TACK COAT	GL	1831	3357	12	5200
ASPH CONC 12.5 mm SMA, GP 2 ONLY, INCL POLYMER MODIFIED	TN	1099	2073	28	3200
ASPH CONC 12.5 mm PEM, GP 2 ONLY, INCL POLYMER MODIFIED	TN	899	1696	5	2600

TRAFFIC CONTROL - WORKZONE LAW ENFORCEMENT (CONTRACTOR BIDS)

TOTAL 2100 HR

PRECAST CONCRETE MEDIAN BARRIER
METHOD 3 - STD. 4960 & 4961

LOCATION	LIN. FT.
AS DIRECTED BY ENGINEER	350
TOTAL	350

IMPACT ATTENUATOR, (COMPRESSION CRASH CUSHION) TYPE T-3-S-30

TOTAL 1

TO BE USED AS DIRECTED BY THE ENGINEER

TRAFFIC STRIPE

DESCRIPTION	UNIT	QUANTITY PREFORMED	QUANTITY THERMOPLASTIC
BRIDGE NO. 1			
5" SOLID WHITE	LIN FEET	418	2,482
5" SOLID YELLOW	LIN FEET	418	2,282
5" SKIP WHITE	GR LIN FT	1,254	6,850
10" SOLID WHITE	LIN FEET		200
BRIDGE NO. 2			
5" SOLID WHITE	LIN FEET	541	
5" SOLID YELLOW	LIN FEET	246	
5" SKIP WHITE	GR LIN FT	592	
10" SOLID WHITE	LIN FEET		
BRIDGE NO. 4			
5" SOLID WHITE	LIN FEET	432	2,904
5" SOLID YELLOW	LIN FEET	432	2,968
5" SKIP WHITE	GR LIN FT	2,376	15,224
10" SOLID WHITE	LIN FEET		675
TOTALS			
5" SOLID WHITE	LIN FEET	1,391	5,386
5" SOLID YELLOW	LIN FEET	1,096	5,250
5" SKIP WHITE	GR LIN FT	4,222	22,074
10" SOLID WHITE	LIN FEET		875

INDENTATION RUMBLE STRIPS GROUND IN PLACE (CONTINUOUS)

TOTAL 2 GLM

PRECAST CONCRETE MEDIAN BARRIER
METHOD 4 - STD. 4960

LOCATION	LIN. FT.
AS DIRECTED BY ENGINEER	250
TOTAL	250

PAVEMENT MARKERS (EACH)

LOCATION	REFLECTIVE-RAISED YELLOW TYPE 1	REFLECTIVE-RAISED CLEAR TYPE 2	REFLECTIVE-RAISED CLEAR/RED TYPE 3
BRIDGE NO. 1			140
BRIDGE NO. 2			20
BRIDGE NO. 3			
BRIDGE NO. 4			270
AS DIRECTED BY ENGINEER			20
TOTALS			450

MILL ASPH CONC PVMT VARIABLE DEPTH

TOTAL 48,000 SY

FIELD ENGINEERS OFFICE TP 3

TOTAL 1 EA