DETAILED ESTIMATE

ITEM NO.	ITEMS	UNIT	QUANTITY
	ROADWAY		
150-1000	TRAFFIC CONTROL - NHS - M002 - 00(136) CONTRACT 1	LS	LUMP
150-9011	TRAFFIC CONTROL - WORKZONE LAW ENFORCEMENT (CONTRACTOR BIDS)	HR	2100
153-1300	FIELD ENGINEERS OFFICE TP 3	EA	1
400-3604	ASPH CONC 12.5 MM SMA, GP 2 ONLY, INCL POLYMER-MODIFIED BITUM MATL & H LIME	TN	3200
400-3624	ASPH CONC 12.5 MM PEM, GP 2 ONLY, INCL POLYMER-MODIFIED BITUM MATL & H LIME	TN	2600
402-3113	RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	800
413-1000	BITUM TACK COAT	GL	5200
432-5010	MILL ASPH CONC PVMT, VARIABLE DEPTH	SY	48000
456-2012	INDENTATION RUMBLE STRIPS - GROUND-IN-PLACE (CONTINUOUS)	GLM	2
622-1033	PRECAST CONCRETE MEDIAN BARRIER, METHOD 3	LF	350
622-1050	PRECAST CONCRETE MEDIAN BARRIER, METHOD 4	LF	250
632-0003	CHANGEABLE MESSAGE SIGN, PORTABLE, TYPE 3	EA	6
650-1200	IMPACT ATTENUATOR UNIT, (COMPRESSION CRASH CUSHION) TYPE T - 3-S-30	EA	1
	SIGNING & MARKING		
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	LF	5386
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	5280
653-1810	THERMOPLASTIC SOLID TRAF STRIPE, 10 IN, WHITE	LF	875
653-3501	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN, WHITE	GLF	22074
654-1003	RAISED PVMT MARKERS TP 3	EA	450
657-1054	PREFORMED PLASTIC SOLID PVMT MKG, 5 IN, WHITE, TP PB	LF	1391
657-3054	PREFORMED PLASTIC SKIP PVMT MKG, 5 IN, WHITE, TP PB	GLF	4222
657-6054	PREFORMED PLASTIC SOLID PVMT MKG, 5 IN, YELLOW, TP PB	LF	1096
	BRIDGE No. 1		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, BR NO-1, BENT NO-1	LF	142
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, BR NO-1, BENT NO-2	LF	142
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, BR NO-1, BENT NO-3	LF	142
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, BR NO-1, BENT NO-4	LF	142
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, BR NO-1, BENT NO-5	LF	142
501-3000	STR STEEL, BR NO - 1 (17606)	LS	LUMP
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONC	CY	117
505-1100	COMPOSITE STEEL GRID DECK WITH PRECAST CONCRETE SLAB	SF	12636
511-3000	SUPERSTR REINF STEEL, BR NO - 1 (14820)	LS	LUMP
519-0515	SURFACE PREPARATION	SY	3713
519-0520	COPOLYMER OVERLAY	SY	3713
521-1000	PATCHING CONCRETE BRIDGE DECK	SF	105
540-1202	REMOVAL OF PARTS OF EXISTING BRIDGE, BR NO - 1	LS	LUMP
	BRIDGE No. 2		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, BRIDGE NO-2, BENT NO-1	LF	68
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, BRIDGE NO-2, BENT NO-2	LF	68
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, BRIDGE NO-2, BENT NO-3	LF	68
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, BRIDGE NO-2, BENT NO-4	LF	68
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, BRIDGE NO-2, BENT NO-5	LF	68
500-0100	GROOVED CONCRETE	SY	1748
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONC	CY	56
511-3000	SUPERSTR REINF STEEL, BR NO -2 (6880)	LS	LUMP
519-0400	CONCRETE OVERLAY, PORTLAND CEMENT, VARB THK	SY	1748
521-1000	PATCHING CONCRETE BRIDGE DECK	SF	200
528-0750	EPOXY SEALING OF CONCRETE CRACKS	LF	2030
540-1202	REMOVAL OF PARTS OF EXISTING BRIDGE, BR NO -2	LS	LUMP
	BRIDGE No. 3		
443-1000	ELASTOMERIC PROFILE BRIDGE JOINT SEALS, BR NO -3, BENT NO-1	EA	1
443-1000	ELASTOMERIC PROFILE BRIDGE JOINT SEALS, BR NO -3, BENT NO-5	EA	1
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, BRIDGE NO-3, BENT NO-1	LF	222
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, BRIDGE NO-3, BENT NO-5	LF	225
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONC	CY	65
511-3000	SUPERSTR REINF STEEL, BR NO -3 (9580)	LS	LUMP
540-1202	REMOVAL OF PARTS OF EXISTING BRIDGE, BR NO -3	LS	LUMP
	BRIDGE No. 4		
443-1000	ELASTOMERIC PROFILE BRIDGE JOINT SEALS, BR NO - 4, BENT NO-1	EA	1
443-1000	ELASTOMERIC PROFILE BRIDGE JOINT SEALS, BR NO - 4, BENT NO-5	EA	1
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, BR NO-4, BENT NO-1	LF	202
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, BR NO-4, BENT NO-5	LF	202
501-3000	STR STEEL, BR NO - 4 (5500)	LS	LUMP
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONC	CY	119
505-1100	COMPOSITE STEEL GRID DECK WITH PRECAST CONCRETE SLAB	SF	13083
511-3000	SUPERSTR REINF STEEL, BR NO - 4 (13420)	LS	LUMP
519-0515	SURFACE PREPARATION	SY	4655
519-0520	COPOLYMER OVERLAY	SY	4655
521-1000	PATCHING CONCRETE BRIDGE DECK	SF	265
535-1105	PAINT EXIST STEEL STRUCTURE, BR ID - 089 - 00407D - 031.50C	LS	LUMP
540-1202	REMOVAL OF PARTS OF EXISTING BRIDGE, BR NO - 4	LS	LUMP