STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	NHS-M002-00(136) CT 2	5	24

DETAILED ESTIMATE

ITEM NO.	ITEMS	UNIT	QUANTITY
	ROADWAY		
150-1000	TRAFFIC CONTROL - NHS - M002 - 00(136) CONTRACT 2	LS	LUMP
150-9011	TRAFFIC CONTROL - WORKZONE LAW ENFORCEMENT (CONTRACTOR BIDS)	HR	1300
632-0003	CHANGEABLE MESSAGE SIGN, PORTABLE, TYPE 3	EA	4
	SIGNING & MARKING		
654-1003	RAISED PVMT MARKERS TP 3	EA	30
657-1054	PREFORMED PLASTIC SOLID PVMT MKG, 5 IN, WHITE, TP PB	LF	1833
657-3054	PREFORMED PLASTIC SKIP PVMT MKG, 5 IN, WHITE, TP PB	GLF	1940
657-6054	PREFORMED PLASTIC SOLID PVMT MKG, 5 IN, YELLOW, TP PB	LF	867
	BRIDGE No. 1		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,BRIDGE NO-1, BENT NO-1	LF	160
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, BRIDGE NO-1, BENT NO-5	LF	160
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONC	CY	24
511-3000	SUPERSTR REINF STEEL, BR NO - 1 (5080)	LS	LUMP
540-1202	REMOVAL OF PARTS OF EXISTING BRIDGE, BR NO -1	LS	LUMP
	BRIDGE No. 2		
447-1010	MODULAR EXPANSION JOINT, ABUTMENT 5-14, BR. NO.-2	EA	1
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONC	CY	6
511-3000	SUPERSTR REINF STEEL, BR NO -2 (610)	LS	LUMP
540-1202	REMOVAL OF PARTS OF EXISTING BRIDGE, BR NO -2	LS	LUMP
	BRIDGE No. 3		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, BR NO-3, BENT NO-1	LF	244
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, BR NO-3, BENT NO-2	LF	122
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, BR NO-3, BENT NO-5	LF	244
500-0100	GROOVED CONCRETE	SY	3830
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONC	CY	17
511-3000	SUPERSTR REINF STEEL, BR NO -3 (3600)	LS	LUMP
519-0400	CONCRETE OVERLAY, PORTLAND CEMENT, VARB THK	SY	3830
521-1000	PATCHING CONCRETE BRIDGE DECK	SF	230
528-0750	EPOXY SEALING OF CONCRETE CRACKS	LF	4450
540-1202	REMOVAL OF PARTS OF EXISTING BRIDGE, BR NO -3	LS	LUMP
	BRIDGE No. 4		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, BR NO-4, BENT NO-1	LF	63
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, BR NO-4, BENT NO-2	LF	63
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, BR NO-4, BENT NO-4	LF	63
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, BR NO-4, BENT NO-5	LF	63
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONC	CY	25
511-3000	SUPERSTR REINF STEEL, BR NO -4 (6400)	LS	LUMP
540-1202	REMOVAL OF PARTS OF EXISTING BRIDGE, BR NO -4	LS	LUMP
	BRIDGE No. 5		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, BR NO-5, BENT NO-1	LF	70
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, BR NO-5, BENT NO-2	LF	70
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, BR NO-5, BENT NO-3	LF	71
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, BR NO-5, BENT NO-4	LF	72
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, BR NO-5, BENT NO-5	LF	77
500-0100	GROOVED CONCRETE	SY	2000
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONC	CY	43
511-3000	SUPERSTR REINF STEEL, BR NO -5 (5700)	LS	LUMP
519-0400	CONCRETE OVERLAY, PORTLAND CEMENT, VARB THK	SY	2000
521-1000	PATCHING CONCRETE BRIDGE DECK	SF	140
528-0750	EPOXY SEALING OF CONCRETE CRACKS	LF	2320
540-1202	REMOVAL OF PARTS OF EXISTING BRIDGE, BR NO -5	LS	LUMP