STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	CSNHS-M002-00(662)	2	26

	INDEX
SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX & GENERAL NOTES
3	REVISION SUMMARY
4	SUMMARY OF QUANTITIES
5	DETAILED ESTIMATE
6-8	BRIDGE NO. I
9-11	BRIDGE NO. 2
12-15	BRIDGE NO. 3
16-17	BRIDGE NO. 4
18	CONSTR DETAILS - SUBBASES FOR APPROACH SLABS (M-2) (06-88)
19	CONSTR DETAILS - DETAILS OF PVM'T MARKING (T-IIB) (01-00)
20	CONSTR DETAILS - DETAILS OF RAISED PVM'T MARKER LOCATION (T-15B) (01-00)
21	CONSTR DETAILS - DETAILS OF RAISED PVM'T MARKERS (T-15C) (01-00)
22	GA STD 3901 - BAR BENDING DETAILS (08-69)
23	GA STD 9017M - REINF CONC APPROACH SLAB 30 FT LENGTH (WITH CONC BARRIER) (06-93)
24	GA STD 9037 - TYPICAL FILL DETAIL AT END OF BRIDGE (10-97)
25	GA STD 9100 - TRAFFIC CONTROL GEN. NOTES, STD. LEGEND, MISC. DETAILS (04-01)
26	GA STD 9106 - TRAFFIC CONTROL DETAIL FOR LANE CLOSURE (07-99)

26	TOTAL SHEETS

2/20/2008 |:37:22 PM \\GDOT-DSN|\GOPLOT\QCF\Road_Design_Tiff-|8x|2_to_Tiff-36x24.qcf wnguyen\Desktop\M002662\Construction\Cover-Index\M002662_0002.tif GO-RD-Plans-Review ...

GENERAL NOTES

- 1. THE CONTRACTOR SHALL BE REQUIRED TO USE THE ONE-CALL CENTER TELEPHONE NUMBER, I-800-282-7411, FOR THE PURPOSE OF COORDINATING THE MARKING OF UNDERGROUND UTILITIES AND BEFORE BEGINNING WORK WITHIN 10 FEET OF OVERHEAD CABLES. THE CONTRACTOR'S ATTENTION IS CALLED TO SUB-SECTION 105.06 "COOPERATION WITH UTILITIES".
- 2. ANY SIGN THAT MAY BE DISTURBED OR REMOVED DURING CONSTRUCTION OR THAT BECOMES
 TOO CLOSE TO THE NEW EDGE OF PAVEMENT SHALL BE RESET OR REPLACED PER GA. STANDARDS.
 NO SEPARATE PAYMENT WILL BE MADE FOR RESETTING OR REPLACING COST TO BE INCLUDED IN OVERALL BID.
- 3. NOTICE OF INTENT IS NOT REQUIRED.
- 4. ALL WORK SHALL BE COMPLETED WITHIN THE EXISTING RIGHT-OF-WAY.
- 5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL AND PROPERLY DISPOSING OF ALL UNSALVAGEABLE MATERIAL IN THIS PROJECT. THE CONTRACTOR SHALL NOT DEPOSIT ANY MATERIAL IN ANY WATERWAY. DISPOSAL SHALL BE INCLUDED IN THE PRICE BID FOR CONTRACT ITEMS.