STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	CSNHS-M002-00(783)	6	70

TRAFFIC CONTROL, TEMPORARY SAND LOADED ATTENUATOR MODULE (60 MPH ARRAY)	
EA	68
AS DIRECTED BY THE ENGINEER	

INDENTATION RUMBLE STRIPS GROUND-IN-PLACE (CONTINUOUS)	
GLM	2.0

GRADING COMPLETE - CSNHS-M002-00(783)	
LS	LUMP SUM

REMOVE CONC ROADWAY SLAB	
SY	1203

FULL DEPTH SLAB REPLACMENT	
CY	361

MILL ASPH CONC PVMT, VARIABLE IN DEPTH	
SY	15231

TRAFFIC CONTROL - CSNHS-M002-00(783)	
LS	LUMP SUM

TRAFFIC CONTROL - WORKZONE LAW ENFORCEMENT (CONTRACTOR BIDS)	
HR	200

CHANGEABLE MESSAGE SIGN, PORTABLE, TYPE 3	
EA	4

REMOVE EXISTING SOLID TRAF STRIPE, 5 IN, THERMOPLASTIC	
LM	2.62

REMOVE EXISTING SKIP TRAF STRIPE, 5 IN, THERMOPLASTIC	
GLM	2.62

REM RAISED PAVEMENT MARKER	
EA	173

ASPHALT-RUBBER JOINT AND CRACK SEAL, TP S	
LF	6500

REINF CONC APPROACH SLAB GA. STD. 9017M	
LOCATION	SY
BRIDGE NO. 1	
STA. 41+60.00 TO 41+90.00 NB	137
STA. 41+60.00 TO 41+90.00 SB	137
STA. 42+98.00 TO 43+28.00 NB	137
STA. 42+98.00 TO 43+28.00 NB	137
BRIDGE NO. 2	
STA. 21+67.00 TO 21+97.00 SB	228
STA. 23+94.00 TO 24+24.00 SB	242
BRIDGE NO. 3	
STA. 32+00.00 TO 32+30.00 NB	275
STA. 32+00.00 TO 32+30.00 SB	300
STA. 33+53.00 TO 33+83.00 NB	275
STA. 33+53.00 TO 33+83.00 SB	300
BRIDGE NO. 4	
STA. 31+51.43 TO 31+81.43 NB	115
STA. 31+51.43 TO 31+81.43 SB	115
STA. 33+09.43 TO 33+39.43 NB	115
STA. 33+09.43 TO 33+39.43 NB	115
TOTAL	2628

TEMPORARY BARRIER, METHOD NO. 1	
LOCATION	LIN. FT.
AS DIRECTED BY THE ENGINEER	1280
TOTAL	1280

RAISED PVMT MARKERS (EACH)		
LOCATION	REFLECTIVE-RAISED	
	CLEAR/RED	
	TYPE 3	
BRIDGE NO. 1		
ON 5" SKIP WHITE LINES	84	
BRIDGE NO. 2 & 3		
ON 5" SKIP WHITE LINES	100	
ON 10" SOLID WHITE LINES	26	
BRIDGE NO. 4		
ON 5" SKIP WHITE LINES	74	
TOTALS	284	

SURFACING QUANTITIES								
ITEMS	UNIT	BRIDGE NO. 1 STAGE 1	BRIDGE NO. 2 & 3 STAGE 1	BRIDGE NO. 4 STAGE 1	BRIDGE NO. 2 & 3 STAGE 2	BRIDGE NO. 4 STAGE 3	BRIDGE NO. 2 & 3 STAGE 3	TOTAL
REQUIRED PAVEMENT								
ASPH CONC 12.5 mm SMA, GP 2 ONLY, INCL POLYMER-MODIFIED BITUM MATL & H LIME	TN	-	-	-	-	927	-	927
ASPH CONC 12.5 MM PEM, GP 2 ONLY, INCL POLYMER-MODIFIED BITUM MATL & H LIME	TN	-	-	-	-	780	-	780
RECYCLED ASPH CONC LEVELING, INCL BITUM MATL & H LIME	TN	-	-	206	-	-	6	212
RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 2 ONLY, INCL BITUM MATL & H LIME	TN	270	29	202	328	345	-	1174
RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	361	39	269	437	-	-	1106
RECYCLED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	541	58	404	656	-	-	1659
GR AGGR BASE CRS, INCL MATL	TN	2213	239	1652	2785	-	167	7056
BITUM TACK COAT	GL	344	37	740	421	-	-	2480

TRAFFIC STRIPE				
DESCRIPTION	UNIT	BR. NO. 1	BR. NO. 2&3	BR. NO. 4
		THERMOPLASTIC	THERMOPLASTIC	THERMOPLASTIC
5 IN SOLID SINGLE WHITE	LF	-	431	2945
5 IN SOLID SINGLE YELLOW	LF	-	-	2945
5 IN SKIP SINGLE WHITE	GLM	-	-	1.12
10 IN SOLID SINGLE WHITE	LF	-	314	-

PREFORM PLASTIC PVMT MARKING TYPE PB				
DESCRIPTION	UNIT	BR. NO. 1 QUANTITY	BR. NO. 2 & 3 QUANTITY	BR. NO. 4 QUANTITY
PREFORMED PLASTIC SOLID PVMT MKG, 8 IN, CONTRAST (BLACK-YELLOW), TP PB	LM	0.59	0.72	0.05
PREFORMED PLASTIC SKIP PVMT MKG, 8 IN, CONTRAST BLACK-WHITE), TP PB	GLM	1.18	1.69	0.10
PREFORMED PLASTIC SOLID PVMT MKG, 8 IN, CONTRAST (BLACK-WHITE), TP PB	LM	0.59	0.72	0.05

Heath & Lineback Engineers
INCORPORATED
12 POWDER SPRINGS STREET, SUITE 240
MARIETTA, GEORGIA 30064

DATE	REVISIONS	DATE	REVISIONS
08-25-05	GENERAL REVISIONS		
10-27-05	GENERAL REVISIONS		
11-01-05	GENERAL REVISIONS		
01-23-06	GENERAL REVISIONS		
02-24-06	GENERAL REVISIONS		

GEORGIA
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

PROJECT: CSNHS-M002-00(783)
COUNTY: DOOLY/HOUSTON

DWG NO.6-01

J:/401B/401B783-1-75 BRIDGES/General/401B783Quant.dgn