# INDEX


| DRAWING NO. | SHEET NO. | DESCRIPTION |
|---|---|---|
| 1 | 1 | COVER SHEET |
| 2-01 | 2 | INDEX/GENERAL NOTES |
| 3-01 | 3 | REVISION SUMMARY |
| 5-01-5-02 | 4-5 | TYPICAL SECTIONS |
| 6-01-6-03 | 6-8 | SUMMARY OF QUANTITIES |
| 7-01 | 9 | QUANTITIES REQUIRED BY AMENDMENT SHEET |
| 8-01 | 10 | QUANTITIES REQUIRED ON CONSTRUCTION SHEET |
| 9-01 | 11 | DETAILED ESTIMATE |
| 13-01-13-06 | 12-17 | CONSTRUCTION PLAN SHEETS |
| 19-01-19-12 | 18-29 | CONSTRUCTION STAGING PLAN SHEETS |
| 26-01-26-06 | 30-35 | SIGNING AND MARKING PLANS |
| 35-01-35-06 | 36-41 | BRIDGE NO. 1 PLANS |
| 35-07-35-15 | 42-50 | BRIDGE NO. 2 PLANS |
| 40-01 | 51 | CONSTR DETAILS - GUARDRAIL IMPACT ATTENUATOR UNITS (G-11) (03-01) |
| 40-02 | 52 | CONSTR DETAILS - SUBBASES FOR APPROACH SLABS (M-2) (06-88) |
| 40-03 | 53 | CONSTR DETAILS - DETAILS OF PVM'T MARKING (T-11B) (01-00) |
| 40-04 | 54 | CONSTR DETAILS - MARKER LOCATION LIMITED ACCESS ROADWAY (T-15B) (01-00) |
| 40-05 | 55 | CONSTR DETAILS - DETAILS OF RAISED PVM'T MARKERS (T-15C) (01-00) |
| 41-01 | 56 | CONSTR DETAILS - DETAILS AND PLACEMENT OF RUMBLE STRIPS (T-19) (04-03) |
| 41-02 | 57 | GA STD 3054 - END POST AND END POST GUARDRAIL ATTACHMENT DETAIL (09-02) |
| 41-03 | 58 | GA STD 3901 - BAR BENDING DETAILS (08-69) |
| 41-04 | 59 | GA STD 4000W - GUARDRAIL WARRANT GUIDES (12-99) |
| 41-05 | 60 | GA STD 4010 - "W" BEAM GUARDRAIL (07-97) |
| 41-06 | 61 | GA STD 4011A - POST & O/S BLOCKS "W" & "T" BEAM GUARDRAIL (12-01) |
| 41-07 | 62 | GA STD 4012C - G-RAIL CONN TP 1 G-RAIL CONN AT BRIDGE/BARRIER (03-03) |
| 41-08 | 63 | GA STD 4051 - GUARDRAIL LOCATION DETAIL (10-97) |
| 41-09 | 64 | GA STD 4057 - LOCATION OF CONTINUOUS DOUBLE FACED GUARDRAIL IN MEDIAN |
| 41-10 | 65 | GA STD 4270 - STD. "T" BEAM GUARDRAIL (11-99) |
| 41-11 | 66 | GA STD 4960 - CONCRETE BARRIER - TEMPORARY (END TREATMENT OPTIONS) (02-01) |
| 41-12 | 67 | GA STD 4961 - DETAILS OF PRECAST TEMPORARY BARRIER (05-01) |
| 41-13 | 68 | GA STD 9017M - REINF CONC APPROACH SLAB WITH CONC BARRIER, 30 FT. LENGTH (08-99) |
| 41-14 | 69 | GA STD 9017-R - REINF CONC APPROACH SLAB WITH ASPHALT INLAY, 30 FT LENGTH (08-99) |
| 41-15 | 70 | GA STD 9100 - TRAFFIC CONTROL GEN. NOTES, STD. LEGEND, MISC. DETAILS (04-01) |
| 41-16 | 71 | GA STD 9106 - TRAFFIC CONTROL DETAIL FOR LANE CLOSURE (07-99) |
| | 71 | TOTAL SHEETS |


# GENERAL NOTES

1.

Georgia Department of Transportation

**Dig Safely.**

**1-800-282-7411**
**770-623-4344**

2. ANY SIGN THAT MAY BE DISTURBED OR REMOVED DURING CONSTRUCTION OR THAT BECOMES TOO CLOSE TO THE NEW EDGE OF PAVEMENT SHALL BE RESET OR REPLACED PER GA. STANDARDS. NO SEPARATE PAYMENT WILL BE MADE FOR RESETTING OR REPLACING COST TO BE INCLUDED IN OVERALL BID.

3. NOTICE OF INTENT IS NOT REQUIRED.

4. ALL WORK SHALL BE COMPLETED WITHIN THE EXISTING RIGHT-OF-WAY.

5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL AND PROPERLY DISPOSING OF ALL UNSALVAGEABLE MATERIAL IN THIS PROJECT. THE CONTRACTOR SHALL NOT DEPOSIT ANY MATERIAL IN ANY WATERWAY. DISPOSAL SHALL BE INCLUDED IN THE PRICE BID FOR CONTRACT ITEMS.

6. THE CONTRACTOR SHALL BE LIMITED TO WORKING ON ONE SITE AT A TIME. THE CONTRACTOR SHALL MOVE THE CHANGEABLE MESSAGE SIGNS FROM WORK SITE TO WORK SITE AS NECESSARY.

7. THE CONTRACTOR SHALL REPLACE IN KIND ANY VEGETATION OR LANDSCAPING DAMAGED DURING CONSTRUCTION. COST SHALL BE INCLUDED IN OVERALL BID PRICE.

8. THE COST FOR GUARDRAIL REMOVAL AND ANY GRADING REQUIRED FOR NEW GUARDRAIL SHALL BE INCLUDED IN THE LUMP SUM PRICE FOR GRADING COMPLETE.

9. THE CONTRACTOR SHALL INCLUDE ALL LANE SHIFTS AND LANE CLOSURES THAT OCCUR OUTSIDE THE PROJECT LIMITS IN THE BID SUBMITTED FOR TRAFFIC CONTROL.

10. THE CONTRACTOR SHALL ERADICATE ALL CONFLICTING STRIPING. COST TO BE INCLUDED IN THE BID SUBMITTED FOR TRAFFIC CONTROL.

11. ALL TEMPORARY STRIPING SHALL BE REMOVABLE REFLECTORIZED TAPE.

J.B. TRIMBLE, INC.
2550 Heritage CT, SE,
Suite 250
Atlanta, GA 30339

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: MAINTENANCE

**INDEX\GENERAL NOTES**

DRAWING No. 2-01

GPLH