TRAFFIC CONTROL CSNHS-M002-00(785)	
TOTAL	LUMP SUM

INDENTATION RUMBLE STRIPS GROUND IN PLACE (CONTINUOUS)	
TOTAL	3.0 GLM

TRAFFIC CONTROL - WORKZONE LAW ENFORCEMENT (CONTRACTOR BIDS)	
TOTAL	500 HR

GRADING COMPLETE CSNHS-M002-00(785)	
TOTAL	LUMP SUM

TRAFFIC CONTROL, PORTABLE IMPACT ATTENUATOR	
TOTAL	2 EA.

TO BE USED AS DIRECTED BY THE ENGINEER

CHANGEABLE MESSAGE SIGN, PORTABLE, TYPE 3	
TOTAL	4

SURFACING QUANTITIES

ITEMS	UNIT	BRIDGE NO. 1 MAINLINE STAGE 1	BRIDGE NO. 1 MAINLINE STAGE 2	BRIDGE NO. 1 MAINLINE FINISHING	BRIDGE NO. 1 SHOULDER STAGE 1	BRIDGE NO. 1 SHOULDER STAGE 2	BRIDGE NO. 1 SHOULDER FINISHING	BRIDGE NO. 2 MAINLINE STAGE 1	BRIDGE NO. 2 MAINLINE STAGE 2	BRIDGE NO. 2 MAINLINE FINISHING	BRIDGE NO. 2 SHOULDER STAGE 1	BRIDGE NO. 2 SHOULDER STAGE 2	BRIDGE NO. 2 SHOULDER FINISHING	AS DIRECTED BY ENGINEER	TOTALS
ASPH CONC 12.5 MM SMA, GP 2 ONLY, INCL POLYMER-MODIFIED BITUM MATL & H LIME	TN			1352										148	1500
ASPH CONC 12.5 MM PEM, GP2 ONLY, INCL POLYMER-MODIFIED BITUM MATL & H LIME	TN			1106			93							101	1300
RECYCLED ASPH CONC LEVELING, INCL BITUM MATL & H LIME	TN	246	246		310	320					416			162	1700
RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN			96			762					508		130	1400
BITUM TACK COAT	GL	983	983	1966	274	281	636				177	370		539	5800
MILL ASPH CONC PVMT, VARIABLE DEPTH	SY			16376			9229					6156		539	32300

J.B. TRIMBLE, INC.
2550 Heritage CT, SE,
Suite 250
Atlanta, GA 30339

REVISION DATES		
06-26-06		

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: MAINTENANCE

SUMMARY OF QUANTITIES

DRAWING No. 6-01

GPLM