TRAFFIC STRIPE

DESCRIPTION	UNIT	QUANTITY PREFORMED	QUANTITY THERMOPLASTIC
STA. 300+00 - 325+00			
5" SOLID WHITE	LIN FEET		4050
5" SOLID YELLOW	LIN FEET		4050
5" SKIP WHITE	GLM		1.534
8" SOLID BLACK-WHITE	LIN FEET	300	
8" SOLID BLACK-YELLOW	LIN FEET	300	
8" SKIP BLACK-WHITE	GR LIN FT	600	
STA. 232+10 - 233+93			
5" SOLID WHITE	LIN FEET		366
5" SOLID YELLOW	LIN FEET		366
5" SKIP WHITE	GLM		0.138
8" SOLID BLACK-WHITE	LIN FEET		
8" SOLID BLACK-YELLOW	LIN FEET		
8" SKIP BLACK-WHITE	GR LIN FT		
TOTALS			
5" SOLID WHITE	LIN FEET		4416
5" SOLID YELLOW	LIN FEET		4416
5" SKIP WHITE	GLM		1.672
8" SOLID BLACK-WHITE	LIN FEET	300	
8" SOLID BLACK-YELLOW	LIN FEET	300	
8" SKIP BLACK-WHITE	GR LIN FT	600	

PAVEMENT MARKERS (EACH)

LOCATION	REFLECTIVE-RAISED YELLOW TYPE 1	REFLECTIVE-RAISED CLEAR TYPE 2	REFLECTIVE-RAISED CLEAR/RED TYPE 3
MAINLINE			
STA 303+50 - 325+00 LT - 5" SKIP WHITE			56
STA 300+00 - 322+00 RT - 5" SKIP WHITE			58
STA 232+10 - 233+93 LT - 5" SKIP WHITE			8
STA 232+10 - 233+93 RT - 5" SKIP WHITE			8
AS DIRECTED BY ENGINEER			10
TOTALS			140

MULCH

AS DIRECTED BY THE ENGINEER	15 TONS
TOTAL	15 TONS

GRASSING

ITEM	UNIT	QUANTITY	AGRICULTURAL LIME TON	LIQUID LIME GAL	FERTILIZER MIXED GRADE TON	FERTILIZER NITROGEN CONTENT LB
PERMANENT GRASSING	AC	1	2	3	1	50
TEMPORARY GRASSING	AC	1			1	
TOTAL			2	3	2	50

REINFORCED CONCRETE APPROACH SLAB GA. STD. 9017-M

LOCATION	REINFORCED CONCRETE APPROACH SLAB INCL SLOPED EDGE & SUBBASE SY	CONCRETE SPILLWAY GA. STD. 9017-J EACH	15" SLOPE DRAIN PIPE LIN. FT	CLASS B CONCRETE APRON CU. YDS
311+68.00 - 311+98.00	440			
313+48.00 - 311+78.00	440			
TOTALS	880			

NOTE: MODIFY GA STD 9017-M TO MATCH THE INLAY CONSTRUCTION OF GA STD 9017-R. COST SHALL BE INCLUDED IN THE PRICE BID FOR REINF. CONC. APPROACH SLAB.

TEMPORARY SILT FENCE TYPE C

TOTAL 1500 LIN FT.

TO BE USED AS DIRECTED BY ENGINEER

MAINTENANCE OF TEMPORARY SILT FENCE TYPE C

TOTAL 1500 LIN FT.

J.B. TRIMBLE, INC.
2550 Heritage CT, SE,
Suite 250
Atlanta, GA 30339

REVISION DATES
1-24-07

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: MAINTENANCE

SUMMARY OF QUANTITIES

DRAWING No. 6-03

GPLM