DETAILED ESTIMATE

ITEM NO.	ITEMS	UNIT	QUANTITY
	ROADWAY		
150-1000	TRAFFIC CONTROL - PROJECT NO CSNHS-M002-00(785)	LS	LUMP
150-5010	TRAFFIC CONTROL, PORTABLE IMPACT ATTENUATOR	EA	2
150-9011	TRAFFIC CONTROL - WORKZONE LAW ENFORCEMENT (CONTRACTOR BIDS)	HR	500
163-0232	TEMPORARY GRASSING	AC	1
163-0240	MULCH	TN	15
165-0030	MAINTENANCE OF TEMPORARY SILT FENCE, TP C	LF	1500
171-0030	TEMPORARY SILT FENCE, TYPE C	LF	1500
210-0100	GRADING COMPLETE - PROJECT NO CSNHS-M002-00(785)	LS	LUMP
400-3604	ASPH CONC 12.5 MM SMA, GP 2 ONLY, INCL POLYMER-MODIFIED BITUM MATL & H LIME	TN	1500
400-3624	ASPH CONC 12.5 MM PEM, GP 2 ONLY, INCL POLYMER-MODIFIED BITUM MATL & H LIME	TN	1300
402-1812	RECYCLED ASPH CONC LEVELING, INCL BITUM MATL & H LIME	TN	1700
402-3113	RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	1400
413-1000	BITUM TACK COAT	GL	5800
432-5010	MILL ASPH CONC PVMT, VARIABLE DEPTH	SY	32300
433-1000	REINF CONC APPROACH SLAB	SY	880
456-2012	INDENTATION RUMBLE STRIPS - GROUND IN PLACE (CONTINUOUS)	GLM	3.0
620-0100	TEMPORARY BARRIER, METHOD NO. 1	LF	2620
632-0003	CHANGEABLE MESSAGE SIGN, PORTABLE, TYPE 3	EA	4
641-2200	DBL FACED GUARDRAIL, TP W	LF	1400
700-6910	PERMANENT GRASSING	AC	1
700-7000	AGRICULTURAL LIME	TN	2
700-7010	LIQUID LIME	GL	3
700-8000	FERTILIZER MIXED GRADE	TN	2
700-8100	FERTILIZER NITROGEN CONTENT	LB	50
	SIGNING & MARKING		
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	LF	4416
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	4416
653-4501	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN, WHITE	GLM	1.672
654-1003	RAISED PVMT MARKERS TP 3	EA	140
657-1085	PREFORMED PLASTIC SOLID PVMT MKG, 8 IN, CONTRAST (BLACK-WHITE), TP PB	LF	300
657-3085	PREFORMED PLASTIC SKIP PVMT MKG, 8 IN, CONTRAST (BLACK-WHITE), TP PB	GLF	600
657-6085	PREFORMED PLASTIC SOLID PVMT MKG, 8 IN, CONTRAST (BLACK-YELLOW), TP PB	LF	300
	BRIDGE NO. 1		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO-1, BENT NO-1	LF	138
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO-1, BENT NO-2	LF	138
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO-1, BENT NO-3	LF	138
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO-1, BENT NO-4	LF	138
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO-1, BENT NO-5	LF	138
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO-1, BENT NO-6	LF	138
500-0100	GROOVED CONCRETE	SY	2100
501-2100	STR. STEEL, SWAYBRACING	LB	1800
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONC	CY	59
511-3000	SUPERSTR REINF STEEL, BR NO - 1 (12300)	LS	LUMP
519-0400	CONCRETE OVERLAY, PORTLAND CEMENT, VARB THK	SY	2160
528-0750	EPOXY SEALING OF CONCRETE CRACKS	LF	2500
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO - 1	LS	LUMP
547-2012	PILE ENCASEMENT, 12 IN PILE	LF	360
	BRIDGE NO. 2		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO-2, BENT NO-1	LF	134
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO-2, BENT NO-2	LF	134
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO-2, BENT NO-3	LF	134
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE, POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO-2, BENT NO-4	LF	134
500-2100	CONCRETE BARRIER	LF	353
501-3000	STR. STEEL, BR NO-2 (20400)	LS	LUMP
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONC	CY	27
505-1100	COMPOSITE STEEL GRID DECK WITH PRECAST CONCRETE SLAB	SF	13810
511-3000	SUPERSTR REINF STEEL, BR NO - 2 (15600)	LS	LUMP
519-0515	SURFACE PREPARATION	SY	2660
519-0520	COPOLYMER OVERLAY	SY	2660
521-3000	PATCHING CONCRETE BRIDGE	SF	100
528-0750	EPOXY SEALING OF CONCRETE CRACKS	LF	100
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO - 2	LS	LUMP
620-0200	TEMPORARY BARRIER, METHOD NO. 2	LF	440

JBT J.B. TRIMBLE, INC.
2550 Heritage CT, SE,
Suite 250
Atlanta, GA 30339

REVISION DATES
06-26-06
08-17-06
01-24-07

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: MAINTENANCE
DETAILED ESTIMATE

DRAWING No. 9-01